

ELMIRA/CORNING RGNL (ELM)(KELM) 6 NW UTC-5(-4DT) N42°09.59' W76°53.50'
 955 B TPA—See Remarks LRA ARFF Index—See Remarks NOTAM FILE ELM

NEW YORK
 H-10H, 12I, L-30J, 32F
 IAP, AD

RWY 06-24: H8001X150 (ASPH-GRVD) S-80, D-121, 2S-154,
 2D-200 PCN 50 F/C/X/T HIRL CL
RWY 06: MALSR. REIL. VASI(V4L)—GA 3.0° TCH 51'. RVR-TMR Thld
 dsplcd 600'. Tree.
RWY 24: MALSR. REIL. PAPI(P4L)—GA 3.0° TCH 52'. RVR-TMR Thld
 dsplcd 202'. Tree.
RWY 10-28: H5404X150 (ASPH-GRVD) S-57, D-90, 2S-114,
 2D-150 PCN 17 F/C/X/T MIRL
RWY 10: Trees.
RWY 28: PAPI(P4L)—GA 3.0° TCH 40'. Thld dsplcd 402'. Pole.
RWY 05-23: 2016X150 (TURF)

RUNWAY DECLARED DISTANCE INFORMATION

RWY 05: TORA-2017	TODA-2017	ASDA-2017	LDA-2017
RWY 06: TORA-8001	TODA-8001	ASDA-8001	LDA-7401
RWY 10: TORA-5404	TODA-5404	ASDA-5004	LDA-5004
RWY 23: TORA-2017	TODA-2017	ASDA-2017	LDA-2017
RWY 24: TORA-8001	TODA-8001	ASDA-8001	LDA-7799
RWY 28: TORA-5404	TODA-5404	ASDA-5404	LDA-5002

ARRESTING GEAR/SYSTEM

RWY 06: EMAS

SERVICE: S4 FUEL 100LL, JET A OX 4 LGT When twr clsd ACTIVATE MALSR Rwy 06 and 24, centerline lgts Rwy 06-24, HIRL Rwy 06-24, twy lights on Twy A, Twy A1, Twy A2, Twy A3, Twy B, Twy D, Twy J, Twy L, Twy T and Twy C north of Rwy 06-24—CTAF. When twr clsd MIRL Rwy 10-28; twy lights on Twy E, Twy G, Twy H and Twy C south of Rwy 06-24 not avbl. PAPI Rwy 24 unusable byd 9° rgt of centerline.

AIRPORT REMARKS: Attended continuously. Extensive glider activity on and infov arpt. Birds and deer on and infov arpt. Blimp activity rqr PPR, ctc arpt management at 607-426-5621. Class I, ARFF Index B. ARFF index C equipment coverage is avbl upon req ctc arpt management at 607-426-5621. TPA—2500(1545) reciprocating eng, 3000(2045) Turboprop/Jet. Rwy 10 opr prohibited for acft with apch speeds greater than or equal to 121 knots and/or wingspans greater than or equal to 118'. Acft with wing spans greater than 93' should use extreme care when taxiing on Twy T adjacent to aprons. Rwy 05-23 (southeast of Rwy 06-24) unmarked seasonal use turf rwy clsd 1 Dec through 30 Apr. For land side access from apron when FBO clsd ctc ELM arpt attendant at 607-426-5621. Rwy 05-23 marked with asph L corner markers. Winter deicing on glycol apron only. Cold temperature airport. Altitude correction required at or below -22C. PAPI Twy H, Twy J, and Twy L limited to design Group II acft. Ldg fee for all non based acft. Terminal ramp is uncontrolled. Do not call for push/power back. Advise ground control when ready to taxi for dep. Twy T btn Twy L and Twy D non-movement area.

AIRPORT MANAGER: 607-739-5621

WEATHER DATA SOURCES: ASOS (607) 796-0065

COMMUNICATIONS: CTAF 121.1 ATIS 125.475 UNICOM 122.95

RCO 122.2 (BUFFALO RADIO)

Ⓡ **ELMIRA APP/DEP CON** 128.425 (1100-0500Z‡)

Ⓡ **NEW YORK CENTER APP/DEP CON** 133.35 (0500-1100Z‡)

ELMIRA TOWER 121.1 (1100-0500Z‡) GND CON 121.9 CLNC DEL 121.9

CLEARANCE DELIVERY PHONE: For CD if una to ctc on FSS freq, ctc New York ARTCC at 631-468-1425.

AIRSPACE: CLASS D svc 1100-0500Z‡; other times CLASS E.

TRSA svc ctc APP CON (within 15 NM)

RADIO AIDS TO NAVIGATION: NOTAM FILE ELM.

(L) (L) VORW/DME 109.65 ULW Chan 33(Y) N42°05.65' W77°01.49' 068° 7.1 NM to fld. 1631/12W.

VOR unusable:

Blw 10,000'

ALPINE NDB (MHW) 245 ALP N42°14.32' W76°45.84' 242° 7.4 NM to fld. 1287/12W.

ILS 109.1 I-UEK Rwy 06. Class IA. Unmonitored when twr clsd.

ILS 109.1 I-ELM Rwy 24. Class IB. Unmonitored when twr clsd.

COMM/NAV/WEATHER REMARKS: For Clnc Del when twr clsd ctc Buffalo Radio on 122.2.

