

APP CRS 186°	Rwy Idg 10000 TDZE 889 Apt Elev 896
------------------------	--

RNAV (RNP) Z RWY 18L
CINCINNATI/NORTHERN KENTUCKY INTL (CVG)

RNP AR APCH - GPS.

T Simultaneous approach authorized. For uncompensated Baro-VNAV systems, procedure NA below -16°C or above 47°C. For inop ALS, increase RNP 0.25 all Cats visibility to RVR 6000. RNP 0.30 all Cats visibility to 1¾ SM.

MALSR



MISSED APPROACH: Climb to 3000 on track 186° to LAPER and on track 136° to FLM VOR/DME and hold.


D-ATIS	CINCINNATI APP CON
ARR DEP	119.7 363.15 (090°-269°)
134.375 135.3	123.875 363.15 (270°-089°)

CINCINNATI TOWER
118.975 360.85 (RWY 18L/36R)
118.3 (RWYS 18C/36C, 09/27)
133.325 (RWY 18R/36L)


GND CON
121.7

CLNC DEL
127.175

CPDLC



ELEV 896		TDZE 889
----------	---	----------



HIRL all Rwys
TDZ/CL all Rwys except 27

3000 ↑	tr 186° ✦	tr 136° ✦	FLM ◻	VGS1 and RNAV glidepath not coincident (VGS1 Angle 3.00/TCH 71).			
CATEGORY	A		B		C		D
RNP 0.25 DA	1283/35		394 (400-½)				
RNP 0.30 DA	1472-1¼		583 (600-1¼)				
AUTHORIZATION REQUIRED							

AUTHORIZATION REQUIRED