

APP CRS
201°

Rwy Ldg
TDZE
578

Apt Elev
599


RNP AR APCH - GPS. Authorization required. From JAQQE, FLMBE, IICKS, POORR, or KLOPR: RF.

MALSF

MISSED APPROACH: Climb to 1200 then climbing right turn to 4000 direct BEVEE and hold.

Simultaneous approach authorized with Rwy 20L. For uncompensated Baro-VNAV systems, LNAV/VNAV NA below -10°C or above 54°C. Inop table does not apply.

D-ATIS 135.1	NASHVILLE APP CON 118.4 360.7 (030°-196°) 119.35 372.0 (197°-029°)	NASHVILLE TOWER 118.6 257.8	GND CON 121.9 348.6
------------------------	--	---------------------------------------	-------------------------------



ELEV 599

D

TDZE 578

1200

4000

BEVEE

VGSI and RNAV glidepath not coincident (VGSI Angle 3.00°/TCH 79°).

See planview for multiple IF locations.

RW20R

OPERY

AKUFF

GP 3.00°

TCH 60

CATEGORY	A	B	C	D
RNP 0.13 DA		927/40	349 (400-¾)	
RNP 0.30 DA		1042/60	464 (500-1¼)	

HIRL all Rwys

TDZL/RCLS Rwys 2L and 2R

REIL Rwys 13, 20C, and 31

AUTHORIZATION REQUIRED