

APP CRS
133°

Rwly Ldg
TDZE
485

Apt Elev
487

RNAV (RNP) W RWY 13L

DALLAS LOVE FLD (DAL)


RNP AR APCH. RF required.

Simultaneous approach authorized. For uncompensated Baro-VNAV systems, procedure NA below -6°C or above 54°C. For inop ALS, increase RNP 0.11 all Cats visibility to RVR 4500.

MALSR

MISSED APPROACH: Climb to 3000 direct DATLE and on track 115° to DUMPY and hold.

D-ATIS 120.15	LONE STAR APP CON 124.3 282.275 (N) 125.2 343.65 (S)	LOVE TOWER 123.7 239.3	GND CON 121.75 348.6
-------------------------	--	----------------------------------	--------------------------------



ELEV **487** **D** TDZE **485**

TDZL/RCLS Rwws 13L and 31L
HIRL Rwws 13L-31R, and 13R-31L

See planview for multiple IF locations.

HEXOV	KUMTE	CEGEP	DATLE	DUMPY
2100	1600	1212	3000	3000
GP 3.00°	1600	1212	tr 115°	tr 115°
TCH 40	1.7 NM	1.2 NM	2.2 NM	
CATEGORY	A	B	C	D
RNP 0.11 DA	754/24 269 (300-½)			
RNP 0.30 DA	846/40 361 (400-¾)			
AUTHORIZATION REQUIRED				