IFR TAKEOFF MINIMUMS, (OBSTACLE) DEPARTURE PROCEDURES, AND DIVERSE VECTOR AREA (RADAR VECTORS)

Civil Airports and Selected Military Airports

ALL USERS: Airports that have Departure Procedures (DPs) designed specifically to assist pilots in avoiding obstacles during the climb to the minimum enroute altitude, and/or airports that have civil IFR takeoff minimums other than standard, are listed below. Takeoff Minimums and Departure Procedures apply to all runways unless otherwise specified. An entry may also be listed that contains only Takeoff Obstacle Notes. Altitudes, unless otherwise indicated, are minimum altitudes in MSL.

The FAA redefined the initial climb area (ICA) criteria used to evaluate and identify the obstacles that penetrate the 40:1 OCS. The takeoff obstacle notes are published in a different manner and an additional minimums option is added for the departure. To ensure the pilot knows which evaluation was accomplished, the charting will be different by bolding certain headers and runway information to indicate the new ICA criteria has been used as indicated in (1) and (2) below. Until the FAA can amend all departures, the legacy obstacle notes will still be published.

(1) For textual departures, the headers Takeoff Minimums, Departure Procedure, and Takeoff Obstacle Notes will be bolded and underlined. The specific runway entries under each header will continue to be bolded.

(2) For graphic departure procedures, the headers Takeoff Minimums and Takeoff Obstacle Notes will be bolded and continue to be underlined. The specific runway entries for these headers will be bolded. In the Departure Route Description section of the graphic departure, the heading will be bolded and underlined, and the runway information will be bolded.

DPs specifically designed for obstacle avoidance are referred to as Obstacle Departure Procedures (ODPs) and are textually described below, or published separately as a graphic procedure. If the ODP is published as a graphic procedure, its name will be listed below, and it can be found in either this volume (civil), or the applicable military volume, as appropriate. Users will recognize graphic obstacle DPs by the term "(OBSTACLE)" included in the procedure title; e.g., TETON TWO (OBSTACLE). If not specifically assigned an ODP, SID, or RADAR vector as part of an IFR clearance, an ODP may be required to be flown for obstacle clearance, even though not specifically stated in the IFR clearance. When doing so in this manner, ATC should be informed when the ODP being used contains a specified route to be flown, restrictions before turning, and/or altitude restrictions.

Some ODPs, which are established solely for obstacle avoidance, require a climb in visual conditions to cross the airport, a fix, or a NAVAID in a specified direction, at or above a specified altitude. These procedures are called Visual Climb Over Airport (VCOA). To ensure safe and efficient operations, the pilot must notify ATC of their intent to fly the VCOA when requesting their IFR clearance.

At some locations where an ODP has been established, a diverse vector area (DVA) may be created to allow RADAR vectors to be used in lieu of an ODP. DVA information will state that headings will be as assigned by ATC and climb gradients, when applicable, will be published immediately following the specified departure procedure.

Graphic DPs designed by ATC to standardize traffic flows, ensure aircraft separation and enhance capacity are referred to as "Standard Instrument Departures (SIDs)". SIDs also provide obstacle clearance and are published under the appropriate airport section. ATC clearance must be received prior to flying a SID.

CIVIL USERS NOTE: Title 14 Code of Federal Regulations Part 91 prescribes standard takeoff rules and establishes takeoff minimums for certain operators as follows: (1) For aircraft, other than helicopters, having two engines or less – one statute mile visibility. (2) For aircraft having more than two engines – one-half statute mile visibility. (3) For helicopters – one-half statute mile visibility. These standard minima apply in the absence of any different minima listed below.

MILITARY USERS NOTE: Civil (nonstandard) takeoff minima are published below. For military takeoff minima, refer to appropriate service directives.

AKRON, OH

AKRON-CANTON RGNL (CAK)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 6 18NOV10 (10322) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 1, multiple trees beginning 2756' from DER, 447' left of centerline, up to 116' AGL/1316' MSL.
Power lines beginning 3215' from DER, left and right of centerline, up to 80' AGL/1289' MSL.
Rwy 5, multiple trees beginning 840' from DER, 550' right of centerline, up to 116' AGL/1336' MSL.
Tree 577' from DER, 561' left of centerline, 46' AGL/1256' MSL.
Rwy 19, trees beginning 1998' from DER, 817' left of centerline, up to 100' AGL/1290' MSL.

AKRON, OH (CON'T)

AKRON FULTON INTL (AKR)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2A 08SEP22 (22307) (FAA)

TAKEOFF MINIMUMS:

Rwy 7, 300-1½ or std w/min climb of 230' per NM to 1400 or alternatively, with std takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1800' prior to DER.

Rwy 25, 300-1⅝ or std w/min climb of 705' per NM to 1500.

DEPARTURE PROCEDURE:

Rwy 25, climb on heading 249° to 2600 before turning right.

TAKEOFF OBSTACLE NOTES:

Rwy 7, terrain 45' from DER, 257' right of centerline, 1073' MSL.
Vehicles on road 62' from DER, 460' right of centerline, 1090' MSL.
Vehicles on road 90' from DER, 358' right of centerline, 1091' MSL.
Vehicles on road beginning 179' from DER, 397' right of centerline, up to 1095' MSL.
Terrain 196' from DER, 493' left of centerline, 1068' MSL.
Fence 251' from DER, 544' left of centerline, 7' AGL/1077' MSL.
Tree, terrain, vehicles on road, vegetation, fence beginning 295' from DER, on centerline, up to 1126' MSL.
Fence 372' from DER, 490' left of centerline, 8' AGL/1080' MSL.
Vehicles on road, terrain beginning 397' from DER, 317' left of centerline, up to 1088' MSL.
Pole, terrain, vehicles on road beginning 476' from DER, 104' left of centerline, up to 34' AGL/1106' MSL.
Tree, terrain, vehicles on road beginning 566' from DER, 7' left of centerline, up to 1134' MSL.
Pole, terrain beginning 572' from DER, 114' right of centerline, up to 1127' MSL.
Poles, terrain, vehicles on road beginning 654' from DER, 1' right of centerline, up to 32' AGL/1141' MSL.
Trees, vehicles on road, poles, terrain, building, fence, sign beginning 692' from DER, 75' left of centerline, up to 1171' MSL.
Tree, vehicles on road beginning 905' from DER, 256' right of centerline, up to 1162' MSL.
Trees, vehicles on road, terrain, poles, buildings beginning 944' from DER, 14' left of centerline, up to 1177' MSL.
Trees, vehicles on road, terrain, fence, pole, building beginning 985' from DER, 2' right of centerline, up to 1175' MSL.
Trees, vehicles on road, sign, building, terrain beginning 1273' from DER, 13' left of centerline, up to 1178' MSL.
Trees, terrain, poles, fence, vehicles on road, building beginning 1432' from DER, 11' left of centerline, up to 1192' MSL.
Tree, vehicles on road, terrain, fence, pole beginning 1459' from DER, 1' right of centerline, up to 1181' MSL.
Trees, buildings, vehicles on road, poles, fence beginning 1857' from DER, 18' right of centerline, up to 1192' MSL.
Trees, terrain, fence, vehicles on road, buildings, poles, vegetation beginning 1887' from DER, 6' left of centerline, up to 1198' MSL.
Trees, vehicles on road, buildings, poles beginning 2277' from DER, 4' right of centerline, up to 1195' MSL.
Trees, buildings, poles beginning 2727' from DER, 1' right of centerline, up to 1197' MSL.
Building 6043' from DER, 460' left of centerline, 123' AGL/1213' MSL.
Tree 1.1 NM from DER, 701' right of centerline, 1247' MSL.
Trees beginning 1.1 NM from DER, 200' right of centerline, up to 1258' MSL.
Tree 1.2 NM from DER, 301' right of centerline, 1254' MSL.

Rwy 25, tree 53' from DER, 497' right of centerline, 1091' MSL.
Vehicles on road, terrain beginning 66' from DER, 69' right of centerline, up to 1092' MSL.
Tree, vehicles on road, terrain beginning 100' from DER, 3' right of centerline, up to 1101' MSL.
Vehicles on road 133' from DER, 33' left of centerline, 1093' MSL.
Trees, fence, terrain beginning 170' from DER, 292' right of centerline, up to 1119' MSL.
Vehicles on road beginning 199' from DER, 130' left of centerline, up to 1094' MSL.
Trees, terrain beginning 215' from DER, 235' right of centerline, up to 1124' MSL.
Vehicles on road beginning 264' from DER, 225' left of centerline, up to 1095' MSL.
Vehicles on road 375' from DER, 403' left of centerline, 1096' MSL.
Tree 503' from DER, 541' left of centerline, 1108' MSL.
Tree 573' from DER, 473' right of centerline, 1142' MSL.
Trees, terrain, vehicles on road, fence, NAVAID, vegetation beginning 594' from DER, 23' right of centerline, up to 1165' MSL.
Trees beginning 614' from DER, 493' left of centerline, up to 1122' MSL.
Trees, fence, vehicles on road, vegetation, tank beginning 687' from DER, 3' left of centerline, up to 1156' MSL.
Trees, vegetation, vehicles on road beginning 1405' from DER, on centerline, up to 1166' MSL.
Trees, vegetation beginning 1590' from DER, 103' right of centerline, up to 1168' MSL.
Trees, vegetation beginning 1612' from DER, 8' right of centerline, up to 1192' MSL.
Pole, tree, vehicles on road, vegetation beginning 1671' from DER, 61' left of centerline, up to 37' AGL/1157' MSL.
Trees, vegetation beginning 1679' from DER, 12' right of centerline, up to 1208' MSL.
Trees, vegetation, poles beginning 1737' from DER, 52' left of centerline, up to 1172' MSL.
Trees, vegetation, terrain, fence, building beginning 1745' from DER, 66' right of centerline, up to 1221' MSL.
Tree 1785' from DER, 406' left of centerline, 1176' MSL.
Tree, vegetation, terrain, poles, fence, vehicles on road, building beginning 1786' from DER, 6' left of centerline, up to 1185' MSL.
Trees, terrain, vegetation, vehicles on road, buildings, poles, fence, signs, tower beginning 1948' from DER, 6' right of centerline, up to 64' AGL/1228' MSL.
Tree, vegetation, terrain, pole beginning 2056' from DER, 76' left of centerline, up to 1215' MSL.
Trees, vegetation, vehicles on road, terrain, pole beginning 2103' from DER, 17' left of centerline, up to 1225' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026
29 OCT 2026 to 26 NOV 2026

26190

AKRON, OH (CON'T)

AKRON FULTON INTL (AKR) (CON'T)

Rwy 25 (CON'T), trees, buildings, vegetation, terrain, vehicles on road, poles fence, stack, tank, sign beginning 2349' from DER, 6' left of centerline, up to 1227' MSL.
Antenna 1.3 NM from DER, 440' left of centerline, 307' AGL/1339' MSL.
Tower 1.3 NM from DER, 215' left of centerline, 305' AGL/1343' MSL.

ANDERSON, IN

ANDERSON RGNL (AID)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT1 10MAR11 (25107) (FAA)

TAKEOFF MINIMUMS:

Rwy 30, 300-1¼ or std w/min climb of 220' per NM to 1200, or alternatively, with std takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1500' prior to DER.

TAKEOFF OBSTACLE NOTES:

Rwy 12, pole and trees beginning 509' from DER, 519' left of centerline, up to 100' AGL/1005' MSL.
Trees beginning 1947' from DER, 446' right of centerline, up to 100' AGL/1010' MSL.
Railroad 944' from DER, left and right of centerline, up to 23' AGL/945' MSL.
Rwy 18, trees beginning 437' from DER, 169' left of centerline, up to 100' AGL/951' MSL.
Trees beginning 440' from DER, 159' right of centerline, up to 100' AGL/1015' MSL.
Vehicles on road beginning 373' from DER, left and right of centerline, up to 15' AGL/922' MSL.
Terrain 417' from DER, 299' left of centerline, 0' AGL/918' MSL.
Rwy 30, tower and trees beginning 1516' from DER, 519' left of centerline, up to 161' AGL/1057' MSL.
Trees beginning 389' from DER, 344' right of centerline, up to 100' AGL/1009' MSL.
Vehicles on road beginning 152' from DER, left and right of centerline, up to 15' AGL/884' MSL.
Rwy 36, trees beginning 850' from DER, 133' left of centerline, up to 100' AGL/999' MSL.
Building and trees beginning 277' from DER, 361' right of centerline, up to 100' AGL/1009' MSL.
Vehicles on road beginning 165' from DER, left and right of centerline, up to 15' AGL/925' MSL.

ANGOLA, IN

TRI-STATE STEUBEN COUNTY (ANQ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 31DEC20 (20366) (FAA)

TAKEOFF MINIMUMS:

Rwy 5, 300-1¼ or std w/min climb of 360' per NM to 1300.

TAKEOFF OBSTACLE NOTES:

Rwy 5, fence, terrain beginning 8' from DER, 268' left of centerline, up to 6' AGL/1003' MSL.
Tree 9' from DER, 460' right of centerline, 1036' MSL.
Trees beginning 170' from DER, 335' left of centerline, up to 1027' MSL.
Trees beginning 237' from DER, 88' right of centerline, up to 1048' MSL.
Trees beginning 655' from DER, 292' right of centerline, up to 1075' MSL.
Trees beginning 845' from DER, 398' left of centerline, up to 1034' MSL.
Tree 1013' from DER, 671' left of centerline, 1040' MSL.
Trees beginning 1092' from DER, 585' left of centerline, up to 1074' MSL.
Tree 1312' from DER, 800' right of centerline, 1078' MSL.
Trees beginning 1397' from DER, 148' right of centerline, up to 1097' MSL.
Trees beginning 1709' from DER, 257' left of centerline, up to 1076' MSL.
Tree 1739' from DER, 928' right of centerline, 1098' MSL.
Trees, buildings, pole beginning 1740' from DER, 202' right of centerline, up to 1099' MSL.
Trees beginning 1828' from DER, 35' left of centerline, up to 1079' MSL.
Trees, poles, buildings, catenary beginning 1895' from DER, 18' right of centerline, up to 1103' MSL.
Trees, fence, terrain, pole beginning 1984' from DER, 14' left of centerline, up to 1106' MSL.
Trees, fence, poles, terrain, buildings, vehicles on traverse way beginning 2205' from DER, 1' left of centerline, up to 1122' MSL.
Trees, buildings, terrain, fence, tower, poles, general utility beginning 2628' from DER, 77' left of centerline, up to 1130' MSL.
Trees, pole, terrain, fence beginning 2927' from DER, 113' left of centerline, up to 1141' MSL.
Tree 3495' from DER, 459' right of centerline, up to 1125' MSL.
Trees beginning 3582' from DER, 366' right of centerline, up to 1134' MSL.
Trees beginning 3659' from DER, 652' right of centerline, up to 1140' MSL.
Trees beginning 3679' from DER, 117' right of centerline, up to 1141' MSL.
Trees, fence, terrain, beginning 3724' from DER, 218' left of centerline, up to 1147' MSL.
Trees, fence, terrain, buildings beginning 3819' from DER, 30' left of centerline, up to 1164' MSL.
Trees beginning 3838' from DER, 22' right of centerline, up to 1154' MSL.
Trees beginning 4029' from DER, abeam centerline, up to 1160' MSL.
Trees beginning 5636' from DER, 50' left of centerline, up to 1173' MSL.
Trees beginning 5721' from DER, 108' left of centerline, up to 1181' MSL.
Trees beginning 5832' from DER, 66' left of centerline, up to 1194' MSL.

CON'T

ANGOLA, IN (CON'T)

TRI-STATE STEUBEN COUNTY (ANQ) (CON'T)

Rwy 5 (CON'T), tree 6072' from DER, 522' left of centerline, 1171' MSL.
Rwy 23, vehicles on traverse way beginning 71' from DER, 343' left of centerline, 998' MSL.
Vehicles on traverse way beginning 114' from DER, 317' right of centerline, up to 1001' MSL.
Building 121' from DER, 456' left of centerline, 22' AGL/1003' MSL.
Building, vehicles on traverse way beginning 172' from DER, 229' left of centerline, up to 28' AGL/1012' MSL.
Trees, vehicles on traverse way, terrain beginning 245' from DER, 7' left of centerline, up to 1029' MSL.
Trees beginning 270' from DER, 374' right of centerline, up to 1002' MSL.
Trees beginning 497' from DER, 149' right of centerline, up to 1013' MSL.
Tree 631' from DER, 224' right of centerline, 1018' MSL.
Trees beginning 632' from DER, 78' right of centerline, up to 1023' MSL.
Trees, poles, terrain beginning 730' from DER, 74' right of centerline, up to 1053' MSL.
Terrain beginning 900' from DER, 10' left of centerline, up to 1031' MSL.
Tree 1331' from DER, 104' left of centerline, 1034' MSL.
Tree 1338' from DER, 18' left of centerline, 1036' MSL.
Trees beginning 1565' from DER, abeam centerline, up to 1061' MSL.
Tree 1623' from DER, 221' left of centerline, 1041' MSL.
Trees beginning 1682' from DER, 283' left of centerline, up to 1042' MSL.
Tree 1818' from DER, 367' left of centerline, 1053' MSL.
Trees beginning 1885' from DER, 2' left of centerline, up to 1065' MSL.
Trees beginning 2188' from DER, 629' left of centerline, up to 1067' MSL.
Trees beginning 2355' from DER, 621' left of centerline, up to 1072' MSL.
Trees beginning 2823' from DER, 37' left of centerline, up to 1082' MSL.
Trees beginning 3045' from DER, 35' left of centerline, up to 1092' MSL.
Trees beginning 3053' from DER, 89' right of centerline, up to 1084' MSL.

ASHLAND, OH

ASHLAND COUNTY (3G4)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 06MAY10 (10126) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 1, trees beginning 61' from DER, 194' right of centerline, up to 50' AGL/1249' MSL.
Rwy 19, trees beginning 5' from DER, 167' left of centerline, up to 50' AGL/1259' MSL.

ASHTABULA, OH

NORTHEAST OHIO RGNL (HZY)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 12OCT17 (17285) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, tree 492' from DER, 507' left of centerline, 23' AGL/942' MSL.
Tree 904' from DER, 708' left of centerline, 5' AGL/962' MSL.
Tree 1187' from DER, 650' left of centerline, 14' AGL/966' MSL.
Trees beginning 1259' from DER, 629' left of centerline, up to 40' AGL/967' MSL.
Tree 1370' from DER, 739' left of centerline, 76' AGL/995' MSL.
Trees beginning 1464' from DER, 619' left of centerline, up to 83' AGL/1002' MSL.
Trees beginning 1613' from DER, 699' left of centerline, up to 90' AGL/1010' MSL.
Trees beginning 1737' from DER, 575' left of centerline, up to 103' AGL/1023' MSL.
Trees beginning 1778' from DER, 468' left of centerline, up to 105' AGL/1026' MSL.
Tree 2099' from DER, 816' right of centerline, 49' AGL/981' MSL.
Tree 2139' from DER, 748' right of centerline, 73' AGL/999' MSL.
Trees beginning 2201' from DER, 169' right of centerline, up to 75' AGL/1003' MSL.
Rwy 27, trees beginning 746' from DER, 646' right of centerline, up to 45' AGL/939' MSL.
Pole 801' from DER, 484' left of centerline, 29' AGL/937' MSL.
Pole 818' from DER, 645' left of centerline, 35' AGL/938' MSL.
Trees beginning 1059' from DER, 678' right of centerline, up to 59' AGL/949' MSL.
Trees beginning 1134' from DER, 646' right of centerline, up to 84' AGL/978' MSL.
Trees beginning 1182' from DER, 740' left of centerline, up to 72' AGL/966' MSL.
Trees beginning 1978' from DER, 546' right of centerline, up to 92' AGL/991' MSL.
Tree 3418' from DER, 811' left of centerline, 97' AGL/995' MSL.
Tree 3717' from DER, 1073' left of centerline, 105' AGL/1003' MSL

29 OCT 2026 to 26 NOV 2026

26190

ATHENS/ALBANY, OH

OHIO UNIVERSITY (UNI)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 23JUL15 (26078) (FAA)

TAKEOFF MINIMUMS:

Rwy 7, 200-1 or std w/min climb of 310' per NM to 1000.

Rwy 25, 200-1 or std w/min climb of 360' per NM to 1000.

TAKEOFF OBSTACLE NOTES:

Rwy 7, trees beginning 4439' from DER, 1034' left of centerline, up to 100' AGL/933' MSL.
Trees beginning 2869' from DER, 1171' right of centerline, up to 100' AGL/879' MSL.
Vehicle abeam DER 451' left of centerline, 17' AGL/769' MSL.

Rwy 25, trees beginning 3371' from DER, 425' left of centerline, up to 100' AGL/925' MSL.
Trees beginning 1221' from DER, 624' right of centerline, up to 100' AGL/999' MSL.

AUBURN, IN

AUBURN/DEKALB EXEC (GWB)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1A 31OCT24 (25275) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, trees beginning 2135' from DER, 975' right of centerline, up to 962' MSL.

Rwy 27, trees beginning 389' from DER, 483' left of centerline, up to 938' MSL.
Trees beginning 693' from DER, 613' right of centerline, up to 933' MSL.
Trees, pole beginning 787' from DER, 363' left of centerline, up to 949' MSL.
Trees beginning 1678' from DER, 546' right of centerline, up to 941' MSL.
Trees beginning 2086' from DER, 676' left of centerline, up to 957' MSL.
Trees beginning 2298' from DER, 693' left of centerline, up to 964' MSL.
Tree 2829' from DER, 1239' right of centerline, 948' MSL.
Trees beginning 2877' from DER, 1104' right of centerline, up to 956' MSL.

BARNESVILLE, OH

BARNESVILLE/BRADFIELD (6G5)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 17APR25 (25107) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, vegetation 4' from DER, 294' right of centerline, 1322' MSL.
Trees beginning 53' from DER, 90' left of centerline, up to 21' AGL/1328' MSL.
Vegetation 81' from DER, 419' right of centerline, 1325' MSL.
Vegetation 105' from DER, 250' right of centerline, 15' AGL/1330' MSL.
Trees, fence, vegetation beginning 164' from DER, 118' right of centerline, up to 78' AGL/1377' MSL.
Trees beginning 278' from DER, 22' right of centerline, up to 78' AGL/1386' MSL.
Tree 655' from DER, 4' left of centerline, 91' AGL/1330' MSL.

Rwy 27, vehicles on road 13' from DER, 94' right of centerline, 1323' MSL.
Poles, vehicles on road, fence, trees beginning 85' from DER, 15' left of centerline, up to 34' AGL/1327' MSL.
Vehicles on road 93' from DER, 22' right of centerline, 1324' MSL.
Poles, trees beginning 256' from DER, 29' left of centerline, up to 1335' MSL.
Building 351' from DER, 295' left of centerline, 1341' MSL.
Trees, buildings beginning 354' from DER, 184' left of centerline, up to 1371' MSL.
Tree 452' from DER, 16' right of centerline, 34' AGL/1331' MSL.
Tree 496' from DER, 243' left of centerline, 70' AGL/1394' MSL.
Trees beginning 533' from DER, 5' left of centerline, up to 75' AGL/1402' MSL.
Tree 550' from DER, 2' right of centerline, 39' AGL/1339' MSL.
Tree 1436' from DER, 198' right of centerline, 47' AGL/1345' MSL.
Tree 1565' from DER, 515' right of centerline, 1352' MSL.
Tree 1665' from DER, 554' right of centerline, 1354' MSL.
Tree 1817' from DER, 77' right of centerline, 53' AGL/1364' MSL.
Trees beginning 1866' from DER, 185' right of centerline, up to 1374' MSL.
Trees beginning 1946' from DER, 299' right of centerline, up to 1402' MSL.
Trees beginning 3176' from DER, 942' right of centerline, up to 75' AGL/1410' MSL.

29 OCT 2026 to 26 NOV 2026

26190

BATAVIA, OH

CLERMONT COUNTY (I69)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 03MAY12 (12124) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 4, terrain 8' from DER, 311' left of centerline, 813' MSL.
Trees beginning 89' from DER, left and right of centerline, up to 100' AGL/899' MSL.
Fence 195' from DER, 276' left of centerline, up to 19' AGL/819' MSL.
Vehicles on roadway beginning 237' from DER, left and right of centerline, up to 15' AGL/824' MSL.
Windsock 408' from DER, 225' right of centerline, up to 24' AGL/824' MSL.
Rwy 22, buildings 55' from DER, left and right of centerline, up to 22' AGL/862' MSL.
Trees beginning 81' from DER, left and right of centerline, up to 100' AGL/ 967' MSL.
Fences beginning 102' from DER, left and right of centerline, up to 17' AGL/857' MSL.
Poles beginning 195' from DER, left and right of centerline, up to 45' AGL/ 885' MSL.
Vehicles on roadway beginning 216' from DER, left and right of centerline, up to 15' AGL/866' MSL.
Sign 441' from DER, 231' left of centerline, up to 19' AGL/859' MSL.

BEDFORD, IN

VIRGIL I GRISSOM MUNI (BFR)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 19MAR26 (26078) (FAA)

TAKEOFF MINIMUMS:

Rwy 13, 300-1⅜ or std w/min climb of 289'/NM to 1100.

TAKEOFF OBSTACLE NOTES:

Rwy 6, trees beginning 128' from DER, 309' left of centerline, up to 40' AGL/762' MSL.
Trees beginning 165' from DER, 73' right of centerline, up to 40' AGL/759' MSL.
Trees beginning 321' from DER, 54' left of centerline, up to 127' AGL/815' MSL.
Trees beginning 403' from DER, 71' right of centerline, up to 40' AGL/766' MSL.
Rwy 13, trees beginning 78' from DER, 229' right of centerline, up to 81' AGL/785' MSL.
Tree 153' from DER, 207' left of centerline, 18' AGL/727' MSL.
Tree 179' from DER, 46' left of centerline, 19' AGL/729' MSL.
Pole 508' from DER, 548' left of centerline, 28' AGL/749' MSL.
Trees beginning 534' from DER, 416' right of centerline, up to 88' AGL/787' MSL.
Trees beginning 660' from DER, 356' right of centerline, up to 100' AGL/799' MSL.
Trees beginning 793' from DER, 389' right of centerline, up to 95' AGL/804' MSL.
Trees beginning 842' from DER, 381' right of centerline, up to 99' AGL/821' MSL.
Tree 1130' from DER, 523' right of centerline, 98' AGL/823' MSL.
Trees beginning 1151' from DER, 4' right of centerline, up to 110' AGL/832' MSL.
Tree 1490' from DER, 628' left of centerline, 76' AGL/798' MSL.
Trees beginning 1540' from DER, 7' left of centerline, up to 86' AGL/807' MSL.
Trees beginning 2438' from DER, 15' left of centerline, up to 102' AGL/825' MSL.
Trees beginning 2823' from DER, 37' left of centerline, up to 98' AGL/827' MSL.
Trees beginning 3228' from DER, 78' right of centerline, up to 142' AGL/849' MSL.
Tree 3431' from DER, 291' left of centerline, 123' AGL/833' MSL.
Tower 1.1 NM from DER, 1350' left of centerline, 293' AGL/979' MSL.
Rwy 24, trees 89' from DER, 463' left of centerline, 40' AGL/746' MSL.
Trees beginning 126' from DER, 79' left of centerline, up to 40' AGL/756' MSL.
Trees beginning 163' from DER, 46' right of centerline, up to 40' AGL/752' MSL.
Rwy 31, tree 27' from DER, 312' left of centerline, 63' AGL/766' MSL.
Trees beginning 75' from DER, 205' left of centerline, up to 66' AGL/770' MSL.
Tree 184' from DER, 466' right of centerline, 18' AGL/733' MSL.
Trees beginning 248' from DER, 5' right of centerline, up to 37' AGL/749' MSL.
Tree 267' from DER, 417' left of centerline, 77' AGL/780' MSL.
Trees beginning 296' from DER, 189' left of centerline, up to 83' AGL/784' MSL.
Trees beginning 407' from DER, 67' left of centerline, up to 94' AGL/794' MSL.
Trees beginning 411' from DER, 148' right of centerline, up to 69' AGL/770' MSL.
Trees beginning 538' from DER, 186' left of centerline, up to 97' AGL/795' MSL.
Trees beginning 615' from DER, 299' right of centerline, up to 89' AGL/774' MSL.
Trees beginning 702' from DER, 36' left of centerline, up to 116' AGL/806' MSL.
Trees beginning 750' from DER, 21' right of centerline, up to 102' AGL/777' MSL.
Trees beginning 815' from DER, 266' right of centerline, up to 91' AGL/783' MSL.
Trees beginning 1048' from DER, 89' right of centerline, up to 104' AGL/789' MSL.

29 OCT 2026 to 26 NOV 2026

26190

BELLEFONTAINE, OH

BELLEFONTAINE RGNL (EDJ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 18OCT12 (12292) (FAA)

TAKEOFF MINIMUMS:

Rwy 7, std w/min climb of 245' per NM to 2100.

DEPARTURE PROCEDURE:

Rwy 7, climb heading 074° to 2100 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 7, trees beginning 2172' from DER, 43' right of centerline, up to 99' AGL/ 1224' MSL.
Trees beginning 2252' from DER, 77' left of centerline, up to 89' AGL/1228' MSL.
Rwy 25, tree 508' from DER, 539' right of centerline, 35' AGL/ 1144' MSL.
Ground 66' from DER, 494' right of centerline, 1107' MSL.

BLOOMINGTON, IN

MONROE COUNTY (BMG)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 6 25AUG11 (11237) (FAA)

TAKEOFF MINIMUMS:

Rwy 24, 300-1.

TAKEOFF OBSTACLE NOTES:

Rwy 6, poles and building beginning 424' from DER, 332' left of centerline, up to 29' AGL/874' MSL.
Trees beginning 491' from DER, left and right of centerline, up to 72' AGL/972' MSL.
Fence 181' from DER, 115' right of centerline, 6' AGL/846' MSL.
Vehicle on road beginning 89' from DER, left and right of centerline,15' AGL/862' MSL.
Rwy 17, vehicle on road 187' from DER, 18' right of centerline, 15' AGL/850' MSL.
Tree 1263' from DER, 625' right of centerline, 32' AGL/871' MSL.
Bush 855' from DER, 594' left of centerline, 25' AGL/862' MSL.
Rwy 24, trees and poles beginning 158' from DER, left and right of centerline, up to 85' AGL/1021' MSL.
Fence 394' from DER, 72' left of centerline, 9' AGL/849' MSL.
Buildings beginning 1990' from DER, 321' right of centerline, up to 25' AGL/952' MSL.
Vehicle on road beginning 45' from DER, left and right of centerline, 15' AGL/945' MSL.
Rwy 35, trees beginning 2119' from DER, 120' left and right of centerline, up to 85' AGL/975' MSL.

BLUFFTON, OH

BLUFFTON (5G7)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1A 15OCT15 (15288) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 5, runway lights beginning 9' from DER, left and right of centerline, up to 3' AGL/848' MSL.
Road and pole beginning 53' from DER, left and right of centerline, up to 42' AGL/889' MSL.
Roads beginning 211' from DER, 330' right of centerline, up to 17' AGL/881' MSL.
Poles, road and tree beginning 497' from DER, up to 100' AGL/883' MSL.
Trees and poles beginning 1205' from DER, left and right of centerline, up to 100' AGL/911' MSL.
Rwy 23, runway lights beginning 8' from DER, left and right of centerline, up to 4' AGL/852' MSL.
Tree 91' from DER, 167' left of centerline, 100' AGL/853' MSL.
Tree 298' from DER, 506' right of centerline, 100' AGL/866' MSL.
Trees beginning 405 from DER, left and right of centerline, up to 100' AGL/900' MSL.
Trees beginning 1007' from DER, left and right of centerline, up to 100' AGL/932' MSL.

BOWLING GREEN, OH

WOOD COUNTY RGNL (1G0)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 15MAR07 (26134) (FAA)

TAKEOFF MINIMUMS:

Rwy 18, 300-1.

TAKEOFF OBSTACLE NOTES:

Rwy 18, building/tower 3581' from DER, 254' right of centerline, 141' AGL/841' MSL.

29 OCT 2026 to 26 NOV 2026
29 OCT 2026 to 26 NOV 2026

26190

BRAZIL, IN

BRAZIL CLAY COUNTY/CHARLES B HALL FLD (0I2)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 09JUL26 (26190) (FAA)

TAKEOFF MINIMUMS:

Rwy 9: 300-2¼ or std w/min climb of 220'/NM to 1100 or std and crossing DER 26' above DER elev clears takeoff minimums obstacles. Alternatively, with std takeoff minimums and a normal 200'/NM climb gradient, takeoff must occur no later than 1900' prior to DER.

TAKEOFF OBSTACLE NOTES:

Rwy 9 Low, Close-in Obstacles: trees within 500' from DER extending to ¾ NM from DER, left, right, and crossing centerline, up to 749' MSL, 118' above DER. Crossing DER 92' above DER elev clears low, close-in obstacles.

Rwy 9 Takeoff Minimums Obstacles: trees 1.6 NM from DER extending to 1.8 NM from DER, left and right of centerline, up to 919' MSL, 288' above DER. Crossing DER 26' above DER elev clears takeoff minimums obstacles.

Rwy 27 Low, Close-in Obstacles: trees within 500' from DER extending to ½ NM from DER, left, right, and crossing centerline, up to 769' MSL, 124' above DER. Crossing DER 99' above DER elev clears low, close-in obstacles.

BRYAN, OH

WILLIAMS COUNTY (0G6)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 12JUN25 (25163) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 7, terrain 71' from DER, 121' right of centerline, 734' MSL.
Vehicles on road 91' from DER, 366' left of centerline, 747' MSL.
Tree, vehicles on road beginning 159' from DER, 171' left of centerline, up to 30' AGL/759' MSL.
Trees, building beginning 392' from DER, 400' right of centerline, up to 801' MSL.
Tree 636' from DER, 605' right of centerline, 822' MSL.
Trees, building beginning 781' from DER, 404' right of centerline, up to 823' MSL.
Trees beginning 937' from DER, 239' right of centerline, up to 828' MSL.
Trees beginning 1280' from DER, 164' right of centerline, up to 836' MSL.
Rwy 25, vegetation beginning 66' from DER, 473' left of centerline, up to 733' MSL.
Pole 208' from DER, 497' right of centerline, 38' AGL/768' MSL.
Poles, vehicles on road, buildings, tree, smokestack beginning 282' from DER, 216' right of centerline, up to 39' AGL/769' MSL.
Vehicles on road beginning 485' from DER, 87' left of centerline, up to 746' MSL.
Transmission lines, vehicles on road, poles beginning 533' from DER, 215' left of centerline, up to 41' AGL/769' MSL.
Tree 2267' from DER, 1087' left of centerline, 794' MSL.
Transmission line 2666' from DER, 958' right of centerline, 67' AGL/796' MSL.
Transmission line 2748' from DER, 991' right of centerline, 70' AGL/798' MSL.
Tree 2841' from DER, 1199' right of centerline, 806' MSL.
Trees beginning 2913' from DER, 1019' right of centerline, up to 810' MSL.

BUCYRUS, OH

PORT BUCYRUS/CRAWFORD COUNTY (17G)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 18NOV10 (22195) (FAA)

TAKEOFF MINIMUMS:

Rwy 4, 300-1½ or std w/min climb of 297' per NM to 1300, or alternatively, with std takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1400' prior to DER.

TAKEOFF OBSTACLE NOTES:

Rwy 4, terrain 4' from DER, 484' right of centerline, up to 1008' MSL.
Aircraft on ramp beginning 47' from DER, 289' right of centerline, up to 15' AGL/1019' MSL.
Terrain beginning 93' from DER, 245' left of centerline, up to 1008' MSL.
Vehicle on road beginning 107' from DER, 487' right of centerline, 15' AGL/1019' MSL.
Trees 229' from DER, 261' left of centerline, up to 100' AGL/1099' MSL.
Trees 2777' from DER,1207' left of centerline, up to 100' AGL/1109' MSL.
Trees 2933' from DER, 330' right of centerline, up to 100' AGL/1124' MSL.
Tower 1.1 NM from DER, 1798' left of centerline, 165' AGL/1175' MSL.
Rwy 22, buildings beginning 4' from DER, 352' right of centerline, up to 40' AGL/1044' MSL.
Vehicle on road beginning 243' from DER, 552' left of centerline, 15' AGL/1019' MSL.
Trees 426' from DER, 382' left of centerline, up to 100' AGL/1104' MSL.
Trees 733' from DER, 466' right of centerline, up to 100' AGL/1099' MSL.

29 OCT 2026 to 26 NOV 2026

26190

CADIZ, OH

HARRISON COUNTY (8G6)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4 10SEP20 (20254) (FAA)

TAKEOFF MINIMUMS:

Rwy 13, 300-1⅛ or std w/min climb of 274' per NM to 1400.

TAKEOFF OBSTACLE NOTES:

Rwy 13, tree, vegetation beginning 31' from DER, 98' left of centerline, up to 1133' MSL.
Building, tree beginning 55' from DER, 163' right of centerline, up to 17' AGL/1127' MSL.
Pole, tree beginning 190' from DER, 114' left of centerline, up to 39' AGL/1148' MSL.
Trees beginning 225' from DER, 154' right of centerline, up to 1132' MSL.
Tree, pole beginning 407' from DER, 82' left of centerline, up to 1175' MSL.
Tree 656' from DER, 449' right of centerline, 1137' MSL.
Tree 697' from DER, 281' right of centerline, 1139' MSL.
Tree 722' from DER, 647' right of centerline, 1144' MSL.
Tree 811' from DER, 450' right of centerline, 1156' MSL.
Trees beginning 858' from DER, 179' right of centerline, up to 1158' MSL.
Trees beginning 927' from DER, 58' right of centerline, up to 1169' MSL.
Tree, terrain, pole, fence beginning 1068' from DER, 44' right of centerline, up to 1199' MSL.
Tree 1530' from DER, 151' left of centerline, 1195' MSL.
Trees beginning 1620' from DER, 221' left of centerline, up to 1204' MSL.
Trees beginning 1727' from DER, 4' left of centerline, up to 1215' MSL.
Terrain, tree beginning 1927' from DER, 22' right of centerline, up to 1208' MSL.
Trees beginning 2703' from DER, 87' left of centerline, up to 1220' MSL.
Tree, terrain beginning 2811' from DER, 228' right of centerline, up to 1224' MSL.
Tree, terrain beginning 2944' from DER, 68' right of centerline, up to 1230' MSL.
Tree 3047' from DER, 126' left of centerline, 1222' MSL.
Tree, terrain beginning 3080' from DER, 43' right of centerline, up to 1232' MSL.
Trees beginning 3277' from DER, 401' right of centerline, up to 1233' MSL.
Trees beginning 3399' from DER, 104' right of centerline, up to 1234' MSL.
Tree 5966' from DER, 2009' right of centerline, 1273' MSL.
Tree 1 NM from DER, 2037' right of centerline, 1309' MSL.
Trees beginning 1 NM from DER, 1544' right of centerline, up to 1325' MSL.
Tree 1.3 NM from DER, 428' left of centerline, 1312' MSL.
Trees beginning 1.3 NM from DER, 343' left of centerline, up to 1329' MSL.
Trees beginning 1.4 NM from DER, 1568' left of centerline, up to 1339' MSL.
Tree 1.4 NM from DER, 1705' left of centerline, 1340' MSL.
Trees beginning 1.5 NM from DER, 1653' left of centerline, up to 1350' MSL.
Trees beginning 1.5 NM from DER, 1592' left of centerline, up to 1350' MSL.
Rwy 31, terrain 40' from DER, 175' right of centerline, 1198' MSL.
Terrain 71' from DER, 374' left of centerline, 1188' MSL.
Terrain 89' from DER, 287' right of centerline, 1219' MSL.
Terrain 99' from DER, 195' left of centerline, 1194' MSL.
Trees and fence beginning 136' from DER, 5' right of centerline, up to 1229' MSL.
Terrain 196' from DER, 494' left of centerline, 1213' MSL.
Trees beginning 204' from DER, 200' left of centerline, up to 1214' MSL.
Fence beginning 341' from DER, 97' left of centerline, up to 3' AGL/1218' MSL.
Trees and fence beginning 403' from DER, 1' right of centerline, up to 1235' MSL.
Fence beginning 485' from DER, 100' left of centerline, up to 4' AGL/1219' MSL.
Fence beginning 802' from DER, 109' left of centerline, up to 4' AGL/1224' MSL.
Fence and vegetation beginning 964' from DER, 41' left of centerline, up to 4' AGL/1226' MSL.
Trees and fence beginning 991' from DER, 88' left of centerline, up to 1229' MSL.

29 OCT 2026 to 26 NOV 2026

26190

CALDWELL, OH

NOBLE COUNTY (I10)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 14MAY26 (26134) (FAA)

TAKEOFF MINIMUMS:

Rwy 5, 400-2½.

Rwy 23, 400-2½ or std w/min climb of 281'/NM to 1300.

DEPARTURE PROCEDURE:

Rwy 5, climb on heading 048° to 1400 before turning left.

Rwy 23, climb on heading 228° to 1600 before turning left.

TAKEOFF OBSTACLE NOTES:

Rwy 5, trees 59' from DER, 39' right of centerline, 100' AGL/983' MSL.
Trees 138' from DER, 335' left of centerline, 100' AGL/980' MSL.
Trees 211' from DER, 217' right of centerline, 100' AGL/996' MSL.
Trees beginning 290' from DER, 157' left of centerline, up to 100' AGL/986' MSL.
Trees beginning 363' from DER, 20' right of centerline, up to 100' AGL/1036' MSL.
Trees, building, vehicles on road beginning 515' from DER, 1' right of centerline, up to 100' AGL/1049' MSL.
Trees, building beginning 521' from DER, 216' left of centerline, up to 100' AGL/990' MSL.
Trees 673' from DER, 176' left of centerline, 100' AGL/996' MSL.
Tree 751' from DER, 552' left of centerline, 100' AGL/1022' MSL.
Trees beginning 903' from DER, 374' left of centerline, up to 100' AGL/1042' MSL.
Trees beginning 1056' from DER, 18' left of centerline, up to 100' AGL/1045' MSL.
Trees, vehicles on road beginning 1438' from DER, 37' left of centerline, up to 100' AGL/1049' MSL.
Trees, building beginning 1669' from DER, 234' left of centerline, up to 100' AGL/1052' MSL.
Trees, vehicles on road beginning 1973' from DER, 56' left of centerline, up to 100' AGL/1062' MSL.
Trees beginning 2126' from DER, 44' right of centerline, up to 100' AGL/1055' MSL.
Trees beginning 2204' from DER, 76' left of centerline, up to 100' AGL/1065' MSL.
Trees beginning 2361' from DER, 95' left of centerline, up to 100' AGL/1081' MSL.
Trees beginning 3804' from DER, 222' right of centerline, up to 100' AGL/1065' MSL.
Trees 3883' from DER, 775' right of centerline, 100' AGL/1072' MSL.
Trees beginning 3956' from DER, 24' right of centerline, up to 100' AGL/1078' MSL.
Trees beginning 3972' from DER, 172' left of centerline, up to 100' AGL/1085' MSL.
Trees beginning 4108' from DER, 577' right of centerline, up to 100' AGL/1085' MSL.
Trees beginning 4187' from DER, 202' right of centerline, up to 100' AGL/1098' MSL.
Trees beginning 4339' from DER, 5' right of centerline, up to 100' AGL/1101' MSL.
Trees beginning 4354' from DER, 13' left of centerline, up to 100' AGL/1101' MSL.
Trees beginning 1 NM from DER, 86' right of centerline, up to 100' AGL/1111' MSL.
Trees beginning 1 NM from DER, 91' left of centerline, up to 100' AGL/1167' MSL.
Trees beginning 1.1 NM from DER, 129' left of centerline, up to 100' AGL/1200' MSL.
Trees beginning 1.1 NM from DER, 48' right of centerline, up to 100' AGL/1147' MSL.
Trees beginning 1.2 NM from DER, 206' right of centerline, up to 100' AGL/1170' MSL.
Trees beginning 1.2 NM from DER, 543' left of centerline, up to 100' AGL/1203' MSL.
Trees beginning 1.3 NM from DER, 9' right of centerline, up to 100' AGL/1236' MSL.
Trees beginning 1.3 NM from DER, 10' left of centerline, up to 100' AGL/1239' MSL.
Trees beginning 1.5 NM from DER, 70' right of centerline, up to 100' AGL/1255' MSL.
Trees beginning 1.6 NM from DER, 87' left of centerline, up to 100' AGL/1265' MSL.
Trees beginning 1.9 NM from DER, 546' right of centerline, up to 100' AGL/1265' MSL.
Trees 2 NM from DER, 724' right of centerline, 100' AGL/1196' MSL.

Rwy 23, trees beginning 31' from DER, 85' right of centerline, up to 100' AGL/954' MSL.
Trees beginning 110' from DER, 54' left of centerline, up to 100' AGL/970' MSL.
Trees beginning 1101' from DER, 263' right of centerline, up to 100' AGL/967' MSL.
Trees beginning 1253' from DER, 441' right of centerline, up to 100' AGL/973' MSL.
Tree 2019' from DER, 778' right of centerline, 100' AGL/976' MSL.
Trees beginning 2171' from DER, 561' right of centerline, up to 100' AGL/983' MSL.
Trees beginning 2948' from DER, 583' left of centerline, up to 100' AGL/986' MSL.
Trees beginning 1.3 NM from DER, 100' left of centerline, up to 100' AGL/1150' MSL.
Trees beginning 1.4 NM from DER, 119' left of centerline, up to 100' AGL/1173' MSL.
Trees beginning 1.4 NM from DER, 58' right of centerline, 100' AGL/1170' MSL.
Trees beginning 1.5 NM from DER, 39' right of centerline, up to 100' AGL/1180' MSL.
Trees beginning 1.6 NM from DER, 730' left of centerline, up to 100' AGL/1190' MSL.
Trees beginning 1.7 NM from DER, 590' left of centerline, up to 100' AGL/1196' MSL.
Trees beginning 2 NM from DER, 1595' left of centerline, 100' AGL/1186' MSL.

29 OCT 2026 to 26 NOV 2026

26190

CAMBRIDGE, OH

CAMBRIDGE MUNI (CDI)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 05MAR15 (15064) (FAA)

TAKEOFF MINIMUMS:

Rwy 4, 400-2 or std w/min climb of 397' per NM to 1400.

Rwy 22, 300-1½ or std w/min climb of 685' per NM to 1100.

DEPATURE PROCEDURE:

Rwy 4, climb heading 040° to 1300 before turning left.

TAKEOFF OBSTACLE NOTES:

Rwy 4, multiple trees beginning 161' from DER, 179' left of centerline, up to 51' AGL/849' MSL.
Multiple trees beginning 672' from DER, 563' right of centerline, up to 62' AGL/860' MSL.
Multiple poles beginning 301' from DER, 519' right of centerline, up to 31' AGL/973' MSL.
Multiple towers beginning 794' from DER, 659' left of centerline, up to 43' AGL/835' MSL.
Building 639' from DER, 386' right of centerline, 25' AGL/825' MSL.
Multiple poles beginning 990' from DER, 26' left of centerline, up to 36' AGL/826' MSL.
Multiple trees beginning 1147' from DER, 144' right of centerline, up to 74' AGL/872' MSL.
Multiple trees beginning 1307' from DER, 2' left of centerline, up to 89' AGL/887' MSL.
Multiple towers, poles beginning 1040' from DER, 336' right of centerline, up to 48' AGL/843' MSL.
Multiple towers, poles beginning 1089' from DER, 613' left of centerline, up to 36' AGL/833' MSL.
Sign 1029' from DER, 623' left of centerline, 35' AGL/832' MSL.
Monument 1.5 NM from DER, 402' left of centerline, 120' AGL/1098' MSL.
Multiple trees beginning 1.5 NM from DER, 738' right of centerline, up to 100' AGL/1126' MSL.
Tower 2.8 NM from DER, 4400' left of centerline, 233' AGL/1106' MSL.
Rwy 22, multiple trees beginning 204' from DER, 309' right of centerline, up to 100' AGL/931' MSL.
Multiple poles beginning 366' from DER, 43' right of centerline, up to 35' AGL/834' MSL.
NAVAID 300' from DER, 1' right of centerline, 9' AGL/807' MSL.
Obstruction light on DME 477' from DER, 168' right of centerline, 19' AGL/817' MSL.
Multiple trees beginning 1004' from DER, 395' left of centerline, up to 100' AGL/1023' MSL.
Multiple poles beginning 1165' from DER, 93' left of centerline, up to 34' AGL/1021' MSL.
Building 1272' from DER, 426' right of centerline, 21' AGL/881' MSL.

29 OCT 2026 to 26 NOV 2026

CARROLLTON, OH

CARROLL COUNTY/TOLSON (TSO)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 5 02DEC21 (25331) (FAA)

TAKEOFF MINIMUMS:

Rwy 7, 400-2½ or std w/min climb of 611' per NM to 1400.

TAKEOFF OBSTACLE NOTES:

Rwy 7, trees, poles beginning 28' from DER, 8' left of centerline, up to 82' AGL/1232' MSL.
Trees beginning 343' from DER, 177' right of centerline, up to 65' AGL/1187' MSL.
Trees beginning 403' from DER, 117' right of centerline, up to 1195' MSL.
Tree 613' from DER, 205' right of centerline, 77' AGL/1203' MSL.
Trees beginning 625' from DER, 54' right of centerline, up to 1212' MSL.
Trees, building beginning 1511' from DER, 502' left of centerline, up to 1246' MSL.
Trees beginning 1549' from DER, 538' right of centerline, up to 1223' MSL.
Trees beginning 1566' from DER, 5' left of centerline, up to 1248' MSL.
Tree 1666' from DER, 612' left of centerline, 1270' MSL.
Trees beginning 1671' from DER, 38' left of centerline, up to 1299' MSL.
Trees beginning 1779' from DER, 25' right of centerline, up to 70' AGL/1253' MSL.
Trees beginning 1836' from DER, 28' left of centerline, up to 1311' MSL.
Trees beginning 1926' from DER, 41' left of centerline, up to 1312' MSL.
Trees beginning 1961' from DER, 60' right of centerline, up to 69' AGL/1264' MSL.
Tree 2003' from DER, 246' right of centerline, 70' AGL/1271' MSL.
Trees beginning 2014' from DER, 133' right of centerline, up to 81' AGL/1279' MSL.
Trees beginning 2035' from DER, 2' right of centerline, up to 108' AGL/1300' MSL.
Trees beginning 2075' from DER, 22' left of centerline, up to 77' AGL/1322' MSL.
Trees beginning 2183' from DER, 53' left of centerline, up to 88' AGL/1323' MSL.
Trees beginning 2383' from DER, 6' left of centerline, up to 119' AGL/1325' MSL.
Trees beginning 2545' from DER, 101' left of centerline, up to 114' AGL/1333' MSL.
Trees beginning 2606' from DER, 181' left of centerline, up to 71' AGL/1334' MSL.
Trees beginning 2706' from DER, 291' left of centerline, up to 76' AGL/1342' MSL.
Trees, transmission line beginning 3135' from DER, 25' left of centerline, up to 1344' MSL.
Tree 1.1 NM from DER, 1828' right of centerline, 91' AGL/1355' MSL.
Transmission line 2 NM from DER, 823' right of centerline, 118' AGL/1479' MSL.
CON'T

CARROLLTON, OH (CON'T)

CARROLL COUNTY/TOLSON (TSO) (CON'T)

Rwy 25, tree 47' from DER, 240' left of centerline, 1183' MSL.
Terrain 119' from DER, 521' left of centerline, 1184' MSL.
Trees beginning 129' from DER, 253' left of centerline, up to 9' AGL/1191' MSL.
Trees beginning 213' from DER, 245' left of centerline, up to 1199' MSL.
Trees beginning 595' from DER, 322' left of centerline, up to 1205' MSL.
Trees beginning 880' from DER, 677' left of centerline, up to 1236' MSL.
Transmission line 5230' from DER, 1788' left of centerline, 1306' MSL.

CELINA, OH

LAKEFIELD (CQA)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 11FEB10 (10042) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 8, trees beginning 782' from DER, 7' right of centerline, up to 100' AGL/969' MSL.
Trees beginning 57' from DER, 130' left of centerline, up to 100' AGL/976' MSL.
Rwy 26, vehicle 63' from DER, 469' right of centerline, 15' AGL/909' MSL.
Poles beginning 127' from DER, 145' right of centerline, up to 51' AGL/941' MSL.
Antenna 653' from DER, 498' right of centerline, 33' AGL/923' MSL.
Trees beginning 1194' from DER, 319' right of centerline, up to 100' AGL/952' MSL.

CHILLICOTHE, OH

ROSS COUNTY (RZT)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3A 17NOV11 (11321) (FAA)

TAKEOFF MINIMUMS:

Rwy 23, 400-1 or std w/min climb of 340' per NM to 1300.

DEPARTURE PROCEDURE:

Rwy 5, climb runway heading to 1500 before turning right.
Rwy 23, climb runway heading to 1500 before turning left.

CINCINNATI, OH

CINCINNATI MUNI/LUNKEN FLD (LUK)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 16 11JUL24 (24193) (FAA)

TAKEOFF MINIMUMS:

Rwy 3, 400-2 w/min climb of 234'/NM to 1300 or std w/min climb of 384'/NM to 1100, or 1700-3 for VCOA.
Rwy 7, 400-2¼ w/min climb of 207'/NM to 1300 or std w/min climb of 451'/NM to 900, or 1700-3 for VCOA.
Rwy 21, 500-3 w/min climb of 230'/NM to 1300 or std w/min climb of 439'/NM to 1000, or 1700-3 for VCOA.
Rwy 25, 600-3 w/min climb of 216'/NM to 1200, or 1700-3 for VCOA.

DEPARTURE PROCEDURE:

Rwy 3, climb on heading 025° to 1400 before proceeding on course.
Rwy 7, climb on heading 066° to 1300 before proceeding on course.
Rwy 21, climb on heading 205° to 1400 before proceeding on course.
Rwy 25, climb on heading 246° to 1900 before proceeding on course.

VCOA:

All runways, obtain ATC approval for VCOA when requesting IFR clearance. Climb in visual conditions to cross Cincinnati Muni/Lunken Fld at or above 2000 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 3, terrain 30' from DER, 476' left of centerline, 476' MSL.
Trees beginning 513' from DER, 335' right of centerline, up to 521' MSL.
Trees beginning 913' from DER, 579' left of centerline, up to 508' MSL.
Trees beginning 1084' from DER, 185' left of centerline, up to 527' MSL.
Trees beginning 1573' from DER, 128' right of centerline, up to 50' AGL/524' MSL.
Trees beginning 1662' from DER, 177' left of centerline, up to 529' MSL.
Trees beginning 1885' from DER, 285' right of centerline, up to 531' MSL.
Tree 1969' from DER, 501' right of centerline, 532' MSL.
Tree 2015' from DER, 979' right of centerline, 58' AGL/533' MSL.
Trees beginning 2058' from DER, 385' right of centerline, up to 539' MSL.
Trees beginning 2437' from DER, 896' right of centerline, up to 549' MSL.
Tree 2448' from DER, 749' left of centerline, 538' MSL.
Trees beginning 2621' from DER, 587' right of centerline, up to 551' MSL.
Tree 2641' from DER, 1000' left of centerline, 543' MSL.
Trees beginning 2649' from DER, 424' right of centerline, up to 558' MSL.
Trees beginning 2698' from DER, 196' right of centerline, up to 572' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026

CINCINNATI, OH (CON'T)

CINCINNATI MUNI/LUNKEN FLD (LUK) (CON'T)

Rwy 3 (CON'T), trees beginning 2814' from DER, 98' right of centerline, up to 574' MSL.
Trees beginning 2833' from DER, 984' left of centerline, up to 553' MSL.
Tree 2914' from DER, 316' left of centerline, 556' MSL.
Trees beginning 2954' from DER, 439' left of centerline, up to 561' MSL.
Trees beginning 3128' from DER, 730' left of centerline, up to 574' MSL.
Trees beginning 3336' from DER, 39' left of centerline, up to 585' MSL.
Trees beginning 3363' from DER, 537' right of centerline, up to 576' MSL.
Trees beginning 3596' from DER, 627' right of centerline, up to 578' MSL.
Trees beginning 3695' from DER, 589' right of centerline, up to 579' MSL.
Trees beginning 3843' from DER, 730' right of centerline, up to 103' AGL/584' MSL.
Trees beginning 1.1 NM from DER, 2295' left of centerline, up to 709' MSL.
Trees, terrain beginning 1.2 NM from DER, 2192' left of centerline, up to 807' MSL.
Trees, building, poles beginning 1.3 NM from DER, 1811' left of centerline, up to 70' AGL/875' MSL
Rwy 7, light poles 10' from DER, 59' right of centerline, 2' AGL/476' MSL.
Building 246' from DER, 553' left of centerline, 486' MSL.
Tree 530' from DER, 567' left of centerline, 26' AGL/498' MSL.
Trees beginning 706' from DER, 423' right of centerline, up to 521' MSL.
Trees beginning 946' from DER, 82' right of centerline, up to 538' MSL.
Tree 1155' from DER, 559' left of centerline, 33' AGL/505' MSL.
Trees beginning 1190' from DER, 84' left of centerline, up to 48' AGL/521' MSL.
Trees beginning 1512' from DER, 265' left of centerline, up to 50' AGL/524' MSL.
Trees beginning 1576' from DER, 30' left of centerline, up to 58' AGL/530' MSL.
Trees beginning 1718' from DER, 260' left of centerline, up to 532' MSL.
Trees beginning 1806' from DER, 316' left of centerline, up to 537' MSL.
Trees beginning 1810' from DER, 115' right of centerline, up to 550' MSL.
Trees beginning 2033' from DER, 300' left of centerline, up to 539' MSL.
Trees beginning 2116' from DER, 266' right of centerline, up to 77' AGL/551' MSL.
Trees beginning 2172' from DER, 21' right of centerline, up to 575' MSL.
Trees beginning 2272' from DER, 680' left of centerline, up to 545' MSL.
Tree 2425' from DER, 532' left of centerline, 549' MSL.
Trees beginning 2451' from DER, 729' left of centerline, up to 556' MSL.
Trees beginning 2499' from DER, 278' left of centerline, up to 572' MSL.
Trees beginning 2769' from DER, 16' left of centerline, up to 574' MSL.
Trees beginning 2879' from DER, on and right of centerline, up to 592' MSL.
Trees beginning 3002' from DER, 141' left of centerline, up to 100' AGL/576' MSL.
Trees beginning 3723' from DER, 1369' right of centerline, up to 668' MSL.
Trees, building, terrain beginning 3889' from DER, 1033' right of centerline, up to 694' MSL.
Trees beginning 4531' from DER, 1354' right of centerline, up to 709' MSL.
Trees beginning 4546' from DER, 1087' right of centerline, up to 731' MSL.
Trees beginning 1.1 NM from DER, 1899' right of centerline, up to 737' MSL.
Trees beginning 1.2 NM from DER, 1131' right of centerline, up to 782' MSL.
Trees, buildings beginning 1.2 NM from DER, 1224' right of centerline, up to 813' MSL.
Trees beginning 1.3 NM from DER, 1653' right of centerline, up to 79' AGL/823' MSL.
Tree 1.6 NM from DER, 2999' right of centerline, 759' MSL.
Rwy 21, vegetation 90' from DER, 436' right of centerline, 7' AGL/486' MSL.
Trees beginning 437' from DER, 602' left of centerline, up to 509' MSL.
Tree 748' from DER, 605' left of centerline, 511' MSL.
Trees beginning 835' from DER, 587' left of centerline, up to 522' MSL.
Trees beginning 945' from DER, 583' left of centerline, up to 531' MSL.
Trees beginning 1288' from DER, 720' left of centerline, up to 535' MSL.
Tree 1510' from DER, 880' right of centerline, 524' MSL.
Tree 1553' from DER, 747' right of centerline, 525' MSL.
Trees beginning 1590' from DER, 648' right of centerline, up to 527' MSL.
Trees beginning 1597' from DER, 635' left of centerline, up to 570' MSL.
Trees beginning 1693' from DER, 218' right of centerline, up to 543' MSL.
Trees beginning 1770' from DER, 576' left of centerline, up to 573' MSL.
Trees beginning 1962' from DER, 173' left of centerline, up to 575' MSL.
Tree 2236' from DER, 372' right of centerline, 546' MSL.
Tree 2246' from DER, 250' right of centerline, 66' AGL/547' MSL.
Trees beginning 2347' from DER, 424' right of centerline, up to 549' MSL.
Trees beginning 2529' from DER, 6' left of centerline, up to 588' MSL.
Tree 2538' from DER, 600' right of centerline, 550' MSL.
Trees beginning 2601' from DER, 725' right of centerline, up to 556' MSL.
Tree 2923' from DER, 84' right of centerline, 96' AGL/575' MSL.
Trees beginning 3044' from DER, 3' right of centerline, up to 104' AGL/580' MSL.
Tree 3254' from DER, 328' right of centerline, 105' AGL/582' MSL.
Trees beginning 3344' from DER, 285' right of centerline, up to 106' AGL/584' MSL.
CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

CINCINNATI, OH (CON'T)

CINCINNATI MUNI/LUNKEN FLD (LUK) (CON'T)

Rwy 21 (CON'T), trees beginning 3470' from DER, 42' right of centerline, up to 115' AGL/591' MSL.
Trees beginning 3614' from DER, 7' right of centerline, up to 135' AGL/597' MSL.
Tree 3868' from DER, 39' left of centerline, 129' AGL/589' MSL.
Trees beginning 3920' from DER, 111' left of centerline, up to 617' MSL.
Trees beginning 4007' from DER, 1406' left of centerline, up to 634' MSL.
Trees beginning 4102' from DER, 1321' left of centerline, up to 654' MSL.
Trees beginning 4376' from DER, 1254' left of centerline, up to 713' MSL.
Trees beginning 4614' from DER, 1152' left of centerline, up to 734' MSL.
Tree 1.4 NM from DER, 2928' right of centerline, 743' MSL.
Trees beginning 1.5 NM from DER, 2239' right of centerline, up to 876' MSL.
Trees, pole, terrain beginning 1.6 NM from DER, 1845' right of centerline, up to 890' MSL.
Building spires, building, tree beginning 1.9 NM from DER, 1589' right of centerline, up to 78' AGL/891' MSL.
Antennas, trees, towers, pole beginning 2 NM from DER, 259' right of centerline, up to 160' AGL/978' MSL.
Rwy 25, terrain 2' from DER, 417' left of centerline, 483' MSL.
Fence 79' from DER, 460' right of centerline, 487' MSL.
Buildings beginning 177' from DER, 154' left of centerline, up to 35' AGL/518' MSL.
Pole 182' from DER, 310' right of centerline, 511' MSL.
Trees, vehicle on road, transmission lines, poles, terrain, buildings beginning 195' from DER, on centerline, up to 67' AGL/551' MSL.
Tree, buildings, poles beginning 513' from DER, on and left of centerline, up to 549' MSL.
Tree, terrain beginning 597' from DER, 50' left of centerline, up to 552' MSL.
Trees, transmission lines, signs beginning 1176' from DER, 34' left of centerline, up to 553' MSL.
Trees beginning 1628' from DER, 281' right of centerline, up to 570' MSL.
Tree 3484' from DER, 393' right of centerline, 103' AGL/577' MSL.
Trees beginning 3531' from DER, 256' right of centerline, up to 589' MSL.
Trees, transmission line beginning 3650' from DER, 152' right of centerline, up to 604' MSL.
Tree 3733' from DER, 361' left of centerline, 101' AGL/578' MSL.
Trees beginning 3752' from DER, 119' left of centerline, up to 81' AGL/584' MSL.
Trees beginning 3753' from DER, 17' right of centerline, up to 605' MSL.
Trees beginning 3800' from DER, 288' right of centerline, up to 640' MSL.
Trees beginning 3830' from DER, 708' right of centerline, up to 660' MSL.
Trees beginning 3857' from DER, 45' left of centerline, up to 76' AGL/590' MSL.
Trees, transmission line beginning 3872' from DER, 175' right of centerline, up to 672' MSL.
Trees beginning 3896' from DER, 287' right of centerline, up to 708' MSL.
Trees beginning 3975' from DER, 159' right of centerline, up to 715' MSL.
Tree 4033' from DER, 1524' right of centerline, 721' MSL.
Trees beginning 4037' from DER, 167' left of centerline, up to 45' AGL/594' MSL.
Trees beginning 4049' from DER, 273' right of centerline, up to 740' MSL.
Tree, terrain beginning 4073' from DER, 495' right of centerline, up to 761' MSL.
Trees, terrain beginning 4096' from DER, 19' right of centerline, up to 779' MSL.
Tree 4104' from DER, 56' left of centerline, 87' AGL/600' MSL.
Trees beginning 4115' from DER, 553' left of centerline, up to 645' MSL.
Trees beginning 4139' from DER, 145' left of centerline, up to 106' AGL/651' MSL.
Trees beginning 4166' from DER, 270' left of centerline, up to 91' AGL/689' MSL.
Trees beginning 4184' from DER, 79' left of centerline, up to 77' AGL/704' MSL.
Trees beginning 4236' from DER, 172' left of centerline, up to 707' MSL.
Trees, terrain beginning 4284' from DER, 28' right of centerline, up to 800' MSL.
Trees beginning 4322' from DER, 30' left of centerline, up to 74' AGL/733' MSL.
Tree 4360' from DER, 520' left of centerline, 769' MSL.
Trees beginning 4374' from DER, 111' left of centerline, up to 780' MSL.
Trees beginning 4504' from DER, 482' left of centerline, up to 788' MSL.
Trees, terrain beginning 4512' from DER, 66' left of centerline, up to 797' MSL.
Tree, terrain, building beginning 4523' from DER, 39' right of centerline, up to 807' MSL.
Trees, building, terrain beginning 4690' from DER, 21' left of centerline, up to 814' MSL.
Trees, building, terrain beginning 4706' from DER, 81' right of centerline, up to 817' MSL.
Trees, terrain beginning 4830' from DER, 256' right of centerline, up to 825' MSL.
Trees, building, terrain beginning 4879' from DER, 137' right of centerline, up to 831' MSL.
Trees, terrain beginning 4939' from DER, 44' right of centerline, up to 843' MSL.
Tree 4973' from DER, 1637' left of centerline, 835' MSL.
Trees, terrain, buildings beginning 4980' from DER, 37' left of centerline, up to 862' MSL.
Trees beginning 5078' from DER, 340' right of centerline, up to 862' MSL.
Trees beginning 5133' from DER, 39' right of centerline, up to 864' MSL.
Trees, pole beginning 5206' from DER, 47' left of centerline, up to 869' MSL.
Trees beginning 5255' from DER, 292' right of centerline, up to 869' MSL.
Trees, transmission line beginning 5301' from DER, 136' right of centerline, up to 870' MSL.
Trees, transmission line beginning 5319' from DER, 36' right of centerline, up to 877' MSL.
Trees, terrain, buildings beginning 5394' from DER, 43' right of centerline, up to 903' MSL.
CON'T

CINCINNATI, OH (CON'T)

CINCINNATI MUNI/LUNKEN FLD (LUK) (CON'T)

Rwy 25 (CON'T), trees, building beginning 5507' from DER, 44' left of centerline, up to 894' MSL.
Trees, building, terrain, transmission line beginning 5706' from DER, 22' right of centerline, up to 914' MSL.
Trees, building beginning 5741' from DER, 30' left of centerline, up to 903' MSL.
Trees, buildings, terrain, transmission lines beginning 5849' from DER, 38' right of centerline, up to 83' AGL/919' MSL.
Trees, terrain, buildings, transmission lines, towers, antenna beginning 1 NM from DER, 16' left of centerline, up to 932 ' MSL.
Trees, buildings, terrain, transmission line beginning 1.1 NM from DER, 3' right of centerline, up to 92' AGL/943' MSL.
Tanks, trees, terrain, buildings, transmission lines beginning 1.4 NM from DER, 16' right of centerline, up to 210' AGL/1045' MSL.
Tree, transmission line, terrain, building beginning 1.4 NM from DER, 1' left of centerline, up to 919' MSL.
Trees, terrain, buildings, pole, tower beginning 1.5 NM from DER, 10' left of centerline, up to 83' AGL/926' MSL.

CIRCLEVILLE, OH

PICKAWAY COUNTY MEML (CYO)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 13NOV14 (21224) (FAA)

DEPARTURE PROCEDURE:

Rwy 1, climb heading 008° to 1300 before turning left.

TAKEOFF MINIMUMS:

Rwy 1, vehicle on road beginning 7' from DER, 447' right of centerline, up to 15' AGL/697' MSL.
Runway end identifier light with electrical system 41' from DER, 79' right of centerline, 5' AGL/687' MSL.
Runway end identifier light with electrical system 42' from DER, 82' left of centerline, 3' AGL/687' MSL.
Fence beginning 177' from DER, 250' left of centerline, up to 12' AGL/694' MSL.
Poles beginning 345' from DER, 518' right of centerline, up to 42' AGL/721' MSL.
Vehicle on road beginning 649' from DER, 16' left of centerline, up to 15' AGL/703' MSL.
Pole 667' from DER, 521' left of centerline, 29' AGL/711' MSL.
Tree 1887' from DER, 184' right of centerline, 54' AGL/740' MSL.
Tree 2251' from DER, 189' left of centerline, 59' AGL/745' MSL.
Rwy 19, terrain beginning 108' from DER, 267' right of centerline, up to 669' MSL.
Trees beginning 261' from DER, 64' left of centerline, up to 100' AGL/755' MSL.
Trees beginning 765' from DER, 99' right of centerline, up to 100' AGL/737' MSL.

CLEVELAND, OH

BURKE LAKEFRONT (BKL)

DIVERSE VECTOR AREA (RADAR VECTORS)

ORIG 01FEB18 (18032) (FAA)

Rwy 6L, heading as assigned by ATC; requires min climb of 220' per NM to 900.
Rwy 6R, heading as assigned by ATC; requires min climb of 290' per NM to 1000.
Rwy 24R, heading as assigned by ATC; requires min climb of 490' per NM to 900.

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 8 19MAR26 (26078) (FAA)

DEPARTURE PROCEDURE:

Use ZEYOU (OBSTACLE) (RNAV) DEPARTURE.

CLEVELAND-HOPKINS INTL (CLE)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 16A 24MAY18 (18144) (FAA)

DEPARTURE PROCEDURE:

Rwys 6L/R, 10, climbing left turn to intercept DJB VOR/DME R-082 inbound to 2600 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 10, tree 828' from DER, 656' right of centerline, 821' MSL.
Tree 880' from DER, 662' right of centerline, 830' MSL.
Sign 906' from DER, 717' left of centerline, 28' AGL/830' MSL.
Pole 1415' from DER, 785' right of centerline, 48' AGL/842' MSL.
Sign 2149' from DER, 955' left of centerline, 59' AGL/857' MSL.
Tower 3826' from DER, 1455' right of centerline, 137' AGL/922' MSL.
Rwy 24L, tree 1903' from DER, 492' left of centerline, 69' AGL/839' MSL.
Trees beginning 1959' from DER, 19' left of centerline, up to 78' AGL/848' MSL.
Pole, tree beginning 2273' from DER, 4' left of centerline, up to 79' AGL/849' MSL.
Rwy 24R, tower 2565' from DER, 1028' right of centerline, 191' AGL/870' MSL.
Tree 3653' from DER, 1047' left of centerline, 103' AGL/863' MSL.
Tree 3754' from DER, 861' left of centerline, 98' AGL/868' MSL.
Rwy 28, tree, building beginning 80' from DER, 424' right of centerline, up to 788' MSL.
Trees beginning 890' from DER, 212' right of centerline, up to 803' MSL.

CON'T

CLEVELAND, OH (CON'T)

CLEVELAND-HOPKINS INTL (CLE) (CON'T)

Rwy 28 (CON'T), trees beginning 1042' from DER, 26' right of centerline, up to 811' MSL.
Tree 1250' from DER, 107' left of centerline, 813' MSL.
Building, trees beginning 1267' from DER, 66' left of centerline, up to 92' AGL/851' MSL.
Pole 2970' from DER, 947' right of centerline, 82' AGL/842' MSL.

CUYAHOGA COUNTY (CGF)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 08NOV18 (18312) (FAA)

TAKEOFF OBSTACLE NOTES:
Rwy 6, terrain 86' from DER, 56' right of centerline, 878' MSL.
Terrain beginning 105' from DER, 26' left of centerline, up to 878' MSL.
Terrain 141' from DER, 37' right of centerline, 879' MSL.
Tree 1757' from DER, 929' left of centerline, 938' MSL.
Trees beginning 2163' from DER, 1008' right of centerline, up to 975' MSL.
Tree 2300' from DER, 1104' left of centerline, 961' MSL.
Trees beginning 2917' from DER, 105' right of centerline, up to 980' MSL.
Trees beginning 3607' from DER, 59' right of centerline, up to 982' MSL.
Rwy 24, pole 423' from DER, 423' right of centerline, 38' AGL/895' MSL.
NAVAID 530' from DER, 195' left of centerline, 19' AGL/894' MSL.
Tree, building beginning 617' from DER, 603' left of centerline, up to 940' MSL.
Tree 1141' from DER, 716' left of centerline, 945' MSL.
Trees beginning 1289' from DER, 555' left of centerline, up to 956' MSL.
Trees beginning 1366' from DER, 438' left of centerline, up to 970' MSL.
Trees beginning 1896' from DER, 95' left of centerline, up to 974' MSL.
Tree 1992' from DER, 76' right of centerline, 944' MSL.
Tree 2149' from DER, 8' right of centerline, 945' MSL.
Tree 3504' from DER, 31' right of centerline, 975' MSL.
Trees beginning 3616' from DER, 164' right of centerline, up to 979' MSL.
Tree 3714' from DER, 409' left of centerline, 975' MSL.
Tree 4153' from DER, 4' left of centerline, 980' MSL.

COLUMBUS, IN

COLUMBUS MUNI (BAK)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 25SEP08 (08269) (FAA)

TAKEOFF OBSTACLE NOTES:
Rwy 14, tree 1589' from DER, 306' right of centerline, 40' AGL/696' MSL.

COLUMBUS, OH

BOLTON FLD (TZR)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 15JAN09 (21112) (FAA)

DEPARTURE PROCEDURE:
Rwy 4, climb heading 037° to 1800 before turning east.

TAKEOFF OBSTACLE NOTES:
Rwy 4, tree 1091' from DER, 770' left of centerline, 53' AGL/959' MSL.
Tree 487' from DER, 356' right of centerline, 23' AGL/929' MSL.
Tree 1317' from DER, 452' right of centerline, 42' AGL/948' MSL.
Tree 1307' from DER, 50' left of centerline, 36' AGL/942' MSL.
Tree 1927' from DER, 135' right of centerline, 49' AGL/955' MSL.
Rwy 22, tree 1273' from DER, 720' right of centerline, 40' AGL/945' MSL.
Tree 712' from DER, 662' right of centerline, 25' AGL/927' MSL.
Tree 1411' from DER, 658' right of centerline 33' AGL/939' MSL.

JOHN GLENN COLUMBUS INTL (CMH)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 7A 17AUG17 (17229) (FAA)

DEPARTURE PROCEDURE:
Rwy 28L, climb heading 281° to 2100 before turning southbound.
Rwy 28R, climb heading 281° to 2000 before turning southbound.

TAKEOFF OBSTACLE NOTES:
Rwy 10L, sign 23' from DER, 348' right of centerline, 3' AGL/813' MSL.
Trees beginning 1308' from DER, 800' left of centerline, up to 79' AGL/869' MSL.
Trees beginning 1721' from DER, 764' right of centerline, up to 88' AGL/878' MSL.
CON'T

COLUMBUS, OH (CON'T)

JOHN GLENN COLUMBUS INTL (CMH) (CON'T)

Rwy 10R, aircraft on taxiway abeam DER, 290' right of centerline, up to 59' AGL/878' MSL.
Sign 42' from DER, 159' left of centerline, 6' AGL/817' MSL.
Poles and building beginning 934' from DER, 538' right of centerline, up to 42' AGL/852' MSL.
Trees beginning 1319' from DER, 225' right of centerline, up to 116' AGL/886' MSL.
Rwy 28L, building 42' from DER, 111' right of centerline, 6' AGL/810' MSL.
Trees beginning 1563' from DER, 870' left of centerline, up to 93' AGL/902' MSL.
Rwy 28R, tower 1260' from DER, 837' left of centerline, 75' AGL/875' MSL.
Trees and poles beginning 1228' from DER, 624' right of centerline, up to 72' AGL/882' MSL.
Light 5' from DER, 4' left of centerline, 1' AGL/815' MSL.

OHIO STATE UNIVERSITY (OSU)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 14JUL22 (22195) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 5, tree 675' from DER, 675' right of centerline, 22' AGL/910' MSL.
Buildings beginning 966' from DER, 528' left of centerline, up to 50' AGL/936' MSL.
Tree, building beginning 1122' from DER, 587' left of centerline, up to 937' MSL.
Tree 1303' from DER, 164' right of centerline, 52' AGL/929' MSL.
Trees beginning 1331' from DER, 43' left of centerline, up to 946' MSL.
Trees beginning 1374' from DER, 46' right of centerline, up to 52' AGL/931' MSL.
Trees beginning 1405' from DER, 98' right of centerline, up to 57' AGL/937' MSL.
Trees beginning 1408' from DER, 2' right of centerline, up to 61' AGL/941' MSL.
Trees beginning 1421' from DER, 46' right of centerline, up to 958' MSL.
Trees beginning 1474' from DER, 4' left of centerline, up to 73' AGL/954' MSL.
Trees beginning 1505' from DER, 40' left of centerline, up to 84' AGL/964' MSL.
Trees beginning 1532' from DER, 51' left of centerline, up to 967' MSL.
Trees beginning 1548' from DER, 25' left of centerline, up to 973' MSL.
Trees beginning 1633' from DER, 9' right of centerline, up to 962' MSL.
Trees beginning 1637' from DER, 20' left of centerline, up to 98' AGL/975' MSL.
Trees beginning 1685' from DER, 31' right of centerline, up to 966' MSL.
Trees beginning 1781' from DER, 69' right of centerline, up to 96' AGL/969' MSL.
Trees beginning 1859' from DER, 169' right of centerline, up to 107' AGL/973' MSL.
Trees beginning 1886' from DER, 156' right of centerline, up to 101' AGL/974' MSL.
Trees beginning 1891' from DER, 4' right of centerline, up to 101' AGL/976' MSL.
Trees beginning 1920' from DER, 7' right of centerline, up to 103' AGL/979' MSL.
Rwy 9L, sign 68' from DER, 225' left of centerline, 4' AGL/894' MSL.
Tree 909' from DER, 634' left of centerline, 44' AGL/923' MSL.
Trees beginning 914' from DER, 547' left of centerline, up to 50' AGL/930' MSL.
Trees beginning 949' from DER, 548' left of centerline, up to 52' AGL/931' MSL.
Tree 953' from DER, 686' left of centerline, 61' AGL/941' MSL.
Trees beginning 958' from DER, 515' left of centerline, up to 68' AGL/948' MSL.
Trees beginning 1016' from DER, 531' left of centerline, up to 958' MSL.
Trees beginning 1301' from DER, 702' left of centerline, up to 90' AGL/965' MSL.
Trees beginning 1328' from DER, 575' left of centerline, up to 966' MSL.
Trees beginning 1393' from DER, 340' left of centerline, up to 98' AGL/969' MSL.
Trees beginning 1477' from DER, 7' left of centerline, up to 107' AGL/973' MSL.
Trees beginning 1590' from DER, 230' right of centerline, up to 72' AGL/942' MSL.
Trees beginning 2000' from DER, 7' right of centerline, up to 960' MSL.
Rwy 9R, tree 64' from DER, 302' left of centerline, 15' AGL/894' MSL.
Trees beginning 201' from DER, 252' left of centerline, up to 918' MSL.
Tree 377' from DER, 511' right of centerline, 907' MSL.
Trees beginning 882' from DER, 378' right of centerline, up to 937' MSL.
Trees beginning 993' from DER, 265' left of centerline, up to 56' AGL/924' MSL.
Trees beginning 1033' from DER, 367' right of centerline, up to 940' MSL.
Trees beginning 1084' from DER, 270' left of centerline, up to 63' AGL/932' MSL.
Trees beginning 1299' from DER, 337' right of centerline, up to 943' MSL.
Trees beginning 1308' from DER, 531' left of centerline, up to 940' MSL.
Tree 1341' from DER, 515' right of centerline, 945' MSL.
Trees beginning 1400' from DER, 460' right of centerline, up to 955' MSL.
Trees beginning 1813' from DER, 556' right of centerline, up to 965' MSL.
Tree 2413' from DER, 961' left of centerline, 96' AGL/953' MSL.
Rwy 23, building 494' from DER, 468' left of centerline, 930' MSL.
Tree, building beginning 544' from DER, 396' left of centerline, up to 944' MSL.
Tree 658' from DER, 624' left of centerline, 945' MSL.
Stack, tank, trees beginning 673' from DER, 261' left of centerline, up to 60' AGL/963' MSL.
Tree 1197' from DER, 208' right of centerline, 45' AGL/942' MSL.
Tree 1919' from DER, 213' right of centerline, 58' AGL/957' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

COLUMBUS, OH (CON'T)

OHIO STATE UNIVERSITY (OSU) (CON'T)

Rwy 23 (CON'T), tree 1995' from DER, 257' right of centerline, 64' AGL/965' MSL.
Trees beginning 2000' from DER, 167' right of centerline, up to 78' AGL/978' MSL.
Tree 2081' from DER, 312' right of centerline, 989' MSL.
Trees beginning 2257' from DER, 351' right of centerline, up to 97' AGL/999' MSL.
Rwy 27L, lighting 4' from DER, 4' left of centerline, 2' AGL/903' MSL.
Tree 291' from DER, 575' left of centerline, 910' MSL.
Rwy 27R, sign 15' from DER, 247' left of centerline, 3' AGL/906' MSL.
Tree 2330' from DER, 861' right of centerline, 964' MSL.
Tree 2479' from DER, 789' right of centerline, 974' MSL.

CONNERSVILLE, IN

METTEL FLD (CEV)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 28SEP06 (21224) (FAA)

TAKEOFF MINIMUMS:
Rwys 4, 22, NA-VFR use only.
DEPARTURE PROCEDURE:
Rwy 18, climb via heading 185° to 1500 before proceeding on course.
TAKEOFF OBSTACLE NOTES:
Rwy 18, railroad 311' from DER, 580' left of centerline, 23' AGL/882' MSL.
Multiple trees beginning 2280' from DER, 100' left of centerline, up to 113' AGL/974' MSL.
Rwy 36, road 120' from DER, 301' right of centerline, 15' AGL/884' MSL.
Railroad 649' from DER, 578' right of centerline, 23' AGL/892' MSL.
Multiple trees beginning 3400' from DER, on centerline, up to 92' AGL/959' MSL.

COSHOCTON, OH

RICHARD DOWNING (I40)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1A 15SEP16 (16259) (FAA)

TAKEOFF MINIMUMS:
Rwys 4, 22, 300-1.
TAKEOFF OBSTACLE NOTES:
Rwy 4, tree 87'from DER, 402' left of centerline, 981' MSL.
Trees beginning 88' from DER, 460' left of centerline, up to 84' AGL/1040' MSL.
Tree 90' from DER, 226' right of centerline, 983' MSL.
Tree 628' from DER, 509' right of centerline, 1006' MSL.
Rwy 22, trees beginning 2' from DER, 290' left of centerline, up to 988' MSL.
Pole, wsk beginning 11' from DER, 57' right of centerline, up to 7' AGL/979' MSL.
Trees beginning 179' from DER, 275' left of centerline, up to 84' AGL/999' MSL.
Trees beginning 1033' from DER, 595' left of centerline, up to 1042' MSL.
Tree 2420' from DER, 123' right of centerline, 96' AGL/1035' MSL.
Tree 2442' from DER, 52' right of centerline, 104' AGL/1043' MSL.
Trees beginning 2443' from DER, 21' right of centerline, up to 106' AGL/1050' MSL.
Trees beginning 2496' from DER, 3' left of centerline, up to 103' AGL/1045' MSL.
Trees beginning 2503' from DER, on centerline, up to 103' AGL/1054' MSL.
Trees beginning 2550' from DER, 43' right of centerline, up to 105' AGL/1061' MSL.

29 OCT 2026 to 26 NOV 2026

CRAWFORDSVILLE, IN

CRAWFORDSVILLE RGNL (CFJ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 19MAR26 (26078) (FAA)

TAKEOFF OBSTACLE NOTES:
Rwy 5, sign 16' from DER, 200' left of centerline, 3' AGL/802' MSL.
Pole, terrain, vehicles on road, tree beginning 41' from DER, 55' left of centerline, up to 30' AGL/834' MSL.
Pole 805' from DER, 223' right of centerline, 27' AGL/829' MSL.
Tree 822' from DER, 96' left of centerline, 841' MSL.
Trees beginning 856' from DER, 124' left of centerline, up to 843' MSL.
Trees beginning 958' from DER, 214' left of centerline, up to 849' MSL.
Tree 1055' from DER, 284' left of centerline, 850' MSL.
Trees beginning 1115' from DER, 83' left of centerline, up to 856' MSL.
Trees beginning 1323' from DER, 125' left of centerline, up to 874' MSL.
Trees beginning 1540' from DER, 178' left of centerline, up to 885' MSL.
Tree 2838' from DER, 255' right of centerline, 873' MSL.
CON'T

CRAWFORDSVILLE, IN (CON'T)

CRAWFORDSVILLE RGNL (CFJ) (CON'T)

Rwy 23, tree 326' from DER, 508' left of centerline, 815' MSL.
Tree 557' from DER, 637' left of centerline, 867' MSL.
Trees beginning 575' from DER, 176' left of centerline, up to 873' MSL.
Tree 651' from DER, 618' right of centerline, 846' MSL.
Trees beginning 672' from DER, 506' right of centerline, up to 861' MSL.
Trees beginning 825' from DER, 205' right of centerline, up to 865' MSL.
Trees beginning 1053' from DER, 29' right of centerline, up to 867' MSL.
Tree 2641' from DER, 633' right of centerline, 872' MSL.
Tree 2736' from DER, 580' right of centerline, 874' MSL.
Tree 2759' from DER, 457' right of centerline, 878' MSL.
Trees beginning 2795' from DER, 384' right of centerline, up to 879' MSL.
Trees beginning 2903' from DER, 480' right of centerline, up to 887' MSL.
Tree 3595' from DER, 1150' left of centerline, 888' MSL.

DAYTON, OH

DAYTON/PHILLIPSBURG (3I7)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1A 16AUG18 (22251) (FAA)

TAKEOFF MINIMUMS:

Rwy 21, 300-1.

DAYTON/WRIGHT BROTHERS (MGY)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3A 21JUL16 (22307) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 2, multiple trees and road beginning 440' from DER, 257' left of centerline, up to 100' AGL/1053' MSL.
Multiple trees beginning 672' from DER, 17' right of centerline, up to 100' AGL/1017' MSL.
Rwy 20, multiple trees beginning 189' from DER, 494' left of centerline, up to 100' AGL/1009' MSL.
Multiple poles and trees beginning 323' from DER, 364' right of centerline, up to 100' AGL/1026' MSL.
Building 1195' from DER, 512' right of centerline, 50' AGL/972' MSL.

GREENE COUNTY/LEWIS A JACKSON RGNL (GDK)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4 19MAR26 (26078) (FAA)

DEPARTURE PROCEDURE:

Rwy 25, climb on heading 232° to 1700 before turning right.

TAKEOFF OBSTACLE NOTES:

Rwy 7, trees, wind indicator beginning 20' from DER, 133' right of centerline, up to 59' AGL/999' MSL.
Tree 73' from DER, 264' left of centerline, 983' MSL.
Trees beginning 111' from DER, 165' left of centerline, up to 986' MSL.
Trees beginning 642' from DER, 329' right of centerline, up to 1016' MSL.
Trees beginning 2361' from DER, 945' right of centerline, up to 1028' MSL.
Rwy 25, trees beginning 51' from DER, 491' left of centerline, up to 996' MSL.
Trees, transmission lines, poles beginning 176' from DER, 278' left of centerline, up to 998' MSL.
Trees beginning 266' from DER, 320' right of centerline, up to 954' MSL.
Transmission line, poles beginning 1122' from DER, 578' right of centerline, up to 81' AGL/972' MSL.
Pole 1409' from DER, 764' right of centerline, 992' MSL.
Transmission line 1410' from DER, 753' right of centerline, 137' AGL/1005' MSL.
Trees beginning 1834' from DER, 320' left of centerline, up to 1002' MSL.
Trees beginning 1983' from DER, 426' left of centerline, up to 127' AGL/1011' MSL.

JAMES M COX DAYTON INTL (DAY)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4 27APR17 (17117) (FAA)

TAKEOFF MINIMUMS:

Rwy 18, 300-1 or std w/min climb of 305 per NM to 1300.

TAKEOFF OBSTACLE NOTES:

Rwy 6R, tower 3128' from DER, 1114' right of centerline, 140' AGL/1101' MSL.
Rwy 18, trees beginning 1033' from DER, 77' right of centerline, up to 1048' MSL.
Tree 1047' from DER, 38' left of centerline, 1039' MSL.
Tree 1049' from DER, 326' left of centerline, 1040' MSL.
Tree 1050' from DER, 437' left of centerline, 1041' MSL.
Trees beginning 1051' from DER, 192' left of centerline, up to 1047' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

DAYTON, OH (CON'T)

JAMES M COX DAYTON INTL (DAY) (CON'T)

Rwy 18 (CON'T), wind indicator on building, steeple, pole, ant on building, tree beginning 1141' from DER, 195' left of centerline, up to 1049' MSL.
Trees beginning 1378' from DER, 325' left of centerline, up to 1056' MSL.
Trees beginning 1618' from DER, 244' left of centerline, up to 1060' MSL.
Tree 1631' from DER, 558' right of centerline, 1054' MSL.
Tree 1711' from DER, 185' left of centerline, 1066' MSL.
Trees beginning 1785' from DER, 311' left of centerline, up to 1072' MSL.
Trees beginning 1825' from DER, 210' left of centerline, up to 74' AGL/1079' MSL.
Tree 1832' from DER, 563' right of centerline, 1060' MSL.
Trees beginning 2013' from DER, 139' right of centerline, up to 1072' MSL.
Trees beginning 2322' from DER, 958' right of centerline, up to 1073' MSL.
Tree 2378' from DER, 916' left of centerline, 1089' MSL.
Trees beginning 2379' from DER, 141' left of centerline, up to 96' AGL/1095' MSL.
Tree 2574' from DER, 1075' right of centerline, 1094' MSL.
Tree 2578' from DER, 1098' right of centerline, 89' AGL/1096' MSL.
Trees beginning 2923' from DER, 412' left of centerline, up to 1098' MSL.
Tank 4227' from DER, 1469' left of centerline, 184' AGL/1168' MSL.
Rwy 24L, vehicles on road 200' from DER, crossing runway centerline, up to 15' AGL/1021' MSL.
Tree 992' from DER, 522' left of centerline, 1049' MSL.
Tree 1139' from DER, 740' left of centerline, 1056' MSL.
Trees beginning 1722' from DER, 527' left of centerline, up to 1061' MSL.
Rwy 36, airfield light beginning 5' from DER, 4' right of centerline, up to 2' AGL/992' MSL.
Tree 1947' from DER, 939' left of centerline, 1040' MSL.

MORAINE AIR PARK (I73)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 03NOV22 (22307) (FAA)

TAKEOFF MINIMUMS:
Rwy 8, std w/min climb of 272' per NM to 2400 or 1700-3 for VCOA.
Rwy 26, std w/min climb of 269' per NM to 2200 or 1700-3 for VCOA.
DEPARTURE PROCEDURE:
Rwy 8, climb on heading 084° to 1700 before proceeding on course.
Rwy 26, climb on heading 264° to 1900 before proceeding on course.
VCOA:
Rwys 8, 26, obtain ATC approval for VCOA when requesting IFR clearance. Climb in visual conditions to cross Moraine Air Park at or above 2300 before proceeding on course.
TAKEOFF OBSTACLE NOTES:
Rwy 8, airport equipment 172' from DER, 112' right of centerline, 10' AGL/730' MSL.
Airport equipment, bldg, catenary, sign, pole beginning 363' from DER, 54' left of centerline, up to 50' AGL/770' MSL.
Bldgs beginning 532' from DER, 417' right of centerline, up to 30' AGL/750' MSL.
Pole 892' from DER, 344' right of centerline, 37' AGL/757' MSL.
Pole 895' from DER, 347' right of centerline, 37' AGL/772' MSL.
Poles, catenary beginning 962' from DER, 19' right of centerline, up to 37' AGL/775' MSL.
Poles beginning 1422' from DER, 102' left of centerline, up to 37' AGL/772' MSL.
Rwy 26, catenaries beginning 1351' from DER, 5' left of centerline, up to 50' AGL/770' MSL.
Pole 1364' from DER, 172' right of centerline, 37' AGL/757' MSL.
Catenaries, pole, silo beginning 1400' from DER, 58' right of centerline, up to 50' AGL/770' MSL.

29 OCT 2026 to 26 NOV 2026

DEFIANCE, OH

DEFIANCE MEML (DFI)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 10MAR11 (21224) (FAA)

TAKEOFF OBSTACLE NOTES:
Rwy 12, trees beginning 398' from DER, 155' right of centerline, up to 50' AGL/749' MSL.
Terrain beginning 62' from DER, 1' right of centerline, up to 706' MSL.
Vehicle on road 833' from DER, 286' left of centerline, up to 15' AGL/724' MSL.
Rwy 30, trees and power lines beginning 527' from DER, beginning 246' left to right of centerline, up to 50' AGL/759' MSL.
Vehicle on road beginning 527' from DER, 246' left to right of centerline, up to 15' AGL/724' MSL.
Terrain beginning 36' from DER, 17' right of centerline, up to 712' MSL.
Terrain beginning 116' from DER, 353' left of centerline, up to 712' MSL.

26190

DELAWARE, OH

DELAWARE MUNI/JIM MOORE FLD (DLZ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 12JUN25 (25163) (FAA)

TAKEOFF MINIMUMS:

Rwy 10, 300-1¾ or std w/min climb of 205'/NM to 1200.

TAKEOFF OBSTACLE NOTES:

Rwy 10, trees beginning 884' from DER, 507' left of centerline, up to 1014' MSL.
Transmission line beginning 1179' from DER, 288' right of centerline, up to 48' AGL/987' MSL.
Tower 1 NM from DER, 2029' right of centerline, 180' AGL/1107' MSL.
Rwy 28, wind indicator, light poles beginning 7' from DER, 103' right of centerline, up to 9' AGL/950' MSL.
Terrain 35' from DER, 189' left of centerline, 950' MSL.
Transmission line beginning 992' from DER, 599' left of centerline, up to 61' AGL/1005' MSL.
Transmission line 1126' from DER, 695' right of centerline, 45' AGL/988' MSL.
Tree 1233' from DER, 743' right of centerline, 990' MSL.

DELPHI, IN

DELPHI MUNI (1I9)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 15JUN23 (23166) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 18, pole 926' from DER, 643' left of centerline, 26' AGL/702' MSL.
Pole beginning 929' from DER, 283' right of centerline, up to 29' AGL/697' MSL.
Rwy 36, light poles 1' from DER, 104' right of centerline, 2' AGL/671' MSL.
Building 63' from DER, 334' left of centerline, 21' AGL/693' MSL.
Tree, building, traverse way, pole beginning 127' from DER, 8' left of centerline, up to 55' AGL/727' MSL.
Traverse way beginning 315' from DER, 86' right of centerline, up to 685' MSL.
Tree 1435' from DER, 614' right of centerline, 55' AGL/715' MSL.

EAST LIVERPOOL, OH

COLUMBIANA COUNTY (02G)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2A 17AUG17 (17229) (FAA)

TAKEOFF MINIMUMS:

Rwy 25, 600-1¾ or std w/min climb gradient of 445' per NM to 1700.

DEPARTURE PROCEDURE:

Rwy 25, climb heading of 249° to 1700 before turning right.

TAKEOFF OBSTACLE NOTES:

Rwy 7, trees beginning abeam DER, 392' left of centerline, up to 71' AGL/1224' MSL.
Tree 156' from DER, 449' right of centerline, 1205' MSL.
Trees beginning 164' from DER, 11' left of centerline, up to 101' AGL/1231' MSL.
Trees beginning 182' from DER, 75' right of centerline, up to 1218' MSL.
Trees beginning 1892' from DER, 635' right of centerline, up to 1219' MSL.
Tree 2212' from DER, 850' right of centerline, 1221' MSL.
Tree 2338' from DER, 840' right of centerline, 1224' MSL.
Tree 2859' from DER, 506' left of centerline, 1236' MSL.
Rwy 25, ground 7' from DER, 401' right of centerline, 1152' MSL.
Ground beginning 104' from DER, 297' right of centerline, up to 1159' MSL.
Ground 118' from DER, 256' left of centerline, 1148' MSL.
Trees beginning 141' from DER, 28' left of centerline, up to 82' AGL/1226' MSL.
Trees beginning 899' from DER, 84' right of centerline, up to 1220' MSL.
Tree 3443' from DER, 611' right of centerline, 1240' MSL.
Tree 3499' from DER, 359' right of centerline, 1242' MSL.
Tree 3531' from DER, 1397' right of centerline, 1247' MSL.
Tree 3533' from DER, 935' right of centerline, 1276' MSL.
Trees beginning 3535' from DER, 161' right of centerline, up to 1287' MSL.
Trees beginning 3653' from DER, 391' right of centerline, up to 1288' MSL.
Trees beginning 3701' from DER, 61' right of centerline, up to 1290' MSL.
Trees beginning 3748' from DER, 231' right of centerline, up to 1315' MSL.
Tree 3748' from DER, 891' right of centerline, 1298' MSL.
Trees beginning 3801' from DER, 44' right of centerline, up to 1322' MSL.
Trees beginning 3854' from DER, 358' right of centerline, up to 1332' MSL.
Tree, ground beginning 3907' from DER, 282' right of centerline, up to 1350' MSL.
Trees beginning 4863' from DER, 804' left of centerline, up to 1279' MSL.
Trees beginning 5051' from DER, 651' left of centerline, up to 1292' MSL.
Trees beginning 5174' from DER, 546' left of centerline, up to 1296' MSL.
Trees beginning 5280' from DER, 328' left of centerline, up to 1311' MSL.
CON'T

EAST LIVERPOOL, OH (CON'T)

COLUMBIANA COUNTY (02G) (CON'T)

Rwy 25 (CON'T), trees beginning 5491' from DER, 59' left of centerline, up to 1316' MSL.
Trees beginning 5860' from DER, 639' right of centerline, up to 1353' MSL.
Trees beginning 5860' from DER, 120' right of centerline, up to 1355' MSL.
Trees beginning 5966' from DER, 1071' right of centerline, up to 1356' MSL.
Trees beginning 6019' from DER, 795' right of centerline, up to 1357' MSL.
Trees beginning 6072' from DER, 15' right of centerline, up to 1364' MSL.
Trees beginning 6072' from DER, 203' right of centerline, up to 1365' MSL.
Trees beginning 1 NM from DER, 26' right of centerline, up to 1389' MSL.
Trees beginning 1 NM from DER, 25' left of centerline, up to 1325' MSL.
Trees beginning 1 NM from DER, 332' right of centerline, up to 1393' MSL.
Trees beginning 1 NM from DER, 84' right of centerline, up to 1406' MSL.
Tree, ground beginning 1 NM from DER, 430' right of centerline, up to 76' AGL/1418' MSL.
Trees beginning 1 NM from DER, 943' right of centerline, up to 1416' MSL.
Transmission tower, tree, ground beginning 1.1 NM from DER, 687' right of centerline, up to 122' AGL/1450' MSL.
Tree 1.4 NM from DER, 2655' left of centerline, 1359' MSL.
Tree 1.4 NM from DER, 2747' left of centerline, 1360' MSL.

ELKHART, IN

ELKHART MUNI (EKM)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 22SEP11 (11265) (FAA)

TAKEOFF OBSTACLE NOTES:
Rwy 9, trees beginning 2039' from DER, 768' right of centerline, up to 68' AGL/845' MSL.
Trees beginning 2649' from DER, 774' left of centerline, up to 90' AGL/867' MSL.
Rwy 18, trees and spire beginning 592' from DER, 63' right of centerline, up to 63' AGL/835' MSL.
Trees beginning 508' from DER, 87' left of centerline, up to 71' AGL/843' MSL.
Rwy 27, trees beginning 1195' from DER, 241' right of centerline, up to 90' AGL/861' MSL.
Trees beginning 1714' from DER, 49' left of centerline, up to 89' AGL/860' MSL.
Rwy 36, tree and building beginning 845' from DER, 212' right of centerline, up to 58' AGL/836' MSL.
Trees beginning1193' from DER, 240' left of centerline, up to 61' AGL/839' MSL.

ELYRIA, OH

ELYRIA (1G1)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2A 19MAR26 (26078) (FAA)

TAKEOFF OBSTACLE NOTES:
Rwy 9, trees beginning 14' from DER, 91' right of centerline, up to 100' AGL/860' MSL.
Trees beginning 92' from DER, 146' left of centerline, up to 100' AGL/860' MSL.
Rwy 27, fence 87' from DER, 150' right of centerline, 5' AGL/760' MSL.
Trees, poles beginning 99' from DER, 22' left of centerline, up to 100' AGL/855' MSL.
Bldg, poles beginning 225' from DER, 115' right of centerline, up to 40' AGL/795' MSL.
Trees, bldg beginning 563' from DER, 63' right of centerline, up to 100' AGL/855' MSL.

EVANSVILLE, IN

EVANSVILLE RGNL (EVV)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 9B 26DEC24 (25023) (FAA)

TAKEOFF MINIMUMS:
Rwys 9, 27, NA-Environmental.
Rwy 36, 300-1½ or std w/min climb of 635'/NM to 700.

TAKEOFF OBSTACLE NOTES:
Rwy 18, electrical system 10' from DER, 80' right of centerline, 13' AGL/396' MSL.
Vehicle on roadway 265' from DER, 420' right of centerline, 398' MSL.
Vehicle on roadway 526' from DER, 17' left of centerline, 403' MSL.
Building 560' from DER, 354' right of centerline, 21' AGL/403' MSL.
Building 570' from DER, 632' right of centerline, 45' AGL/427' MSL.
Buildings beginning 758' from DER, 137' right of centerline, up to 53' AGL/435' MSL.
Tree 1595' from DER, 162' left of centerline, 51' AGL/433' MSL.
Building 1929' from DER, 460' right of centerline, 66' AGL/447' MSL.
Transmission line 4136' from DER, 1568' left of centerline, 132' AGL/513' MSL.
Rwy 22, vertical structure, building beginning 142' from DER, 401' left of centerline, up to 18' AGL/401' MSL.
Tower 165' from DER, 398' left of centerline, 45' AGL/429' MSL.
CON'T

EVANSVILLE, IN (CON'T)

EVANSVILLE RGNL (EVV) (CON'T)

Rwy 36, tree, building beginning 2160' from DER, 479' right of centerline, up to 105' AGL/567' MSL.
Trees beginning 4224' from DER, 1024' right of centerline, up to 101' AGL/588' MSL.
Trees 5130' from DER, 1791' right of centerline, 100' AGL/593' MSL.
Trees 5741' from DER, 2019' right of centerline, 100' AGL/602' MSL.
Trees 5963' from DER, 2064' left of centerline, 100' AGL/563' MSL.
Trees beginning 6045' from DER, 1150' right of centerline, up to 100' AGL/606' MSL.
Trees beginning 1 NM from DER, 1776' right of centerline, up to 126' AGL/618' MSL.
Trees beginning 1 NM from DER, 2070' left of centerline, up to 100' AGL/586' MSL.
Trees 1.2 NM from DER, 2222' right of centerline, 100' AGL/593' MSL.

FINDLAY, OH

FINDLAY (FDY)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 06DEC18 (18340) (FAA)

TAKEOFF MINIMUMS:

Rwy 25, 300-1⅝ or std w/min climb of 210' per NM to 1100, or alternatively with std takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1400' prior to DER.

TAKEOFF OBSTACLE NOTES:

Rwy 7, road with vehicles beginning 55' from DER, 308' right of centerline, up to 15' AGL/821' MSL.
Wall, pole beginning 121' from DER, 48' left of centerline, up to 10' AGL/816' MSL.
Tree, road with vehicles, pole beginning 154' from DER, 69' right of centerline, up to 32' AGL/838' MSL.
Road with vehicles beginning 210' from DER, 1' left of centerline, up to 15' AGL/821' MSL.
Trees beginning 279' from DER, 45' right of centerline, up to 33' AGL/839' MSL.
Tree, pole, building beginning 338' from DER, 33' left of centerline, up to 26' AGL/832' MSL.
Tree 1715' from DER, 959' right of centerline, 54' AGL/860' MSL.
Trees beginning 1846' from DER, 407' right of centerline, up to 64' AGL/870' MSL.
Building 2374' from DER, 1054' right of centerline, 110' AGL/916' MSL.
Building, tree, wind indicator beginning 2417' from DER, 109' right of centerline, up to 121' AGL/927' MSL.
Rwy 18, tree 2786' from DER, 150' left of centerline, 876' MSL.
Rwy 25, fence, vegetation beginning 26' from DER, 141' left of centerline, up to 6' AGL/799' MSL.
Road with vehicles beginning 133' from DER, 108' right of centerline, up to 15' AGL/803' MSL.
Sign, tree, pole beginning 473' from DER, 421' right of centerline, up to 64' AGL/852' MSL.
Tree, pole, road with vehicles beginning 785' from DER, 397' right of centerline, up to 15' AGL/802' MSL.
Elevator, tree beginning 1824' from DER, 295' right of centerline, up to 78' AGL/869' MSL.
Trees beginning 2207' from DER, 454' right of centerline, up to 88' AGL/876' MSL.
Elevator 1.2 NM from DER, 1040' right of centerline, 206' AGL/999' MSL.
Elevator 1.3 NM from DER, 1114' right of centerline, 207' AGL/1000' MSL.
Rwy 36, pole 1191' from DER, 742' right of centerline, 39' AGL/835' MSL.
Tree 1559' from DER, 498' left of centerline, 51' AGL/847' MSL.

29 OCT 2026 to 26 NOV 2026

FORT WAYNE, IN

FORT WAYNE INTL (FWA)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 17SEP15 (15260) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 5, lighted structures beginning 9' from DER, left and right of centerline, up to 3' AGL/800' MSL.
Fence and trees beginning 152' from DER, 521' right of centerline, up to 42' AGL/842' MSL.
Railroad 834' from DER, 582' right of centerline, 23' AGL/820' MSL.
Trees beginning 927' from DER, 499' left of centerline, 40' AGL/836' MSL.
Rwy 9, lighted structures beginning 11' from DER, left and right of centerline, up to 2' AGL/794' MSL.
Pole 86' from DER, 442' right of centerline, 28' AGL/820' MSL.
Pole 380' from DER, 505' right of centerline, 32' AGL/822' MSL.
Tower 3124' from DER, 1109' left of centerline, 111' AGL/910' MSL.
Rwy 14, lighted structures beginning 9' from DER, left and right of centerline, up 2' AGL/797' MSL.
Tree 1079' from DER, 667' left of centerline, 23' AGL/825' MSL.
Rwy 23, lighted structures beginning 8' from DER, left and right of centerline, up to 2' AGL/815' MSL.
Rwy 27, lighted structures beginning 9' from DER, 48' left of centerline, up 2' AGL/800' MSL.
Fences beginning 28' from DER, 470' right of centerline, up to 6' AGL/804' MSL.
Tower 194' from DER, 523' left of centerline, 19' AGL/809' MSL.
Obstruction light 370' from DER, 230' left of centerline, 14' AGL/812' MSL.
Trees beginning 3587' from DER, left and right of centerline, up to 104' AGL/910' MSL.
Rwy 32, lighted structures beginning 9' from DER, left and right of centerline, up to 2' AGL/803' MSL.
Trees beginning 3672' from DER, 611' left of centerline, up to 100' AGL/901' MSL.

26190

FORT WAYNE, IN (CON'T)

SMITH FLD (SMD)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 5 18NOV10 (21168) (FAA)

TAKEOFF MINIMUMS:

Rwy 23, 800-3 or std w/min climb of 420' per NM to 1900.

DEPARTURE PROCEDURE:

Rwy 13, climb on heading between 133° CW to 185° from DER or climb on heading between 313° CW to 133° from DER to 2700 before proceeding on course or min. climb of 250' per NM to 2000 for all other courses.

Rwy 23, climb on heading 236° to 1900 before proceeding on course.

Rwy 31, climb on heading between 313° CW to 133° from DER or climb on heading between 250° CW to 313° from DER to 2700 before proceeding on course or min. climb of 250' per NM to 1900 for all other courses.

TAKEOFF OBSTACLE NOTES:

Rwy 5, vehicle on road 465' from DER, on centerline, 15' AGL/844' MSL.

Trees, light poles, flag poles, power poles, buildings, bus garages and cell tower beginning 345' from DER, 34' right of centerline, up to 153' AGL/974' MSL.

Trees, buildings and light poles beginning 234' from DER, 11' left of centerline, up to 72' AGL/896' MSL.

Rwy 13, vehicle on road 458' from DER, on centerline, 15' AGL/842' MSL.

Trees, houses and light pole beginning 21' from DER, 38' right of centerline, up to 100' AGL/929' MSL.

Trees, buildings, power poles, hanger, terminal, light pole and flag pole beginning 330' from DER, 25' left of centerline, up to 128' AGL/ 936' MSL.

Rwy 23, power poles, light poles, trees, building, house and shed beginning 469' from DER, 6' right of centerline, up to 82' AGL/909' MSL.

Trees, houses and light poles beginning 193' from DER, 43' left of centerline, up to 81' AGL/906' MSL.

Rwy 31, trees, buildings, power poles, garages, light pole and antenna beginning 237' from DER, 30' right of centerline, up to 95' AGL/936' MSL.

Trees and vert tank beginning 488' from DER, 202' left of centerline, up to 73' AGL/910' MSL.

FOSTORIA, OH

DONALD P MILLER (FZI)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 03JUN10 (25163) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, trees beginning 343' from DER, 584' left of centerline, up to 74' AGL/823' MSL.

Trees beginning 26' from DER, 277' right of centerline, up to 75' AGL/820' MSL.

Rwy 27, trees beginning 938' from DER, 342' left of centerline, up to 100' AGL/859' MSL.

Trees beginning 379' from DER, 444' right of centerline, up to 64' AGL/806' MSL.

Building 2' from DER, 500' left of centerline, 8' AGL/758' MSL.

Building 262' from DER, 523' right of centerline, 34' AGL/776' MSL.

Silo 292' from DER, 376' right of centerline, 36' AGL/778' MSL.

Pole 898' from DER, 413' right of centerline, 39' AGL/778' MSL.

Power pole 961' from DER, 562' right of centerline, 48' AGL/790' MSL.

29 OCT 2026 to 26 NOV 2026

FRANKFORT, IN

FRANKFORT CLINTON COUNTY RGNL (FKR)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 30OCT25 (25303) (FAA)

TAKEOFF MINIMUMS:

Rwy 27, 300-1⅛ or std w/min climb of 220' per NM to 1100.

TAKEOFF OBSTACLE NOTES:

Rwy 4, trees beginning 14' from DER, 138' left of centerline, up to 55' AGL/912' MSL.

Trees beginning 25' from DER, 224' right of centerline, up to 55' AGL/909' MSL.

Trees beginning 265' from DER, 29' left of centerline, up to 55' AGL/915' MSL.

Trees beginning 276' from DER, 54' right of centerline, up to 55' AGL/912' MSL.

Trees beginning 658' from DER, 75' right of centerline, up to 55' AGL/915' MSL.

Building 2675' from DER, 441' left of centerline, 90' AGL/947' MSL.

Building, industrial system beginning 3064' from DER, 33' right of centerline, up to 90' AGL/947' MSL.

Rwy 9, vegetation beginning 22' from DER, 324' right of centerline, up to 865' MSL.

Vegetation 66' from DER, 288' left of centerline, 865' MSL.

Tree 2765' from DER, 1208' right of centerline, 954' MSL.

Rwy 22, vegetation 186' from DER, 103' left of centerline, 866' MSL.

Trees, pole beginning 240' from DER, 7' left of centerline, up to 55' AGL/912' MSL.

Trees beginning 1647' from DER, 14' right of centerline, up to 55' AGL/912' MSL.

Trees beginning 1908' from DER, 35' right of centerline, up to 55' AGL/915' MSL.

Trees beginning 2139' from DER, 327' left of centerline, up to 55' AGL/915' MSL.

Rwy 27, vegetation 88' from DER, 442' left of centerline, 866' MSL.

Vegetation 110' from DER, 172' right of centerline, 862' MSL.

Tree 3143' from DER, 905' left of centerline, 942' MSL.

FREMONT, OH

FREMONT (14G)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 22OCT09 (09295) (FAA)

TAKEOFF MINIMUMS:

Rwys 18, 36, NA-Environmental.

TAKEOFF OBSTACLE NOTES:

Rwy 9, train 268' from DER, 516' right of centerline, 23' AGL/677' MSL.
Trees beginning 3269' from DER, 1265' right of centerline, up to 100' AGL/754' MSL.
Multiple trees and buildings beginning 320' from DER, left and right of centerline, up to 100' AGL/749' MSL.
Rwy 27, road 65' from DER, 4' right of centerline, 15' AGL/669' MSL.
Trees beginning 2230' from DER, 834' left of centerline, up to 100' AGL/754' MSL.

SANDUSKY COUNTY RGNL (S24)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 25AUG11 (11237) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 6, REILs 39' from DER, 93' right of centerline, 8' AGL/659' MSL.
REILs 39' from DER, 93' left of centerline, 7' AGL/658' MSL.
Trees beginning 796' from DER, 709' left of centerline, up to 91' AGL/737' MSL.
Rwy 24, REILs 41' from DER, 94' right of centerline, 7' AGL/668' MSL.
REILs 41' from DER, 93' left of centerline, 7' AGL/668' MSL.
Trees beginning 1569' from DER, left and right of centerline, up to 145' AGL/786' MSL.

FRENCH LICK, IN

FRENCH LICK MUNI (FRH)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 10APR08 (08101) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 8, terrain 59' from DER, 86' left of centerline, 0' AGL/799' MSL.
Trees beginning 184' from DER, 391' left of centerline, up to 100' AGL/889' MSL.
Trees beginning 215' from DER, 148' right of centerline, up to 100' AGL/849' MSL.
Rwy 26, trees beginning 429' from DER, 90' left of centerline, up to 100' AGL/849' MSL.
Trees beginning 580' from DER, 57' right of centerline, up to 100' AGL/909' MSL.

29 OCT 2026 to 26 NOV 2026

GALION, OH

GALION MUNI (GQQ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 25AUG11 (11237) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 5, trees beginning 354' from DER, 335' right of centerline, up to 50' AGL/1269' MSL.
Rwy 23, vehicles on road beginning 0' from DER, 348' right of centerline, up to 15' AGL/1244' MSL.
Vehicles on road beginning 0' from DER, 362' left of centerline, up to 17' AGL/1236' MSL.
Train and power lines 0' from DER, 351' left of centerline, up to 30' AGL/1252' MSL.
Trees beginning 341' from DER, right and left of centerline, up to 50' AGL/1279' MSL.

GALLIPOLIS, OH

GALLIA-MEIGS RGNL (GAS)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 20JUN19 (19171) (FAA)

TAKEOFF MINIMUMS:

Rwy 5, 400-2½ or std w/min climb of 465' per NM to 1300.
Rwy 23, 300-1 w/min climb of 350' per NM to 1600 or std w/min climb of 460' per NM to 1300 or 1300-3 for VCOA.

DEPARTURE PROCEDURE:

Rwy 5, climb heading 55° to 1800 before proceeding on course.
Rwy 23, climb heading 235° to 1200 before proceeding on course.

VCOA:

Rwy 23, obtain ATC approval for VCOA when requesting IFR clearance. Climb in visual conditions to cross Gallia-Meigs Rgnl airport at or above 1700 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 5, vehicle on road 5' from DER, 391' left of centerline, 17' AGL/586' MSL.
Tree and power poles beginning 72' from DER, 388' right of centerline, up to 100' AGL/669' MSL.
Tree, sign, light pole beginning 99' from DER, 326' left of centerline, up to 100' AGL/659' MSL.
Tree 293' from DER, 409' right of centerline, 100' AGL/669' MSL.
Trees beginning 426' from DER, 346' right of centerline, up to 100' AGL/669' MSL.

CON'T

GALLIPOLIS, OH (CON'T)

GALLIA-MEIGS RGNL (GAS) (CON'T)

Rwy 5 (CON'T), trees, light pole, vehicle on road beginning 438' from DER, 267' left of centerline, up to 100' AGL/669' MSL.
Vehicle on road 935' from DER, on and left of centerline, 17' AGL/586' MSL.
Tree and vehicle on overpass beginning 937' from DER, 440' left of centerline, up to 100' AGL/669' MSL.
Sign 1124' from DER, 285' right of centerline, 30' AGL/599' MSL.
Trees beginning 1297' from DER, 113' right of centerline, up to 100' AGL/669' MSL.
Trees beginning 1.5 NM from DER, 1270' right of centerline, up to 940' MSL.
Rwy 23, vehicles on road, train beginning 2' from DER, 207' right of centerline, up to 15' AGL/594' MSL.
Trees beginning 4' from DER, 451' left of centerline, up to 100' AGL/669' MSL.
Power poles, train 90' from DER, 407' right of centerline, up to 30' AGL/599' MSL.
Vehicles on road beginning 179' from DER, on and left of centerline, up to 15' AGL/575' MSL.
Tree 187' from DER, 424' left of centerline, 100' AGL/669' MSL.
Vehicle on road 551' from DER, 70' left of centerline, 15' AGL/575' MSL.
Buildings beginning 923' from DER, 220' left of centerline, up to 40' AGL/609' MSL.
Power poles, tank, tree beginning 1238' from DER, 510' left of centerline, up to 50' AGL/619' MSL.
Trees beginning 2322' from DER, 1074' right of centerline, up to 100' AGL/699' MSL.

GARY/CHICAGO, IN

GARY/CHICAGO INTL (GYY)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 9 19MAR26 (26078) (FAA)

TAKEOFF MINIMUMS:

Rwy 2, 300-1½ or std w/min climb of 330'/NM to 900.

DEPARTURE PROCEDURE:

Rwy 20, climb on heading 203° to 1300 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 2, pole, vehicle on road, tree, building beginning 553' from DER, 1' right of centerline, up to 26' AGL/617' MSL.
Tree 1488' from DER, 235' left of centerline, 56' AGL/647' MSL.
Tower 3431' from DER, 1125' right of centerline, 120' AGL/708' MSL.
Transmission line tower, tower, smokestack beginning 4433' from DER, 1004' right of centerline, up to 148' AGL/739' MSL.
Transmission line towers beginning 4597' from DER, 1079' left of centerline, up to 137' AGL/731' MSL.
Tank 4922' from DER, 1425' right of centerline, 199' AGL/791' MSL.
Smokestack 4928' from DER, 1417' right of centerline, 201' AGL/792' MSL.
Tower 5920' from DER, 572' left of centerline, 199' AGL/785' MSL.
Rwy 12, electrical system 199' from DER, 5' left of centerline, 8' AGL/596' MSL.
Pole 790' from DER, 619' right of centerline, 30' AGL/621' MSL.
Pole, trees beginning 847' from DER, 257' right of centerline, up to 29' AGL/623' MSL.
Pole 1011' from DER, 728' right of centerline, 30' AGL/629' MSL.
Trees beginning 1615' from DER, 744' left of centerline, up to 65' AGL/656' MSL.
Tree 1635' from DER, 612' right of centerline, 46' AGL/640' MSL.
Trees beginning 1680' from DER, 219' right of centerline, up to 59' AGL/652' MSL.
Pole 2519' from DER, 411' right of centerline, 61' AGL/658' MSL.
Tree 2680' from DER, 1035' left of centerline, 81' AGL/666' MSL.
Tree, pole beginning 2756' from DER, 236' right of centerline, up to 76' AGL/667' MSL.
Trees beginning 2882' from DER, 513' right of centerline, up to 86' AGL/675' MSL.
Tree 3363' from DER, 1267' right of centerline, 87' AGL/678' MSL.
Antenna, tower beginning 4245' from DER, 446' left of centerline, up to 102' AGL/700' MSL.
Rwy 20, tree, pole, vehicles on road beginning 202' from DER, 1' right of centerline, up to 79' AGL/668' MSL.
Poles beginning 847' from DER, 60' left of centerline, up to 35' AGL/634' MSL.
Poles, vehicle on highway beginning 957' from DER, 14' left of centerline, up to 35' AGL/635' MSL.
Pole 1185' from DER, 665' right of centerline, 88' AGL/674' MSL.
Poles beginning 1186' from DER, 79' right of centerline, up to 35' AGL/676' MSL.
Pole 1320' from DER, 766' right of centerline, 35' AGL/681' MSL.
Tree 1925' from DER, 79' left of centerline, 63' AGL/658' MSL.
Pole 3154' from DER, 424' right of centerline, 96' AGL/685' MSL.
Tower 4527' from DER, 868' right of centerline, 118' AGL/716' MSL.
Rwy 30, poles beginning 1264' from DER, 778' left of centerline, up to 45' AGL/635' MSL.
Vehicles on road 1626' from DER, 59' left of centerline, 638' MSL.
Poles beginning 2021' from DER, 390' right of centerline, up to 72' AGL/663' MSL.
Pole, tree beginning 2549' from DER, 935' right of centerline, up to 105' AGL/710' MSL.

29 OCT 2026 to 26 NOV 2026

GEORGETOWN, OH

BROWN COUNTY (GEO)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 26AUG10 (10238) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 18, vehicle on road beginning 430' from DER, 116' right of centerline, up to 15' AGL/974' MSL.
Vehicle on road beginning 400' from DER, 155' left of centerline, up to 15' AGL/974' MSL.
Rwy 36, trees 328' from DER, 232' right of centerline, up to 100' AGL/1059' MSL.
Trees 301' from DER, 452' left of centerline, up to 100' AGL, 1069' MSL.

GOSHEN, IN

GOSHEN MUNI (GSH)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-B 12JUN25 (25163) (FAA)

TAKEOFF MINIMUMS:

Rwys 5, 23, NA-Environmental.

TAKEOFF OBSTACLE NOTES:

Rwy 9, pole 43' from DER, 251' right of centerline, 4' AGL/831' MSL.
Poles beginning 990' from DER, 675' left of centerline, up to 29' AGL/855' MSL.
Tree 1091' from DER, 692' right of centerline, 885' MSL.
Tree 2132' from DER, 1027' right of centerline, 902' MSL.
Trees beginning 2245' from DER, 984' right of centerline, up to 915' MSL.
Tree 2319' from DER, 1019' left of centerline, 887' MSL.
Trees beginning 2494' from DER, 963' left of centerline, up to 91' AGL/921' MSL.
Trees beginning 3049' from DER, 717' left of centerline, up to 935' MSL.
Trees beginning 3297' from DER, 116' right of centerline, up to 923' MSL.
Trees beginning 3450' from DER, 194' left of centerline, up to 942' MSL.
Trees beginning 3585' from DER, 208' right of centerline, up to 74' AGL/927' MSL.
Trees beginning 3678' from DER, 874' right of centerline, up to 928' MSL.
Trees beginning 3919' from DER, 662' right of centerline, up to 935' MSL.
Trees beginning 3927' from DER, 319' left of centerline, up to 946' MSL.
Trees beginning 4079' from DER, 540' right of centerline, up to 951' MSL.
Trees beginning 4175' from DER, 342' left of centerline, up to 94' AGL/950' MSL.
Trees beginning 4186' from DER, 317' left of centerline, up to 952' MSL.
Trees beginning 4288' from DER, 346' left of centerline, up to 96' AGL/953' MSL.
Trees beginning 4325' from DER, 373' left of centerline, up to 958' MSL.
Trees beginning 4370' from DER, 359' left of centerline, up to 960' MSL.
Trees beginning 4442' from DER, 412' left of centerline, up to 969' MSL.
Trees beginning 4486' from DER, 354' left of centerline, up to 970' MSL.
Trees beginning 4744' from DER, 410' left of centerline, up to 971' MSL.
Rwy 27, agricultural equipment 78' from DER, 482' right of centerline, 19' AGL/835' MSL.
Agricultural equipment, terrain beginning 85' from DER, 301' right of centerline, up to 19' AGL/837' MSL.
Trees beginning 1570' from DER, 512' left of centerline, up to 888' MSL.
Tree 1691' from DER, 769' left of centerline, 893' MSL.
Trees beginning 1760' from DER, 449' left of centerline, up to 901' MSL.
Trees beginning 2222' from DER, 816' left of centerline, up to 89' AGL/904' MSL.
Trees beginning 2227' from DER, 236' left of centerline, up to 916' MSL.
Trees beginning 2278' from DER, 328' right of centerline, up to 887' MSL.
Trees beginning 2399' from DER, 609' right of centerline, up to 891' MSL.
Trees beginning 2853' from DER, 105' left of centerline, up to 113' AGL/917' MSL.
Trees beginning 3032' from DER, 71' left of centerline, up to 123' AGL/923' MSL.
Trees beginning 3053' from DER, 81' left of centerline, up to 124' AGL/925' MSL.
Tree 3085' from DER, 244' right of centerline, 909' MSL.
Trees beginning 3105' from DER, 51' right of centerline, up to 111' AGL/916' MSL.
Tree 3475' from DER, 661' right of centerline, 917' MSL.
Trees beginning 3478' from DER, 314' right of centerline, up to 120' AGL/923' MSL.

29 OCT 2026 to 26 NOV 2026

26190

GREENCASTLE, IN

PUTNAM COUNTY RGNL (GPC)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 05JAN17 (17005) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 18, grd 91' from DER, 299' left of centerline, 817' MSL.
Fence 113' from DER, 306' left of centerline, 3' AGL/822' MSL.
Fence 199' from DER, 307' left of centerline, 7' AGL/825' MSL.
Trees, poles, and bldgs beginning 538' from DER, 373' right of centerline, up to 873' MSL.
Tree 997' from DER, 266' left of centerline, 855' MSL.
Tree 1015' from DER, 360' left of centerline, 859' MSL.
Tree 2728' from DER, 1049' right of centerline, 894' MSL.
Rwy 36, grd 4' from DER, 486' right of centerline, 850' MSL.
Trees beginning 656' from DER, 596' right of centerline, up to 910' MSL.
Trees and bldg beginning 1269' from DER, 206' right of centerline, up to 912' MSL.
Trees, spire, and bldg beginning 1861' from DER, 217' right of centerline, up to 67' AGL/918' MSL.
Tree 1862' from DER, 535' left of centerline, 42' AGL/889' MSL.
Trees beginning 2227' from DER, 199' left of centerline, up to 64' AGL/912' MSL.
Tree and bldg beginning 2334' from DER, 18' left of centerline, up to 913' MSL.

GREENSBURG, IN

GREENSBURG MUNI (I34)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 11JUL24 (24193) (FAA)

TAKEOFF MINIMUMS:

Rwy 1, 300-1.

TAKEOFF OBSTACLE NOTES:

Rwy 1, tree 416' from DER, 598' left of centerline, 950' MSL.
Tree 428' from DER, 487' left of centerline, 964' MSL.
Utility building 1360' from DER, 855' left of centerline, 122' AGL/1035' MSL.
Elevators beginning 1443' from DER, 724' left of centerline, up to 153' AGL/1067' MSL.
Tree 1980' from DER, 962' right of centerline, 1018' MSL.
Rwy 19, tree 131' from DER, 487' right of centerline, 961' MSL.
Trees beginning 280' from DER, 510' left of centerline, up to 944' MSL.
Trees beginning 498' from DER, 459' right of centerline, up to 992' MSL.
Tree 799' from DER, 597' left of centerline, 968' MSL.
Trees beginning 924' from DER, 585' left of centerline, up to 989' MSL.
Trees beginning 2401' from DER, 630' left of centerline, up to 993' MSL.

GRIFFITH, IN

GRIFFITH-MERRILLVILLE (05C)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4B 07OCT21 (21280) (FAA)

TAKEOFF MINIMUMS:

Rwy 8, 300-1.

TAKEOFF OBSTACLE NOTES:

Rwy 8, tree, pole, vehicles on road beginning 164' from DER, 135' right of centerline, up to 703' MSL.
Pole 307' from DER, 514' left of centerline, 44' AGL/675' MSL.
Tree, vehicles on road beginning 432' from DER, 169' left of centerline, up to 695' MSL.
Trees beginning 444' from DER, 6' right of centerline, up to 708' MSL.
Pole, building beginning 454' from DER, 191' left of centerline, up to 75' AGL/704' MSL.
Tree, pole beginning 831' from DER, 7' left of centerline, up to 712' MSL.
Trees beginning 1055' from DER, 5' right of centerline, up to 709' MSL.
Trees beginning 1980' from DER, 58' left of centerline, up to 717' MSL.
Tree 2967' from DER, 388' right of centerline, 714' MSL.
Trees beginning 3166' from DER, 259' left of centerline, up to 718' MSL.
Trees beginning 3288' from DER, 153' left of centerline, up to 724' MSL.
Tree 3747' from DER, 284' left of centerline, 726' MSL.
Tower 4136' from DER, 1383' left of centerline, 257' AGL/896' MSL.
Tower 4426' from DER, 1293' left of centerline, 148' AGL/791' MSL.
Rwy 26, vegetation 164' from DER, 471' left of centerline, 653' MSL.
Building 192' from DER, 156' right of centerline.
Pole 1247' from DER, 199' right of centerline, 40' AGL/675' MSL.
Tree 1286' from DER, 285' left of centerline, 667' MSL.
Tree, pole beginning 1298' from DER, 58' right of centerline, up to 693' MSL.
Tree, pole beginning 1380' from DER, 25' left of centerline, up to 703' MSL.
Tree 1498' from DER, 80' right of centerline, 703' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

GRIFFITH, IN (CON'T)

GRIFFITH-MERRILLVILLE (05C) (CON'T)

Rwy 26 (CON'T), tree 1523' from DER, 271' left of centerline, 709' MSL.
Pole, tree beginning 1590' from DER, 21' left of centerline, up to 75 ' AGL/713' MSL.
Trees beginning 1613' from DER, 93' right of centerline, up to 710' MSL.
Trees beginning 1739' from DER, 25' left of centerline, up to 723' MSL.
Trees beginning 1826' from DER, 60' right of centerline, up to 716' MSL.
Trees beginning 1920' from DER, 68' right of centerline, up to 717' MSL.
Trees beginning 2144' from DER, 12' right of centerline, up to 739' MSL.
Tree 3205' from DER, 716' left of centerline, 725' MSL.

HAMILTON, OH

BUTLER COUNTY RGNL/HOGAN FLD (HAO)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 5A 17APR25 (25107) (FAA)

TAKEOFF MINIMUMS:

Rwy 30, 300-1 or std w/min climb of 482'/NM to 900.

DEPARTURE PROCEDURE:

Rwy 12, climb heading 126° to 1700 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 12, tree 939' from DER, 751' right of centerline, 667' MSL.
Pole 2962' from DER, 616' left of centerline, 29' AGL/694' MSL.
Pole 3320' from DER, 614' left of centerline, 53' AGL/706' MSL.
Pole 3559' from DER, 167' left of centerline, 62' AGL/711' MSL.
Tree 3624' from DER, 129' right of centerline, 717' MSL.
Rwy 30, vegetation 155' from DER, 277' right of centerline, 641' MSL.
Building 533' from DER, 374' left of centerline, 29' AGL/657' MSL.
Tree 963' from DER, 416' right of centerline, 667' MSL.
Tree 1123' from DER, 722' left of centerline, 698' MSL.
Tree 1395' from DER, 758' left of centerline, 702' MSL.
Vehicles on road, trees beginning 1946' from DER, 244' right of centerline, up to 703' MSL.
Pole 2217' from DER, 422' right of centerline, 22' AGL/721' MSL.
Trees, buildings beginning 2243' from DER, 371' right of centerline, up to 782' MSL.
Tree 2580' from DER, 289' left of centerline, 705' MSL.
Trees beginning 2595' from DER, 105' right of centerline, up to 788' MSL.
Trees beginning 2667' from DER, 57' left of centerline, up to 723' MSL.
Tree 3395' from DER, 863' right of centerline, 796' MSL.
Trees beginning 3548' from DER, 242' right of centerline, up to 814' MSL.

HARRISON, OH

CINCINNATI WEST (I67)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2A 08OCT20 (20282) (FAA)

TAKEOFF MINIMUMS:

Rwy 1, 500-3 or std w/min climb of 385' per NM to 1200.
Rwy 19, 500-3 or std w/min climb of 253' per NM to 1300.

TAKEOFF OBSTACLE NOTES:

Rwy 1, multiple trees beginning 5364' from DER, 180' right of centerline, up to 100' AGL/915' MSL.
Multiple trees beginning 5596' from DER, 1180' left of centerline up to 100' AGL/909' MSL.
Multiple trees beginning 1.5 NM from DER, 2293' left of centerline, up to 200' AGL/849' MSL.
Rwy 19, road 23' from DER, on centerline, 15' AGL/599' MSL.

HILLSBORO, OH

HIGHLAND COUNTY (HOC)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4 19JUL18 (18200) (FAA)

TAKEOFF MINIMUMS:

Rwy 5, 300-1¾ or std w/min climb of 285' per NM to 1300.

DEPARTURE PROCEDURES:

Rwy 23, climb on heading 234° to 1600 before turning left.

TAKEOFF OBSTACLE NOTES:

Rwy 5, trees beginning 20' from DER, 40' left of centerline, up to 1023' MSL.
Fence 105' from DER, 326' right of centerline, 9' AGL/952' MSL.
Trees beginning 145' from DER, 13' right of centerline, up to 1023' MSL.
Tree 4652' from DER, 205' right of centerline, 1051' MSL.
Trees beginning 4692' from DER, 31' right of centerline, up to 100' AGL/1078'MSL.

CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

HILLSBORO, OH (CON'T)

HIGHLAND COUNTY (HOC) (CON'T)

Rwy 5 (CON'T), tree 1.1 NM from DER, 2294' right of centerline, 100' AGL/1170' MSL.
Rwy 23, tree 49' from DER, 444' right of centerline, 999' MSL.
Trees beginning 90' from DER, 185' right of centerline, up to 100' AGL/1075' MSL.
Tree, pole beginning 109' from DER, 42' left of centerline, up to 100' AGL/1062' MSL.
Trees beginning 448' from DER, 109' right of centerline, up to 100' AGL/1081' MSL.
Trees beginning 627' from DER, 33' right of centerline, up to 100' AGL/1085' MSL.

HUNTINGBURG, IN

HUNTINGBURG (HNB)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 12AUG21 (21224) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, tree 1255' from DER, 507' left of centerline, 76' AGL/567' MSL.
Trees beginning 1257' from DER, 544' left of centerline, up to 90' AGL/584' MSL.
Tree 1558' from DER, 763' left of centerline, 597' MSL.
Trees beginning 1643' from DER, 800' left of centerline, up to 604' MSL.
Trees beginning 1980' from DER, 901' left of centerline, up to 606' MSL.
Trees beginning 4445' from DER, 1257' right of centerline, up to 646' MSL.
Tree 4621' from DER, 978' left of centerline, 646' MSL.
Trees beginning 4648' from DER, 730' left of centerline, up to 654' MSL.
Tree 4824' from DER, 1677' right of centerline, 654' MSL.
Trees beginning 4854' from DER, 889' left of centerline, up to 666' MSL.
Tree 4894' from DER, 1561' right of centerline, 655' MSL.
Trees beginning 4998' from DER, 733' right of centerline, up to 660' MSL.
Trees beginning 5201' from DER, 696' right of centerline, up to 671' MSL.
Electrical system 5509' from DER, 592' left of centerline, 90' AGL/667' MSL.
Rwy 27, lighting 9' from DER, 16' right of centerline, 1' AGL/514' MSL.
Trees beginning 415' from DER, 465' right of centerline, up to 57' AGL/557' MSL.
Trees beginning 569' from DER, 500' right of centerline, up to 87' AGL/583' MSL.
Trees beginning 606' from DER, 613' right of centerline, up to 97' AGL/591' MSL.
Trees beginning 741' from DER, 511' right of centerline, up to 597' MSL.
Trees beginning 860' from DER, 333' left of centerline, up to 569' MSL.
Tree 1740' from DER, 764' left of centerline, 581' MSL.
Trees beginning 1970' from DER, 750' left of centerline, up to 587' MSL.
Tree 2805' from DER, 1215' left of centerline, 590' MSL.

HUNTINGTON, IN

HUNTINGTON MUNI (HHG)

TAKEOFF MINIMUMS AND (OBSTACLE)DEPARTURE PROCEDURES

AMDT 2A 27JAN22 (22027) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 10, trees beginning 2' from DER, 59' right of centerline, up to 854' MSL.
Pole 47' from DER, 198' left of centerline, 23' AGL/812' MSL.
Trees beginning 291' from DER, 10' left of centerline, up to 882' MSL.
Trees beginning 1006' from DER, 230' left of centerline, up to 892' MSL.
Trees beginning 1142' from DER, 35' right of centerline, up to 866' MSL.
Tree 2112' from DER, 509' right of centerline, 872' MSL.
Rwy 28, tree 112' from DER, 498' left of centerline, 855' MSL.
Tree, vegetation, vehicles on road, pole beginning 159' from DER, 20' left of centerline, up to 875' MSL.
Building 269' from DER, 519' right of centerline, 20' AGL/826' MSL.
Pole, tree beginning 456' from DER, 31' right of centerline, up to 41' AGL/846' MSL.
Tree, pole beginning 832' from DER, 2' right of centerline, up to 851' MSL.
Tree 2727' from DER, 816' right of centerline, 900' MSL.

29 OCT 2026 to 26 NOV 2026

INDIANAPOLIS, IN

EAGLE CREEK AIRPARK (EYE)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 31MAR16 (16091) (FAA)

DEPARTURE PROCEDURE:

Rwy 3, climb heading 031° to 2100 before turning on course.

TAKEOFF OBSTACLE NOTES:

Rwy 3, pole 507' from DER, 631' left of centerline, 38' AGL/860' MSL.
Building 859' from DER, 524' right of centerline, 35' AGL/851' MSL.
Trees beginning 2015' from DER, 583' left of centerline, up to 87' AGL/904' MSL.
Rwy 21, airport beacon 10' from DER, 464' left of centerline, 54' AGL/867' MSL.
Pole 167' from DER, 385' left of centerline, 33' AGL/848' MSL.
Vehicles on road 310' from DER, right and left of centerline, up to 15' AGL/833' MSL.
Building 363' from DER, 258' left of centerline, 14' AGL/828' MSL.
Trees beginning 677' from DER, 267' right of centerline, up to 89' AGL/901' MSL.
Poles and power lines beginning 699' from DER, 451' left of centerline, up to 38' AGL/849' MSL.
Trees beginning 1623' from DER, 57' left of centerline, up to 90' AGL/890' MSL.

HENRICKS COUNTY-GORDON GRAHAM FLD (2R2)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 05JUN08 (21280) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 18, pole 746' from DER, on centerline, 60' AGL/919' MSL.
Trees 2091' from DER, 625' left of centerline, 100' AGL/949' MSL.
Rwy 36, trees 1302' from DER, 648' right of centerline, 100' AGL/1009' MSL.
Tree 3529' from DER, 788' right of centerline, 100' AGL/1009' MSL.
Tree 5244' from DER, 1005' left of centerline, 100' AGL/1029' MSL.

INDIANAPOLIS EXEC (TYQ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 05OCT23 (23278) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 18, tree 212' from DER, 203' left of centerline, 40' AGL/954' MSL.
Trees beginning 370' from DER, 247' left of centerline, up to 60' AGL/971' MSL.
Trees beginning 1385' from DER, 752' left of centerline, up to 75' AGL/986' MSL.
Tree 1541' from DER, 741' left of centerline, 78' AGL/990' MSL.
Trees beginning 1568' from DER, 196' left of centerline, up to 79' AGL/993' MSL.
Tree 1602' from DER, 622' right of centerline, 74' AGL/988' MSL.
Trees beginning 1670' from DER, 192' left of centerline, up to 994' MSL.
Trees beginning 1875' from DER, 733' right of centerline, up to 86' AGL/997' MSL.
Trees beginning 1924' from DER, 251' right of centerline, up to 96' AGL/1007' MSL.
Trees beginning 2031' from DER, 311' left of centerline, up to 996' MSL.
Rwy 36, wind indicator, building beginning 124' from DER, 429' left of centerline, up to 22' AGL/943' MSL.
Pole 1115' from DER, 490' left of centerline, 26' AGL/951' MSL.
Pole 1134' from DER, 321' left of centerline, 33' AGL/958' MSL.
Poles beginning 1144' from DER, 326' left of centerline, up to 961' MSL.
Poles beginning 1156' from DER, 336' right of centerline, up to 955' MSL, pole 1203' from DER, 776' right of centerline, 959' MSL.
Trees beginning 1242' from DER, 55' left of centerline, up to 974' MSL.
Trees beginning 1256' from DER, 320' right of centerline, up to 52' AGL/974' MSL.
Trees beginning 1755' from DER, 318' right of centerline, up to 993' MSL.
Trees beginning 1963' from DER, 779' left of centerline, up to 977' MSL.
Trees beginning 2024' from DER, 22' right of centerline, up to 996' MSL.
Trees beginning 2159' from DER, 25' left of centerline, up to 997' MSL.
Tree 2853' from DER, 58' left of centerline, 74' AGL/999' MSL.
Tree 2880' from DER, 88' left of centerline, 74' AGL/1000' MSL.
Trees beginning 2887' from DER, 21' left of centerline, up to 79' AGL/1004' MSL.
Trees beginning 2955' from DER, 22' left of centerline, up to 80' AGL/1005' MSL.
Trees beginning 2957' from DER, 4' left of centerline, up to 84' AGL/1008' MSL.
Tree 2966' from DER, 129' right of centerline, 75' AGL/1001' MSL.
Tree 2988' from DER, 332' left of centerline, 97' AGL/1011' MSL.
Trees beginning 2999' from DER, 5' left of centerline, up to 105' AGL/1018' MSL.
Tree 3045' from DER, 185' right of centerline, 77' AGL/1003' MSL.
Tree 3055' from DER, 167' right of centerline, 79' AGL/1004' MSL.
Trees beginning 3058' from DER, 18' right of centerline, up to 87' AGL/1011' MSL.
Trees beginning 3179' from DER, 16' left of centerline, up to 106' AGL/1020' MSL.
Trees beginning 3193' from DER, 1' left of centerline, up to 109' AGL/1022' MSL.
Trees beginning 3259' from DER, 24' right of centerline, up to 99' AGL/1018' MSL.

CON'T

INDIANAPOLIS, IN (CON'T)

INDIANAPOLIS EXEC (TYQ) (CON'T)

Rwy 36 (CON'T), trees beginning 3318' from DER, 7' right of centerline, up to 103' AGL/1023' MSL.
Trees beginning 3355' from DER, 4' right of centerline, up to 107' AGL/1026' MSL.
Trees beginning 3403' from DER, 1' left of centerline, up to 1024' MSL.
Trees beginning 3476' from DER, 4' right of centerline, up to 102' AGL/1028' MSL.
Trees beginning 3506' from DER, 4' left of centerline, up to 111' AGL/1027' MSL.
Trees beginning 3613' from DER, 8' right of centerline, up to 126' AGL/1036' MSL.
Trees beginning 3755' from DER, 9' left of centerline, up to 1034' MSL.

INDIANAPOLIS INTL (IND)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 18JAN07 (07018) (FAA)

TAKEOFF OBSTACLE NOTES:
Rwy 5R, tower 3756' from DER, 1048' left of centerline, 111' AGL/901' MSL.
Rod on obstruction light dome 3765' from DER, 1076' left of centerline, 107' AGL/901' MSL.
Rwy 5L, rod on obstruction light MCWV tower 5052' from DER, 140' right of centerline, 129' AGL/923' MSL.
Tower 5073' from DER, 93' right of centerline, 128'AGL/923'MSL.
Rwy 23R, tree 5159' from DER, 1144' right of centerline, 101' AGL/870' MSL.
Tree 3295' from DER, 948' right of centerline, 78' AGL/822' MSL.
Rwy 32, antenna 2370' from DER, 755' right of centerline, 70' AGL/849' MSL.
Tree 2244' from DER, 707' right of centerline, 66' AGL/845' MSL.

INDIANAPOLIS METRO (UMP)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4 16MAY24 (24137) (FAA)

DEPARTURE PROCEDURE:
Rwy 33, climb on heading 329° to 1400 before turning left.

TAKEOFF OBSTACLE NOTES:
Rwy 15, NAVAID 39' from DER, 124' left of centerline, 3' AGL/812' MSL.
Sign and pole beginning 1275' from DER,206' right of centerline, up to 45' AGL/857' MSL.
Pole 1733' from DER, 42' right of centerline, 44' AGL/859' MSL.
Pole 1861' from DER, 144' left of centerline, 47' AGL/866' MSL.
Trees beginning 1964' from DER, 65' right of centerline, up to 884' MSL.
Tree 1992' from DER, 236' left of centerline, 868' MSL.
Tree 2611' from DER, 113' right of centerline, 887' MSL.
Pole 3089' from DER, 1316' left of centerline, 127' AGL/952' MSL.
Tower 4370' from DER, 1455' left of centerline, 137' AGL/962' MSL.
Rwy 33, trees beginning 666' from DER, 108' left of centerline, up to 865' MSL.
Tree 852' from DER, 605' right of centerline, 810' MSL.
Tree 1080' from DER, 635' right of centerline, 830' MSL.
Tree 1199' from DER, 486' right of centerline, 842' MSL.
Trees beginning 1210' from DER, 365' right of centerline, up to 859' MSL.

INDIANAPOLIS RGNL (MQJ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3A 14MAY26 (26134) (FAA)

TAKEOFF MINUMUMS:
Rwy 34, 300-1 or std w/min climb of 347'/NM to 1100.

DEPARTURE PROCEDURE:
Rwy 25, climb on heading 270° to 2100 before turning left.

TAKEOFF OBSTACLE NOTES:
Rwy 7, light poles 6' from DER, 29' right of centerline, 2' AGL/860' MSL.
Tree 1649' from DER, 403' right of centerline, 46' AGL/901' MSL.
Tree 2027' from DER, 861' right of centerline, 59' AGL/915' MSL.
Rwy 16, light poles 9' from DER, 17' left of centerline, 2' AGL/858' MSL.
Tree 1633' from DER, 665' left of centerline, 78' AGL/929' MSL.
Trees beginning 2418' from DER, 496' right of centerline, up to 930' MSL.
Tree 4394' from DER, 1512' left of centerline, 968' MSL.
Rwy 25, light poles 10' from DER, 30' left of centerline, 2' AGL/864' MSL.
Tree 2128' from DER, 968' left of centerline, 923' MSL.
Tree 2762' from DER, 949' left of centerline, 940' MSL.
Tree 2834' from DER, 1127' left of centerline, 945' MSL.
Tree 3526' from DER, 1375' left of centerline, 959' MSL.
Tree 3626' from DER, 1431' left of centerline, 970' MSL.
Tower, antenna beginning 3942' from DER, 452' right of centerline, up to 123' AGL/977' MSL.
CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

26190

INDIANAPOLIS, IN (CON'T)

INDIANAPOLIS RGNL (MQJ) (CON'T)

Rwy 34, light poles 9' from DER, 16' right of centerline, 2' AGL/859' MSL.
Pole 1260' from DER, 795' left of centerline, 894' MSL.
Tree, pole beginning 1386' from DER, 295' left of centerline, up to 927' MSL.
Tree 3028' from DER, 69' right of centerline, 77' AGL/935' MSL.
Tree 3063' from DER, 17' left of centerline, 79' AGL/938' MSL.
Tree 3076' from DER, 16' right of centerline, 78' AGL/938' MSL.
Trees beginning 3081' from DER, 26' left of centerline, up to 81' AGL/941' MSL.
Trees beginning 3086' from DER, 54' right of centerline, up to 84' AGL/944' MSL.
Trees beginning 3098' from DER, 6' right of centerline, up to 89' AGL/946' MSL.
Tree 3150' from DER, 40' left of centerline, 93' AGL/951' MSL.
Tree 3154' from DER, 9' left of centerline, 99' AGL/958' MSL.
Trees beginning 3425' from DER, 1302' right of centerline, up to 965' MSL.
Tower 3858' from DER, 1372' right of centerline, 150' AGL/1008' MSL.
Trees beginning 3961' from DER, 1490' left of centerline, up to 961' MSL.

INDY SOUTH GREENWOOD (HFY)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 5 01FEB18 (18032) (FAA)

DEPARTURE PROCEDURE:

Rwy 1, climb heading 010° to 1500 before turning right.

TAKEOFF OBSTACLE NOTES:

Rwy 1, poles beginning 7' from DER, 224' left of centerline, up to 17' AGL/835' MSL.
Tree 41' from DER, 364' right of centerline, 26' AGL/846' MSL.
Building 105' from DER, 495' right of centerline, 27' AGL/848' MSL.
Building 430' from DER, 603' left of centerline, 37' AGL/857' MSL.
Building, tree, pole beginning 458' from DER, 378' right of centerline, up to 40' AGL/858' MSL.
Building, pole beginning 463' from DER, 562' left of centerline, up to 39' AGL/859' MSL.
Building, pole, tree beginning 506' from DER, 470' left of centerline, up to 45' AGL/865' MSL.
Pole 671' from DER, 464' right of centerline, 51' AGL/868' MSL.
Pole, traverse way, sign, building, tree beginning 690' from DER, 245' right of centerline, up to 53' AGL/872' MSL.
Transmission line, pole beginning 1555' from DER, 659' right of centerline, up to 70' AGL/893' MSL.
Trees beginning 1917' from DER, 321' left of centerline, up to 90' AGL/899' MSL.
Trees beginning 2026' from DER, 328' left of centerline, up to 103' AGL/907' MSL.
Tree, transmission line beginning 2328' from DER, 795' right of centerline, up to 76' AGL/894' MSL.
Tree, transmission line beginning 2463' from DER, 376' right of centerline, up to 77' AGL/898' MSL.
Building 5365' from DER, 1405' right of centerline, 135' AGL/957' MSL.
Rwy 19, terrain 2' from DER, 496' left of centerline, 824' MSL.
Fence 12' from DER, 490' right of centerline, 4' AGL/826' MSL.
Tree 212' from DER, 549' left of centerline, 52' AGL/873' MSL.
Tree 543' from DER, 417' right of centerline, 18' AGL/845' MSL.
Tree, building beginning 564' from DER, 612' left of centerline, up to 62' AGL/884' MSL.
Tree 638' from DER, 402' right of centerline, 20' AGL/849' MSL.
Tree 752' from DER, 383' right of centerline, 24' AGL/852' MSL.
Trees beginning 782' from DER, 65' right of centerline, up to 41' AGL/868' MSL.
Tree, pole beginning 953' from DER, 9' left of centerline, up to 62' AGL/886' MSL.
Tree, pole beginning 1155' from DER, 145' right of centerline, up to 69' AGL/896' MSL.
Trees beginning 1487' from DER, 83' right of centerline, up to 78' AGL/902' MSL.
Trees beginning 1561' from DER, 25' right of centerline, up to 76' AGL/904' MSL.
Trees beginning 2035' from DER, 270' right of centerline, up to 87' AGL/908' MSL.
Trees beginning 2161' from DER, 634' left of centerline, up to 76' AGL/908' MSL.
Trees beginning 2706' from DER, 156' left of centerline, up to 80' AGL/916' MSL.
Trees beginning 2730' from DER, 248' right of centerline, up to 98' AGL/923' MSL.
Tree 3079' from DER, 1113' left of centerline, 60' AGL/918' MSL.
Trees beginning 3080' from DER, 181' left of centerline, up to 64' AGL/921' MSL.
Trees beginning 3246' from DER, 131' left of centerline, up to 72' AGL/923' MSL.
Tree 4071' from DER, 127' left of centerline, 79' AGL/944' MSL.

29 OCT 2026 to 26 NOV 2026

26190

JACKSON, OH

JAMES A RHODES (JRO)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4A 14JUL22 (22195) (FAA)

TAKEOFF MINIMUMS:

Rwy 1, 300-1⅞.

Rwy 19, 300-1⅝.

DEPARTURE PROCEDURE:

Rwy 1, climb on heading 010° to 1500 before turning left.

TAKEOFF OBSTACLE NOTES:

Rwy 1, vehicle on road 104' from DER, 233' left of centerline, 748' MSL.
Trees, terrain, beginning 162' from DER, 186' left of centerline, up to 38' AGL/773' MSL.
Tree, terrain, vehicle on road, beginning 540' from DER, 234' left of centerline, up to 32' AGL/784' MSL.
Tree 763' from DER, 596' left of centerline, 51' AGL/806' MSL.
Trees, beginning 930' from DER, 431' right of centerline, up to 71' AGL/799' MSL.
Tree, vehicle on road, beginning 956' from DER, 237' left of centerline, up to 83' AGL/840' MSL.
Tree, vehicle on road, beginning 1138' from DER, 238' left of centerline, up to 84' AGL/843' MSL.
Trees, pole, transmission line, beginning 1286' from DER, 222' left of centerline, up to 94' AGL/864' MSL.
Trees, vehicle on road, poles, transmission line, beginning 1425' from DER, 224' left of centerline, up to 99' AGL/867' MSL.
Tree, terrain, beginning 1973' from DER, 599' left of centerline, up to 55' AGL/871' MSL.
Tree 2132' from DER, 568' left of centerline, 84' AGL/893' MSL.
Tree 2142' from DER, 997' left of centerline, 91' AGL/894' MSL.
Tree, terrain, beginning 2156' from DER, 343' left of centerline, up to 93' AGL/911' MSL.
Tree 2239' from DER, 589' left of centerline, 78' AGL/915' MSL.
Trees, pole, transmission line, terrain, beginning 2291' from DER, 249' left of centerline, up to 65' AGL/922' MSL.
Trees, vehicle on road, beginning 2453' from DER, 197' left of centerline, up to 71' AGL/931' MSL.
Trees, transmission line, pole, beginning 2590' from DER, 167' right of centerline, up to 71' AGL/810' MSL.
Trees, pole, beginning 2645' from DER, 283' left of centerline, up to 68' AGL/933' MSL.
Trees, pole, transmission line, building, sign, tower, beginning 2721' from DER, 106' left of centerline, up to 86' AGL/939' MSL.
Tree 2779' from DER, 25' right of centerline, 64' AGL/826' MSL.
Trees, beginning 2800' from DER, 122' right of centerline, up to 76' AGL/833' MSL.
Trees, beginning 2863' from DER, 7' right of centerline, up to 93' AGL/845' MSL.
Trees, building, beginning 2866' from DER, 170' left of centerline, up to 75' AGL/945' MSL.
Trees, poles, beginning 2973' from DER, 32' left of centerline, up to 108' AGL/955' MSL.
Trees, beginning 3628' from DER, 681' right of centerline, up to 100' AGL/854' MSL.
Trees, beginning 3737' from DER, 547' right of centerline, up to 92' AGL/861' MSL.
Trees, beginning 4116' from DER, 487' right of centerline, up to 108' AGL/880' MSL.
Trees, beginning 4220' from DER, 11' left of centerline, up to 92' AGL/956' MSL.
Trees, beginning 4277' from DER, 673' right of centerline, up to 101' AGL/888' MSL.
Trees, beginning 4362' from DER, 7' right of centerline, up to 98' AGL/894' MSL.
Tree 4507' from DER, 279' right of centerline, 81' AGL/895' MSL.
Trees, beginning 4507' from DER, 369' right of centerline, up to 90' AGL/898' MSL.
Tree 4532' from DER, 524' right of centerline, 108' AGL/900' MSL.
Trees, beginning 4541' from DER, 278' right of centerline, up to 87' AGL/907' MSL.
Trees, beginning 4590' from DER, 16' right of centerline, up to 98' AGL/908' MSL.
Trees, beginning 4812' from DER, 74' right of centerline, up to 70' AGL/914' MSL.
Trees, beginning 5025' from DER, 65' right of centerline, up to 72' AGL/917' MSL.
Trees, beginning 5093' from DER, 40' left of centerline, up to 81' AGL/957' MSL.
Trees, beginning 5145' from DER, 14' left of centerline, up to 89' AGL/962' MSL.
Trees, beginning 5167' from DER, 72' left of centerline, up to 77' AGL/965' MSL.
Trees, poles, building, beginning 5259' from DER, 66' right of centerline, up to 80' AGL/919' MSL.
Trees, beginning 5348' from DER, 203' left of centerline, up to 82' AGL/968' MSL.
Trees, beginning 5417' from DER, 1003' left of centerline, up to 83' AGL/969' MSL.
Trees, transmission line, poles, building, beginning 5447' from DER, 70' left of centerline, up to 93' AGL/971' MSL.
Trees, pole, building, beginning 5481' from DER, 116' right of centerline, up to 73' AGL/934' MSL.
Trees, beginning 5819' from DER, 54' right of centerline, up to 109' AGL/936' MSL.
Trees, beginning 6037' from DER, 21' left of centerline, up to 95' AGL/973' MSL.
Transmission line, trees, beginning 1 NM from DER, 188' left of centerline, up to 138' AGL/1013' MSL.
Transmission line, trees, water towers, tank, beginning 1.1 NM from DER, 10' left of centerline, up to 171' AGL/1023' MSL.
Transmission line, trees, beginning 1.1 NM from DER, 75' right of centerline, up to 147' AGL/960' MSL.
Tree 1.5 NM from DER, 2581' left of centerline, 95' AGL/957' MSL.
Rwy 19, terrain, beginning 3' from DER, 205' right of centerline, up to 725' MSL.
Tree, terrain, pole, building, beginning 774' from DER, 196' right of centerline, up to 60' AGL/817' MSL.
Terrain 792' from DER, 6' left of centerline, 746' MSL.
Trees, building, beginning 820' from DER, 476' right of centerline, up to 55' AGL/821' MSL.
Tree 863' from DER, 336' left of centerline, 30' AGL/752' MSL.
Trees, buildings, terrain, poles, vehicle on road, beginning 888' from DER, 3' right of centerline, up to 67' AGL/831' MSL.
Building 899' from DER, 280' left of centerline, 24' AGL/754' MSL.
Trees, stack, pole, beginning 914' from DER, 111' left of centerline, up to 62' AGL/800' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

JACKSON, OH (CON'T)

JAMES A RHODES (JRO) (CON'T)

Rwy 19 (CON'T), trees, poles, beginning 1106' from DER, 113' left of centerline, up to 62' AGL/804' MSL.
Trees, poles, beginning 1418' from DER, 21' left of centerline, up to 89' AGL/810' MSL.
Trees, pole, beginning 1447' from DER, 194' right of centerline, up to 65' AGL/853' MSL.
Trees, terrain, buildings, beginning 1555' from DER, 45' right of centerline, up to 65' AGL/864' MSL.
Trees, poles, buildings, terrain, beginning 1736' from DER, 24' right of centerline, up to 87' AGL/878' MSL.
Tree 2233' from DER, 25' left of centerline, 73' AGL/830' MSL.
Trees, building, beginning 2266' from DER, 6' left of centerline, up to 78' AGL/836' MSL.
Trees, beginning 2817' from DER, 64' left of centerline, up to 94' AGL/857' MSL.
Trees, pole, beginning 2843' from DER, 27' left of centerline, up to 93' AGL/860' MSL.
Trees, beginning 3067' from DER, 186' right of centerline, up to 110' AGL/890' MSL.
Trees, beginning 3179' from DER, 183' right of centerline, up to 98' AGL/893' MSL.
Trees, beginning 3272' from DER, 193' right of centerline, up to 99' AGL/899' MSL.
Trees, beginning 3345' from DER, 462' right of centerline, up to 103' AGL/914' MSL.
Trees, beginning 3370' from DER, 364' right of centerline, up to 106' AGL/930' MSL.
Trees, beginning 3436' from DER, 198' right of centerline, up to 119' AGL/936' MSL.
Trees, beginning 3576' from DER, 175' right of centerline, up to 113' AGL/940' MSL.
Trees, beginning 3642' from DER, 193' right of centerline, up to 113' AGL/942' MSL.
Trees, beginning 3747' from DER, 188' right of centerline, up to 124' AGL/944' MSL.
Trees, beginning 3927' from DER, 146' right of centerline, up to 102' AGL/962' MSL.
Trees, building, beginning 4077' from DER, 12' right of centerline, up to 105' AGL/965' MSL.
Trees, beginning 4196' from DER, 817' left of centerline, up to 60' AGL/885' MSL.
Trees, beginning 4202' from DER, 305' left of centerline, up to 105' AGL/886' MSL.
Tree 4241' from DER, 600' left of centerline, 80' AGL/892' MSL.
Trees, terrain, fence, buildings, pole, beginning 4573' from DER, 42' left of centerline, up to 88' AGL/929' MSL.
Tree 5543' from DER, 176' left of centerline, 77' AGL/939' MSL.
Trees, beginning 5549' from DER, 16' left of centerline, up to 84' AGL/947' MSL.
Transmission line 1.1 NM from DER, 1896' right of centerline, 125' AGL/969' MSL.
Transmission line, trees, beginning 1.1 NM from DER, 12' right of centerline, up to 128' AGL/999' MSL.
Transmission line, trees, beginning 1.1 NM from DER, 22' left of centerline, up to 162' AGL/1009' MSL.
Tree 1.3 NM from DER, 1626' left of centerline, 115' AGL/944' MSL.

JEFFERSONVILLE, IN

CLARK RGNL (JVY)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 13SEP18 (18256) (FAA)

TAKEOFF MINIMUMS:

Rwy 14, 300-1⅞ or std w/min climb of 230' per NM to 900.
Rwy 32, std w/min climb of 225' per NM to 1600 or 1900-3 for VCOA.

DEPARTURE PROCEDURE:

Rwy 14, climb heading 140° to 1300 before turning right.
Rwy 18, climb heading 182° to 1600 before turning right.
Rwy 32, climb heading 320° to 2000 before turning left.
Rwy 36, climb heading 002° to 1600 before turning left.

VCOA:

Rwy 32, obtain ATC approval for VCOA when requesting IFR clearance. Climb in visual conditions to cross Clark Rgnl airport at or above 2200 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 14, sign and tree beginning 22' from DER, 88' right of centerline, up to 7' AGL/465' MSL.
Tree 73' from DER, 266' left of centerline, 529' MSL.
Tree 123' from DER, 377' left of centerline, 540' MSL.
Tree and pole beginning 126' from DER, 29' left of centerline, up to 92' AGL/553' MSL.
Tree 205' from DER, 176' right of centerline, 21' AGL/468' MSL.
Tree 248' from DER, 179' right of centerline, 23' AGL/470' MSL.
Trees beginning 372' from DER, 41' right of centerline, up to 41' AGL/491' MSL.
Trees beginning 397' from DER, 129' right of centerline, up to 51' AGL/503' MSL.
Trees beginning 420' from DER, 22' right of centerline, up to 506' MSL.
Tree 563' from DER, 266' right of centerline, 518' MSL.
Trees beginning 565' from DER, 422' right of centerline, up to 526' MSL.
Trees beginning 596' from DER, 175' right of centerline, up to 100' AGL/536' MSL.
Catenary, tree and pole beginning 1615' from DER, 252' left of centerline, up to 563' MSL.
Tree 1693' from DER, 858' right of centerline, 537' MSL.
Tree 1793' from DER, 790' right of centerline, 550' MSL.
Trees beginning 1884' from DER, 732' right of centerline, up to 551' MSL.
Pole, catenary and tree beginning 2085' from DER, 242' left of centerline, up to 566' MSL.
Catenary and transmission line beginning 2148' from DER, 316' left of centerline, up to 580' MSL.
Tower 2207' from DER, 734' left of centerline, 594' MSL.

CON'T

JEFFERSONVILLE, IN (CON'T)

CLARK RGNL (JVY) (CON'T)

Rwy 14 (CON'T), tower, catenary, tree and transmission line beginning 2216' from DER, 201' left of centerline, up to 110' AGL/600' MSL.
Tree and catenary beginning 2388' from DER, 321' right of centerline, up to 558' MSL.
Catenary and tree beginning 2507' from DER, 165' left of centerline, up to 607' MSL.
Catenary and tree beginning 2742' from DER, 1025' right of centerline, up to 572' MSL.
Catenary 3380' from DER, 10' right of centerline, 119' AGL/578' MSL.
Catenary 3763' from DER, 202' right of centerline, 95' AGL/590' MSL.
Catenary 4265' from DER, 508' right of centerline, 593' MSL.
Antenna 1.5 NM from DER, 1335' left of centerline, 171' AGL/730' MSL.
Rwy 18, tree 262' from DER, 523' left of centerline, 50' AGL/490' MSL.
Tree 301' from DER, 515' right of centerline, 53' AGL/492' MSL.
Trees beginning 320' from DER, 475' right of centerline, up to 496' MSL.
Tree 369' from DER, 543' left of centerline, 493' MSL.
Tree and building beginning 545' from DER, 94' right of centerline, up to 508' MSL.
Trees beginning 559' from DER, 105' left of centerline, up to 512' MSL.
Trees beginning 1223' from DER, 691' left of centerline, up to 526' MSL.
Trees beginning 1375' from DER, 791' left of centerline, up to 90' AGL/538' MSL.
Tree 1716' from DER, 777' left of centerline, 545' MSL.
Tree and tank beginning 1720' from DER, 29' right of centerline, up to 96' AGL/559' MSL.
Trees beginning 1778' from DER, 746' left of centerline, up to 552' MSL.
Trees beginning 1946' from DER, 676' left of centerline, up to 559' MSL.
Trees beginning 2254' from DER, 164' left of centerline, up to 563' MSL.
Trees beginning 3221' from DER, 678' right of centerline, up to 562' MSL.
Trees beginning 3833' from DER, 303' left of centerline, up to 86' AGL/570' MSL.
Catenary and transmission line beginning 4274' from DER, 564' left of centerline, up to 603' MSL.
Catenary and transmission line beginning 4976' from DER, 254' left of centerline, up to 125' AGL/610' MSL.
Catenary 5675' from DER, 681' right of centerline, 606' MSL.
Rwy 32, sign 19' from DER, 87' left of centerline, 8' AGL/474' MSL.
Tree 40' from DER, 419' right of centerline, 87' AGL/542' MSL.
Tree 145' from DER, 447' right of centerline, 101' AGL/557' MSL.
Tree, pole and building beginning 192' from DER, 12' right of centerline, up to 91' AGL/546' MSL.
Tree, pole and traverse way beginning 386' from DER, 8' left of centerline, up to 70' AGL/531' MSL.
Trees beginning 1054' from DER, 9' right of centerline, up to 101' AGL/560' MSL.
Tree 1638' from DER, 744' left of centerline, 534' MSL.
Trees beginning 1648' from DER, 608' left of centerline, up to 541' MSL.
Trees beginning 1819' from DER, 518' left of centerline, up to 542' MSL.
Trees beginning 2052' from DER, 11' left of centerline, up to 101' AGL/569' MSL.
Tree 2824' from DER, 1250' left of centerline, 575' MSL.
Trees beginning 3038' from DER, 1195' left of centerline, up to 576' MSL.
Trees beginning 3296' from DER, 895' right of centerline, up to 567' MSL.
Trees beginning 3501' from DER, 821' right of centerline, up to 582' MSL.
Trees beginning 3880' from DER, 563' left of centerline, up to 600' MSL.
Trees beginning 4783' from DER, 1553' left of centerline, up to 616' MSL.
Rwy 36, fence 172' from DER, 462' right of centerline, 482' MSL.
Traverse way 330' from DER, 508' right of centerline, 494' MSL.
Tree 418' from DER, 596' left of centerline, 505' MSL.
Trees beginning 604' from DER, 596' left of centerline, up to 527' MSL.
Pole 1130' from DER, 791' right of centerline, 513' MSL.
Pole 1310' from DER, 568' right of centerline, 515' MSL.
Transmission line 1648' from DER, 888' right of centerline, 92' AGL/544' MSL.
Catenary, tree and pole beginning 1648' from DER, 603' right of centerline, up to 548' MSL.
Trees beginning 2148' from DER, 821' left of centerline, up to 94' AGL/552' MSL.
Trees beginning 2216' from DER, 555' left of centerline, up to 553' MSL.
Tree 2823' from DER, 871' right of centerline, 550' MSL.
Tree 3009' from DER, 1296' right of centerline, 552' MSL.
Tree 3055' from DER, 818' right of centerline, 562' MSL.
Transmission line and tree beginning 3192' from DER, 321' right of centerline, up to 71' AGL/564' MSL.

29 OCT 2026 to 26 NOV 2026

26190

KENDALLVILLE, IN

KENDALLVILLE MUNI (C62)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2A 12JUN25 (25163) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 10, terrain, electrical system beginning 14' from DER, 112' left of centerline, up to 1007' MSL.
Electrical system 39' from DER, 112' right of centerline, 5' AGL/1006' MSL.
Vehicles on road, poles beginning 424' from DER, 99' left of centerline, up to 1015' MSL.
Vehicles on road beginning 428' from DER, 3' right of centerline, up to 1015' MSL.
Poles, trees beginning 435' from DER, 105' left of centerline, up to 35' AGL/1023' MSL.
Pole 464' from DER, 495' right of centerline, 30' AGL/1024' MSL.
Tree 475' from DER, 282' left of centerline, 1029' MSL.
Trees beginning 518' from DER, 233' left of centerline, up to 38' AGL/1035' MSL.
Trees beginning 532' from DER, 234' left of centerline, up to 1049' MSL.
Trees beginning 550' from DER, 122' left of centerline, up to 1053' MSL.
Trees beginning 860' from DER, 95' left of centerline, up to 89' AGL/1065' MSL.
Trees beginning 1399' from DER, 115' left of centerline, up to 76' AGL/1067' MSL.
Trees beginning 1795' from DER, 103' left of centerline, up to 1071' MSL.
Trees beginning 1823' from DER, 120' left of centerline, up to 84' AGL/1090' MSL.
Tree 1927' from DER, 76' right of centerline, 46' AGL/1053' MSL.
Trees beginning 1940' from DER, 290' right of centerline, up to 57' AGL/1062' MSL.
Trees beginning 1961' from DER, 58' right of centerline, up to 1064' MSL.
Trees beginning 2657' from DER, 157' left of centerline, up to 108' AGL/1096' MSL.
Trees beginning 2697' from DER, 10' left of centerline, up to 1100' MSL.
Tree 2759' from DER, 162' right of centerline, 74' AGL/1073' MSL.
Trees beginning 2770' from DER, 12' right of centerline, up to 81' AGL/1082' MSL.
Tree 2829' from DER, 334' right of centerline, 81' AGL/1083' MSL.
Trees beginning 2837' from DER, 15' right of centerline, up to 83' AGL/1085' MSL.
Trees beginning 2852' from DER, 66' right of centerline, up to 89' AGL/1088' MSL.
Trees beginning 2868' from DER, 47' right of centerline, up to 86' AGL/1089' MSL.
Trees beginning 2880' from DER, 4' left of centerline, up to 1101' MSL.
Trees beginning 2885' from DER, 19' right of centerline, up to 94' AGL/1090' MSL.
Trees beginning 2906' from DER, 10' right of centerline, up to 94' AGL/1096' MSL.
Trees beginning 2965' from DER, 4' left of centerline, up to 1106' MSL.
Trees beginning 2989' from DER, 17' left of centerline, up to 1107' MSL.
Trees beginning 3101' from DER, 224' left of centerline, up to 111' AGL/1108' MSL.
Trees beginning 3207' from DER, 244' left of centerline, up to 1109' MSL.
Trees beginning 3315' from DER, 372' left of centerline, up to 1119' MSL.
Trees beginning 3327' from DER, 310' left of centerline, up to 1126' MSL.
Trees beginning 3421' from DER, 346' left of centerline, up to 1127' MSL.
Trees beginning 3448' from DER, 299' left of centerline, up to 1128' MSL.
Trees beginning 3546' from DER, 337' left of centerline, up to 1130' MSL.
Trees beginning 3935' from DER, 329' left of centerline, up to 126' AGL/1142' MSL.
Trees beginning 4047' from DER, 354' left of centerline, up to 133' AGL/1146' MSL.
Rwy 28, building 126' from DER, 365' left of centerline, 22' AGL/1013' MSL.
Trees beginning 151' from DER, 425' left of centerline, up to 1036' MSL.
Trees beginning 331' from DER, 277' left of centerline, up to 1037' MSL.
Trees beginning 474' from DER, 3' left of centerline, up to 1056' MSL.
Tree 1679' from DER, 40' right of centerline, 63' AGL/1047' MSL.
Trees beginning 1697' from DER, 80' right of centerline, up to 67' AGL/1052' MSL.
Trees beginning 1723' from DER, 110' right of centerline, up to 77' AGL/1058' MSL.
Trees beginning 1739' from DER, 113' right of centerline, up to 1073' MSL.
Trees beginning 1807' from DER, 208' right of centerline, up to 1083' MSL.
Tree 2843' from DER, 1131' left of centerline, 1073' MSL.
Trees beginning 2907' from DER, 376' left of centerline, up to 1078' MSL.
Trees beginning 2926' from DER, 384' left of centerline, up to 1079' MSL.
Tree 2983' from DER, 485' left of centerline, 1084' MSL.
Trees beginning 2987' from DER, 564' left of centerline, up to 1102' MSL.
Trees beginning 3174' from DER, 599' left of centerline, up to 1103' MSL.

29 OCT 2026 to 26 NOV 2026

26190

KENT, OH

KENT STATE UNIVERSITY (1G3)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 19MAR26 (26078) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 2, terrain, sign beginning 21' from DER, 200' left of centerline, up to 1138' MSL.
Terrain, light poles beginning 26' from DER, 70' left of centerline, up to 1141' MSL.
Tree 73' from DER, 477' right of centerline, 1168' MSL.
Terrain beginning 86' from DER, 469' left of centerline, up to 1142' MSL.
Fence 169' from DER, 402' left of centerline, 6' AGL/1143' MSL.
Trees, smokestack, poles beginning 207' from DER, 369' right of centerline, up to 1179' MSL.
Vehicle on road 357' from DER, 582' left of centerline, 1145' MSL.
Pole 394' from DER, 493' left of centerline, 40' AGL/1167' MSL.
Trees beginning 412' from DER, 328' left of centerline, up to 1178' MSL.
Trees beginning 449' from DER, 461' left of centerline, up to 82' AGL/1207' MSL.
Trees beginning 614' from DER, 341' left of centerline, up to 88' AGL/1209' MSL.
Trees beginning 723' from DER, 462' left of centerline, up to 93' AGL/1211' MSL.
Trees beginning 1025' from DER, 507' right of centerline, up to 85' AGL/1182' MSL.
Trees beginning 1179' from DER, 14' left of centerline, up to 109' AGL/1216' MSL.
Trees beginning 1234' from DER, 4' right of centerline, up to 88' AGL/1184' MSL.
Trees beginning 1447' from DER, 84' right of centerline, up to 93' AGL/1187' MSL.
Trees beginning 1550' from DER, 125' right of centerline, up to 102' AGL/1188' MSL.
Trees beginning 1669' from DER, 1' right of centerline, up to 107' AGL/1195' MSL.
Tree 2136' from DER, 668' right of centerline, 117' AGL/1199' MSL.
Tree 3046' from DER, 570' right of centerline, 123' AGL/1212' MSL.
Rwy 20, tree 62' from DER, 485' right of centerline, 1180' MSL.
Trees, pole, buildings beginning 133' from DER, 338' right of centerline, up to 86' AGL/1200' MSL.
Tree 188' from DER, 538' left of centerline, 11' AGL/1126' MSL.
Vehicle on road 371' from DER, 406' left of centerline, 1130' MSL.
Poles, vehicles on road, building, trees beginning 375' from DER, 216' left of centerline, up to 44' AGL/1152' MSL.
Trees beginning 1210' from DER, 10' right of centerline, up to 102' AGL/1201' MSL.
Tree 1241' from DER, 66' left of centerline, 1168' MSL.
Trees beginning 1272' from DER, 1' left of centerline, up to 84' AGL/1170' MSL.
Trees beginning 1312' from DER, 418' right of centerline, up to 125' AGL/1214' MSL.
Trees beginning 1336' from DER, 625' right of centerline, up to 110' AGL/1216' MSL.
Trees beginning 1385' from DER, 26' left of centerline, up to 104' AGL/1171' MSL.
Trees beginning 1513' from DER, 7' right of centerline, up to 120' AGL/1217' MSL.
Trees beginning 1873' from DER, 47' left of centerline, up to 93' AGL/1172' MSL.
Trees beginning 2162' from DER, 315' right of centerline, up to 93' AGL/1223' MSL.
Trees beginning 2224' from DER, 247' right of centerline, up to 97' AGL/1230' MSL.
Trees beginning 2510' from DER, 224' right of centerline, up to 99' AGL/1231' MSL.
Trees beginning 2626' from DER, 152' right of centerline, up to 110' AGL/1233' MSL.

29 OCT 2026 to 26 NOV 2026

KENTLAND, IN

KENTLAND MUNI (50I)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 14SEP17 (17257)

DEPARTURE PROCEDURE:

Rwy 27, climb heading 260° to 1100' before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 9, vehicle on road 486' from DER, crossing centerline, 715' MSL/15' AGL.
Trees beginning 571' from DER, 116' right of centerline, up to 770' MSL/70' AGL.
Rwy 27, trees, building, pole beginning 533' from DER, 146' right of centerline, up to 765' MSL.
Pole beginning 746' from DER, 25' left of centerline, up to 23' AGL/723' MSL.
Pole beginning 925' from DER, 130' left of centerline, up to 27' AGL/724' MSL.
Tree 1215' from DER, 450' left of centerline, 733' MSL.

26190

KENTON, OH

HARDIN COUNTY (I95)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 13JAN11 (11013) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 4, trees, buildings, antenna on building, light poles, and flag poles beginning 31' from DER, 240' left of centerline, up to 29' AGL/1027' MSL.
Sign 103' from DER, 204' right of centerline, 8' AGL/1012' MSL.
Trees beginning 877' from DER, left and right of centerline, up to 103' AGL/1093' MSL.
Rwy 22, trees and buildings beginning 7' from DER, 484' left of centerline, up to 77' AGL/1103' MSL.
Trees beginning 179' from DER, 51' right of centerline, up to 108' AGL/1122' MSL.
Trees beginning 1345' from DER, left and right of centerline, up to 115' AGL/1158' MSL.

KNOX, IN

STARKE COUNTY (OXI)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 25SEP08 (08269) (FAA)

TAKEOFF MINIMUMS:

Rwys 9, 27, NA-Environmental.

TAKEOFF OBSTACLE NOTES:

Rwy 36, tree 1234' from DER, 477' left of centerline, 35' AGL/715' MSL.
Rwy 18, trees beginning 2442' from DER, 135' right of centerline, up to 86' AGL/769' MSL.
Tree 21' from DER, 449' left of centerline, 5' AGL/668' MSL.

KOKOMO, IN

KOKOMO MUNI (OKK)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 23JUN16 (16175) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 5, sign 20' from DER, 210' left of centerline, 3' AGL/821' MSL.
Trees beginning 501' from DER, 361' right of centerline, up to 57' AGL/870' MSL.
Tree 640' from DER, 466' left of centerline, 20' AGL/835' MSL.
Pole 642' from DER, 653' left of centerline, 843' MSL.
Buildings beginning 908' from DER, 706' left of centerline, up to 37' AGL/856' MSL.
Pole 971' from DER, 610' left of centerline, up to 39' AGL/858' MSL.
Trees, poles beginning 1042' from DER, 609' left of centerline, up to 48' AGL/870' MSL.
Elevator 1835' from DER, 361' right of centerline, 41' AGL/867' MSL.
Trees beginning 3730' from DER, 1373' left of centerline, up to 928' MSL.
Trees beginning 3747' from DER, 1245' left of centerline, up to 936' MSL.
Rwy 14, tree, bush beginning 6' from DER, 196' left of centerline, up to 31' AGL/849' MSL.
Tree, fence, vertical structure beginning 53' from DER, 153' right of centerline, up to 9' AGL/831' MSL.
Bush, fence beginning 116' from DER, 297' right of centerline, up to 842' MSL.
Building 2117' from DER, 488' left of centerline, 58' AGL/880' MSL.
Building, elevator beginning 2120' from DER, 485' left of centerline, up to 885' MSL.
Tree 2181' from DER, 215' left of centerline, 64' AGL/890' MSL.
Trees beginning 2186' from DER, 213' left of centerline, up to 77' AGL/904' MSL.
Tree 2945' from DER, 1073' right of centerline, 899' MSL.
Rwy 32, post 0' from DER, 149' right of centerline, 4' AGL/828' MSL.
Buildings beginning 133' from DER, 493' right of centerline, up to 15' AGL/837' MSL.
Buildings beginning 155' from DER, 490' right of centerline, up to 20' AGL/843' MSL.
Poles beginning 706' from DER, 520' right of centerline, up to 49' AGL/873' MSL.
Buildings, elevator, trees beginning 1592' from DER, 414' left of centerline, up to 68' AGL/889' MSL.
Tree 4804' from DER, 500' left of centerline, 121' AGL/949' MSL.

29 OCT 2026 to 26 NOV 2026

26190

LA PORTE, IN

LA PORTE MUNI (PPO)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2A 02OCT25 (25275) (FAA)

TAKEOFF MINIMUMS:

Rwy 2, 300-1 or std w/min climb of 262'/NM to 1100.

TAKEOFF OBSTACLE NOTES:

Rwy 2, vehicles on road 48' from DER, 496' right of centerline, 821' MSL.
Trees, vehicles on road beginning 150' from DER, 401' right of centerline, up to 43' AGL/847' MSL.
Tree 1158' from DER, 76' right of centerline, 42' AGL/848' MSL.
Tree 1196' from DER, 58' right of centerline, 44' AGL/850' MSL.
Trees beginning 1323' from DER, 5' right of centerline, up to 52' AGL/859' MSL.
Tree 1375' from DER, 8' left of centerline, 43' AGL/850' MSL.
Tree 1416' from DER, 16' left of centerline, 49' AGL/857' MSL.
Tree 1460' from DER, 31' left of centerline, 57' AGL/864' MSL.
Trees beginning 1724' from DER, 548' left of centerline, up to 877' MSL.
Tree 1829' from DER, 168' left of centerline, 71' AGL/878' MSL.
Trees beginning 1851' from DER, 176' left of centerline, up to 879' MSL.
Trees beginning 1971' from DER, 234' left of centerline, up to 83' AGL/882' MSL.
Trees beginning 1996' from DER, 234' left of centerline, up to 82' AGL/889' MSL.
Trees beginning 2077' from DER, 304' left of centerline, up to 893' MSL.
Tree 2414' from DER, 1078' right of centerline, 874' MSL.
Trees beginning 2506' from DER, 223' left of centerline, up to 897' MSL.
Trees beginning 2526' from DER, 1022' right of centerline, up to 890' MSL.
Trees beginning 2855' from DER, 699' left of centerline, up to 901' MSL.
Trees beginning 2880' from DER, 20' right of centerline, up to 79' AGL/894' MSL.
Tree 2893' from DER, 594' left of centerline, 904' MSL.
Trees beginning 3039' from DER, 269' left of centerline, up to 912' MSL.
Tree 3218' from DER, 1206' right of centerline, 899' MSL.
Antenna 4709' from DER, 1065' left of centerline, 144' AGL/966' MSL.
Rwy 14, transmission line 5476' from DER, 238' left of centerline, 172' AGL/947' MSL.
Rwy 20, light poles 7' from DER, 17' left of centerline, 2' AGL/802' MSL.
Vehicles on road beginning 71' from DER, 450' right of centerline, up to 810' MSL.
Tree, vehicles on road beginning 257' from DER, 394' right of centerline, up to 858' MSL.
Tree 356' from DER, 447' right of centerline, 859' MSL.
Tree 394' from DER, 491' right of centerline, 82' AGL/871' MSL.
Trees, pole beginning 420' from DER, 8' right of centerline, up to 95' AGL/884' MSL.
Tree 1523' from DER, 79' left of centerline, 58' AGL/845' MSL.
Trees beginning 1539' from DER, 12' left of centerline, up to 58' AGL/846' MSL.
Trees beginning 1717' from DER, 30' left of centerline, up to 70' AGL/856' MSL.
Tree 2027' from DER, 663' left of centerline, 869' MSL.
Trees beginning 2052' from DER, 379' left of centerline, up to 877' MSL.
Trees beginning 2258' from DER, 348' left of centerline, up to 885' MSL.
Trees beginning 2315' from DER, 37' left of centerline, up to 887' MSL.
Trees beginning 2675' from DER, 15' left of centerline, up to 122' AGL/895' MSL.
Trees beginning 3277' from DER, 67' right of centerline, up to 105' AGL/886' MSL.
Transmission line 4500' from DER, 1072' left of centerline, 162' AGL/936' MSL.
Rwy 32, vehicles on road 277' from DER, 199' left of centerline, 15' AGL/820' MSL.
Trees beginning 351' from DER, 368' left of centerline, up to 100' AGL/908' MSL.
Vehicles on road 540' from DER, 55' right of centerline, 15' AGL/825' MSL.
Trees beginning 2961' from DER, 742' left of centerline, up to 100' AGL/914' MSL.
Trees beginning 3456' from DER, 762' right of centerline, up to 100' AGL/917' MSL.
Tree 3614' from DER, 305' left of centerline, 100' AGL/920' MSL.
Tree 3898' from DER, 263' right of centerline, 100' AGL/920' MSL.

29 OCT 2026 to 26 NOV 2026

26190

LAFAYETTE, IN

PURDUE UNIVERSITY (LAF)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1A 30NOV23 (23334) (FAA)

TAKEOFF MINIMUMS:

Rwy 5, 300-1¼ or std w/min climb of 342'/NM to 1000.

Rwy 23, 400-2¼ or std w/min climb of 225'/NM to 1100.

TAKEOFF OBSTACLE NOTES:

Rwy 5, building, terrain, trees, vehicles on road beginning 11' from DER, 75' left of centerline, up to 31'AGL/642' MSL.
Fence 42' from DER, 423' right of centerline, 609' MSL.
Fence 124' from DER, 329' right of centerline, 610' MSL.
Poles, vehicles on road, terrain beginning 186' from DER, 135' left of centerline, up to 34' AGL/645' MSL.
Fence 189' from DER, 249' right of centerline, 612' MSL.
Fence 259' from DER, 164' right of centerline, 6' AGL/613' MSL.
Fence 269' from DER, 155' right of centerline, 12' AGL/619' MSL.
Poles, fences, vehicles on road beginning 289' from DER, 2' right of centerline, up to 20' AGL/621' MSL.
Pole, vehicles on road beginning 408' from DER, 227' left of centerline, up to 38' AGL/646' MSL.
Poles, vehicles on road beginning 416' from DER, 16' right of centerline, up to 20' AGL/623' MSL.
Transmission line, vehicles on road, pole beginning 459' from DER, 25' left of centerline, up to 39' AGL/648' MSL.
Trees, pole, vehicles on road beginning 685' from DER, 36' left of centerline, up to 649' MSL.
Vehicles on road 736' from DER, 65' right of centerline, 626' MSL.
Transmission line 867' from DER, 434' left of centerline, 39' AGL/650' MSL.
Trees, poles beginning 901' from DER, 424' left of centerline, up to 651' MSL.
Tree 995' from DER, 212' right of centerline, 36' AGL/638' MSL.
Tree 1000' from DER, 33' right of centerline, 40' AGL/649' MSL.
Tree 1042' from DER, 642' left of centerline, 654' MSL.
Tree, transmission line beginning 1046' from DER, 312' left of centerline, up to 49' AGL/660' MSL.
Tree 1125' from DER, 245' left of centerline, 50' AGL/661' MSL.
Trees, transmission lines, poles beginning 1146' from DER, 49' left of centerline, up to 684' MSL.
Poles beginning 1568' from DER, 49' right of centerline, up to 48' AGL/657' MSL.
Tree 1887' from DER, 256' right of centerline, 66' AGL/663' MSL.
Tree 2065' from DER, 239' right of centerline, 63' AGL/667' MSL.
Tree 2109' from DER, 203' right of centerline, 61' AGL/668' MSL.
Trees, buildings beginning 2116' from DER, 275' left of centerline, up to 694' MSL.
Building 3150' from DER, 34' right of centerline, 67' AGL/687' MSL.
Poles beginning 3257' from DER, 241' right of centerline, up to 76' AGL/696' MSL.
Tree 3507' from DER, 1179' left of centerline, 697' MSL.
Building 3594' from DER, 278' right of centerline, 102' AGL/723' MSL.
Building 4187' from DER, 1567' left of centerline, 92' AGL/717' MSL.
Buildings, building spire beginning 4731' from DER, 385' left of centerline, up to 747' MSL.
Buildings beginning 4908' from DER, 771' left of centerline, up to 143' AGL/767' MSL.
Building 4954' from DER, 1036' right of centerline, 752' MSL.
Building 5069' from DER, 870' right of centerline, 167' AGL/780' MSL.
Building 5541' from DER, 784' left of centerline, 162' AGL/782' MSL.
Building 5579' from DER, 778' left of centerline, 784' MSL.
Smokestack 5718' from DER, 633' left of centerline, 850' MSL.
Rwy 10, trees beginning 696' from DER, 629' right of centerline, up to 95' AGL/642' MSL.
Tree 857' from DER, 697' left of centerline, 61' AGL/643' MSL.
Rwy 23, fences beginning 50' from DER, 498' right of centerline, up to 605' MSL.
Tree 89' from DER, 235' left of centerline, 24' AGL/613' MSL.
Tree 171' from DER, 278' left of centerline, 31' AGL/617' MSL.
Tree 324' from DER, 281' left of centerline, 43' AGL/622' MSL.
Tower and antenna 1.9 NM from DER, 269' left of centerline, up to 321' AGL/923' MSL.
Rwy 28, tree 1190' from DER, 470' left of centerline, 630' MSL.
Trees beginning 1752' from DER, 765' right of centerline, up to 669' MSL.
Tree 2166' from DER, 675' left of centerline, 96' AGL/656' MSL.
Tree 2744' from DER, 1020' right of centerline, 672' MSL.
Trees beginning 2751' from DER, 954' right of centerline, up to 689' MSL.
Trees beginning 2968' from DER, 984' right of centerline, up to 697' MSL.
Trees beginning 3132' from DER, 920' right of centerline, up to 722' MSL.

29 OCT 2026 to 26 NOV 2026

LANCASTER, OH

FAIRFIELD COUNTY (LHQ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 12DEC13 (13346) (FAA)

TAKEOFF MINIMUMS:

Rwy 10, 400-2 or std w/min climb of 310' per NM to 1400.

DEPARTURE PROCEDURE:

Rwy 10, climb heading 100° to 1600 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 10, trees beginning 1571' from DER, 647' right of centerline, up to 56' AGL/927' MSL.
Trees beginning 1617' from DER, 509' left of centerline, up to 89' AGL/974' MSL.
Trees beginning 2131' from DER, 460' right of centerline, up to 74' AGL/945' MSL.
Trees beginning 5480' from DER, 173' right of centerline, up to 76' AGL/1037' MSL.
Trees beginning 1.1 NM from DER, 724' left of centerline, up to 84' AGL/1061' MSL.
Tree 1.9 NM from DER, 1990' right of centerline, 100' AGL/1259' MSL.
Rwy 28, trees beginning 738' from DER, 315' left of centerline, up to 77' AGL/912' MSL.
Trees 1509' from DER, 97' right of centerline, up to 76' AGL/897' MSL.
Trees beginning 1906' from DER, 358' right of centerline, up to 107' AGL/942' MSL.
Silo 2230' from DER, 267' left of centerline, 60' AGL/915' MSL.

LEBANON, OH

WARREN COUNTY/JOHN LANE FLD (I68)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 20SEP12 (22083) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 1, terrain and tree beginning 36' from DER, 320' left of centerline, up to 50' AGL/958' MSL.
Trees beginning 1084' from DER, left and right of centerline, up to 65' AGL/955' MSL.
Trees beginning 1510' from DER, left and right of centerline, up to 80' AGL/986' MSL.
Trees beginning 2001' from DER, 83' left of centerline, up to 100' AGL/1015' MSL.
Rwy 19, vehicles on roadway beginning abeam the DER, left and right of centerline, up to 15' AGL/901' MSL.
Terrain beginning 32' from DER, left and right of centerline, up to 886' MSL.
Buildings 74' from DER, 425' right of centerline, up to 15' AGL/892' MSL.
Trees 252' from DER, 359' right of centerline, up to 60' AGL/948' MSL.
Trees beginning 1089' from DER, 179' left of centerline, up to 55' AGL/952' MSL.
Trees beginning 1804' from DER, left and right of centerline, up to 85' AGL/960' MSL.

LIMA, OH

LIMA ALLEN COUNTY (AOH)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1A 16AUG18 (18228) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 10, bush beginning 162' from DER, 310' right of centerline, up to 4' AGL/983' MSL.
Rwy 28, multiple trees beginning 1343' from DER, 160' right of centerline, up to 71' AGL/1015' MSL.

LOGANSPORT, IN

LOGANSPORT/CASS COUNTY (GGP)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 12AUG21 (21224) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, fence 9' from DER, 443' right of centerline, 11' AGL/744' MSL.
Fence 187' from DER, 497' left of centerline, 11' AGL/743' MSL.
Tree 934' from DER, 730' left of centerline, 791' MSL.
Tree 2218' from DER, 487' right of centerline, 62' AGL/794' MSL.
Rwy 27, terrain 4' from DER, 495' left of centerline, 739' MSL.
Lighting 8' from DER, 17' right of centerline, 2' AGL/738' MSL.
Poles beginning 638' from DER, 489' right of centerline, up to 34' AGL/763' MSL.
Pole 734' from DER, 331' right of centerline, 39' AGL/767' MSL.
Poles beginning 924' from DER, 334' left of centerline, up to 39' AGL/773' MSL.
Tree 2041' from DER, 143' left of centerline, 65' AGL/801' MSL.
Tree 3360' from DER, 1358' left of centerline, 825' MSL.
Trees beginning 3374' from DER, 1002' left of centerline, up to 842' MSL.

29 OCT 2026 to 26 NOV 2026

26190

LONDON, OH

MADISON COUNTY (UYF)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 30JAN20 (20030) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, tree 164' from DER, 484' left of centerline, 1059' MSL.
Trees beginning 289' from DER, 417' left of centerline, up to 1065' MSL.
Pole 1154' from DER, 791' left of centerline, 1080' MSL.
Trees beginning 1330' from DER, 301' left of centerline, up to 1096' MSL.
Tree 1495' from DER, 416' left of centerline, 1103' MSL.
Tree 2591' from DER, 511' left of centerline, 1121' MSL.
Rwy 27, vertical structure 53' from DER, 206' left of centerline, 1089' MSL.
Vertical structure 134' from DER, 188' right of centerline, 1085' MSL.
Tree 2091' from DER, 973' right of centerline, 1142' MSL.

LORAIN/ELYRIA, OH

LORAIN COUNTY RGNL (LPR)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 24MAY18 (18144) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 7, terrain beginning 21' from DER, 83' left of centerline, up to 801' MSL.
Terrain 180' from DER, 288' right of centerline, 794' MSL.
Terrain beginning 229' from DER, 261' left of centerline, up to 804' MSL.
Terrain 308' from DER, 13' right of centerline, 801' MSL.
Trees beginning 839' from DER, 520' left of centerline, up to 832' MSL.
Tree 972' from DER, 294' right of centerline, 823' MSL.
Trees beginning 1181' from DER, 52' left of centerline, up to 836' MSL.
Tree 1294' from DER, 538' right of centerline, 847' MSL.
Tree 1852' from DER, 431' right of centerline, 861' MSL.
Tree 1875' from DER, 653' right of centerline, 865' MSL.
Rwy 25, vegetation 582' from DER, 468' right of centerline, 809' MSL.
Tree 1587' from DER, 697' left of centerline, 838' MSL.
Tree 2180' from DER, 785' right of centerline, 848' MSL.
Tree 2276' from DER, 435' right of centerline, 854' MSL.

MADISON, IN

MADISON RGNL (IMS)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 31JUL08 (26022) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 3, vehicle on road 625' from DER, on centerline, 15' AGL/844' MSL.
Antenna on building and trees beginning 170' from DER, 432' left of centerline, up to 85' AGL/904' MSL.
Poles and trees beginning 526' from DER, 64' right of centerline, up to 130' AGL/959' MSL.
Rwy 21, vehicle on road 575' from DER, on centerline, 15' AGL/824' MSL.
Trees and poles beginning 285' from DER, 16' left of centerline, up to 157' AGL/947' MSL.
Trees and pole beginning 116' from DER, 1' right of centerline, up to 123' AGL/912' MSL.

MANSFIELD, OH

MANSFIELD LAHM RGNL (MFD)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 12MAR09 (09071) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 5, trees 1337' from DER, 209' right of centerline, 78' AGL/1318' MSL.
Trees 1494' from DER, 410' left of centerline, 80' AGL/1330' MSL.
Rwy 32, trees 2399' from DER, 868' right of centerline, 90' AGL/1310' MSL.

26190

MARION, IN (SEE MARION, OH IN ENTRY BELOW)

MARION MUNI - MCKINNEY FLD (MZZ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 20JUN19 (25275) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 4, terrain, NAVAID, pole beginning abeam DER, 124' left of centerline, up to 854' MSL.
Pole, NAVAID beginning 34' from DER, 124' right of centerline, up to 852' MSL.
Terrain beginning 68' from DER, 412' right of centerline, up to 856' MSL.
Tree 534' from DER, 612' left of centerline, 890' MSL.
Trees beginning 775' from DER, 435' left of centerline, up to 895' MSL.
Trees beginning 929' from DER, 694' right of centerline, up to 65' AGL/914' MSL.
Trees beginning 1082' from DER, 13' left of centerline, up to 915' MSL.
Trees beginning 1283' from DER, 8' right of centerline, up to 921' MSL.
Trees beginning 1672' from DER, 107' left of centerline, up to 927' MSL.
Trees beginning 1852' from DER, 30' left of centerline, up to 936' MSL.
Trees beginning 2280' from DER, 42' right of centerline, up to 927' MSL.
Trees beginning 2749' from DER, 838' left of centerline, up to 942' MSL.
Tree 3145' from DER, 1200' right of centerline, 937' MSL.
Rwy 15, trees beginning 77' from DER, 224' left of centerline, up to 921' MSL.
Terrain 116' from DER, 462' right of centerline, 855' MSL.
Vegetation, terrain beginning 162' from DER, 282' right of centerline, up to 858' MSL.
Trees beginning 431' from DER, 239' left of centerline, up to 925' MSL.
Tree 539' from DER, 269' right of centerline, 51' AGL/901' MSL.
Tree, pole, vehicle on traverse way beginning 569' from DER, 63' left of centerline, up to 926' MSL.
Tree 676' from DER, 393' right of centerline, 904' MSL.
Tree 701' from DER, 331' right of centerline, 73' AGL/914' MSL.
Trees beginning 780' from DER, 361' right of centerline, up to 95' AGL/941' MSL.
Trees beginning 870' from DER, 361' right of centerline, up to 102' AGL/943' MSL.
Tree, pole beginning 1102' from DER, 20' right of centerline, up to 107' AGL/948' MSL.
Trees beginning 2580' from DER, 70' left of centerline, up to 942' MSL.
Rwy 22, pole 902' from DER, 572' left of centerline, 24' AGL/881' MSL.
Tree 1651' from DER, 605' right of centerline, 45' AGL/904' MSL.
Tree, pole beginning 1717' from DER, 760' right of centerline, up to 921' MSL.
Rwy 33, sign 11' from DER, 72' right of centerline, 3' AGL/859' MSL.
Vegetation 61' from DER, 242' left of centerline, 11' AGL/864' MSL.
Pole, vehicle on traverse way, tree, transmission line beginning 366' from DER, 261' left of centerline, up to 38' AGL/895' MSL.
Tree 725' from DER, 427' left of centerline, 908' MSL.
Trees beginning 795' from DER, 507' right of centerline, up to 928' MSL.
Tree, pole beginning 815' from DER, 362' left of centerline, up to 58' AGL/913' MSL.
Tree, pole beginning 889' from DER, 4' right of centerline, up to 931' MSL.
Tree 986' from DER, 741' left of centerline, 88' AGL/941' MSL.
Trees beginning 1006' from DER, 130' left of centerline, up to 94' AGL/946' MSL.
Tree 2839' from DER, 1245' left of centerline, 948' MSL.
Tree 2989' from DER, 1133' left of centerline, 950' MSL.
Trees beginning 3140' from DER, 1063' left of centerline, up to 959' MSL.
Trees beginning 3257' from DER, 1' left of centerline, up to 111' AGL/965' MSL.
Tree 3426' from DER, 106' right of centerline, 947' MSL.
Tree 3579' from DER, 144' right of centerline, 952' MSL.
Trees beginning 3695' from DER, 29' right of centerline, up to 958' MSL.

29 OCT 2026 to 26 NOV 2026

MARION, OH (SEE MARION, IN IN ENTRY ABOVE)

MARION MUNI (MNN)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 30AUG07 (25275) (FAA)

DEPARTURE PROCEDURE:

Rwy 25, climb heading 245° to 1600 before turning right.

TAKEOFF OBSTACLE NOTES:

Rwy 7, trees 3283' from DER, 273' left of centerline, up to 89' AGL/1088' MSL.
Multiple trees beginning 36' from DER, 280' right of centerline, up to 43' AGL/1033' MSL.
Rwy 13, trees 512' from DER, 277' left of centerline, up to 100' AGL/1089' MSL.
Road 491' from DER, 15' AGL/1004' MSL.
Rwy 25, obstruction light on antenna 419' from DER, 407' left of centerline, up to 13' AGL/1008' MSL.
Road 434' from DER, 15' AGL/1004' MSL.
Rwy 31, trees 2186' from DER, up to 100' AGL/1089' MSL.
Road 355' from DER, 485' left of centerline, 15' AGL/1004' MSL.

TAKEOFF MINS

26190

MARYSVILLE, OH

UNION COUNTY (MRT)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 30NOV23 (23334) (FAA)

TAKEOFF MINIMUMS:

Rwys 8, 26, NA-Environmental.

TAKEOFF OBSTACLE NOTES:

Rwy 9, sign 12' from DER, 51' left of centerline, 4' AGL/999' MSL.
Trees, light pole beginning 16' from DER, 78' left of centerline, up to 1000' MSL.
Pole 290' from DER, 499' left of centerline, 40' AGL/1032' MSL.
Pole, traverse ways beginning 364' from DER, 169' left of centerline, up to 41' AGL/1033' MSL.
Trees, traverse ways beginning 479' from DER, 27' left of centerline, up to 69' AGL/1063' MSL.
Traverse ways beginning 591' from DER, 5' right of centerline, up to 1018' MSL.
Bldg, trees beginning 721' from DER, 199' left of centerline, up to 1080' MSL.
Poles beginning 1034' from DER, 398' right of centerline, up to 52' AGL/1038' MSL.
Trees beginning 1572' from DER, 158' left of centerline, up to 1081' MSL.
Trees beginning 1720' from DER, 131' left of centerline, up to 1084' MSL.
Trees beginning 1909' from DER, 175' left of centerline, up to 1088' MSL.
Trees beginning 1946' from DER, 145' left of centerline, up to 1090' MSL.
Rwy 27, sign 10' from DER, 52' right of centerline, 4' AGL/1022' MSL.
Tree 42' from DER, 471' right of centerline, 1027' MSL.
Buildings, tree, pole beginning 56' from DER, 396' right of centerline, up to 30' AGL/1037' MSL.
Pole 218' from DER, 337' left of centerline, 33' AGL/1034' MSL.
Trees beginning 458' from DER, 526' right of centerline, up to 63' AGL/1066' MSL.
Trees 1893' from DER, 808' right of centerline, 1069' MSL.
Antenna 2753' from DER, 463' right of centerline, 1094' MSL.

MEDINA, OH

MEDINA MUNI (1G5)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4A 09JUL26 (26190) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 1, building 14' from DER, 378' left of centerline, 1200' MSL.
Building 15' from DER, 247' right of centerline, 1209' MSL.
Building 15' from DER, 264' left of centerline, 1202' MSL.
Building 16' from DER, 283' right of centerline, 1212' MSL.
Trees 59' from DER, 426' left of centerline, 100' AGL/1285' MSL.
Trees, building beginning 63' from DER, 197' left of centerline, up to 100' AGL/1288' MSL.
Trees, pole, terrain, building beginning 67' from DER, 32' right of centerline, up to 100' AGL/1291' MSL.
Trees beginning 367' from DER, 202' left of centerline, up to 100' AGL/1291' MSL.
Trees 371' from DER, 27' right of centerline, 100' AGL/1295' MSL.
Trees beginning 375' from DER, 21' right of centerline, up to 100' AGL/1301' MSL.
Trees beginning 678' from DER, 5' right of centerline, up to 100' AGL/1305' MSL.
Trees beginning 1277' from DER, 218' left of centerline, up to 100' AGL/1301' MSL.
Trees, pole beginning 1589' from DER, on centerline, up to 100' AGL/1308' MSL.
Trees beginning 2192' from DER, 4' left of centerline, up to 100' AGL/1305' MSL.
Trees beginning 4317' from DER, 42' left of centerline, up to 100' AGL/1308' MSL.
Trees 4621' from DER, 47' left of centerline, 100' AGL/1311' MSL.
Trees 4924' from DER, 53' left of centerline, 100' AGL/1314' MSL.
Trees 4929' from DER, 176' right of centerline, 100' AGL/1314' MSL.
Rwy 9, tree 57' from DER, 416' right of centerline, 1190' MSL.
Tree 328' from DER, 557' right of centerline, 1238' MSL.
Trees beginning 501' from DER, 401' right of centerline, up to 1243' MSL.
Tree 816' from DER, 322' left of centerline, 1205' MSL.
Tree 1011' from DER, 584' left of centerline, 1215' MSL.
Trees beginning 1048' from DER, 45' left of centerline, up to 1239' MSL.
Tree 1751' from DER, 525' left of centerline, 1246' MSL.
Tower 3626' from DER, 534' left of centerline, 189' AGL/1321' MSL.
Rwy 19, trees 96' from DER, 315' left of centerline, 100' AGL/1255' MSL.
Trees beginning 100' from DER, 85' left of centerline, up to 100' AGL/1268' MSL.
Trees beginning 104' from DER, 111' right of centerline, up to 100' AGL/1268' MSL.
Rwy 27, tree, terrain beginning 10' from DER, 272' right of centerline, up to 1254' MSL.
Tree, vegetation beginning 49' from DER, 278' left of centerline, up to 1243' MSL.
Trees, vehicle on road, building beginning 188' from DER, 4' right of centerline, up to 80' AGL/1257' MSL.
Tree 205' from DER, 479' left of centerline, 1251' MSL.
Trees, pole beginning 281' from DER, 288' left of centerline, up to 1262' MSL.
Trees beginning 698' from DER, 281' left of centerline, up to 1275' MSL.
Trees, building beginning 969' from DER, 83' left of centerline, up to 1284' MSL.
CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

MEDINA, OH (CON'T)

MEDINA MUNI (1G5) (CON'T)

Rwy 27 (CON'T), trees beginning 1771' from DER, 54' right of centerline, up to 101' AGL/1295' MSL.
Trees beginning 2030' from DER, 484' left of centerline, up to 1290' MSL.
Trees beginning 2092' from DER, 211' left of centerline, up to 1310' MSL.
Trees beginning 2388' from DER, 315' left of centerline, up to 1314' MSL.
Tree 2532' from DER, 750' left of centerline, 1317' MSL.
Trees beginning 2566' from DER, 65' left of centerline, up to 1319' MSL.

MICHIGAN CITY, IN

MICHIGAN CITY MUNI-PHILLIPS FLD (MGC)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2A 07SEP23 (23250) (FAA)

DEPARTURE PROCEDURE:

Rwy 20, climb on heading 203° to 1200 before turning left.

TAKEOFF OBSTACLE NOTES:

Rwy 2, pole 12' from DER, 427' left of centerline, 28' AGL/659' MSL.
Tree 12' from DER, 493' left of centerline, 674' MSL.
Terrain 13' from DER, 172' right of centerline, 643' MSL.
Tree 51' from DER, 349' left of centerline, 685' MSL.
Tree 65' from DER, 443' left of centerline, 691' MSL.
Terrain 129' from DER, 497' right of centerline, 649' MSL.
Trees beginning 198' from DER, 337' left of centerline, up to 710' MSL.
Traverse way 303' from DER, 568' right of centerline, 667' MSL.
Pole, tree beginning 344' from DER, 213' right of centerline, up to 37' AGL/687' MSL.
Trees beginning 468' from DER, 231' left of centerline, up to 712' MSL.
Tree 615' from DER, 380' right of centerline, 711' MSL.
Trees, antenna beginning 641' from DER, 46' right of centerline, up to 731' MSL.
Trees beginning 949' from DER, 67' left of centerline, up to 716' MSL.
Trees beginning 1091' from DER, 347' left of centerline, up to 723' MSL.
Trees, antenna beginning 1250' from DER, 2' right of centerline, up to 733' MSL.
Trees beginning 1553' from DER, 89' left of centerline, up to 726' MSL.
Trees beginning 1657' from DER, 6' left of centerline, up to 731' MSL.
Trees beginning 1709' from DER, on centerline, up to 734' MSL.
Antenna, trees beginning 1778' from DER, on centerline, up to 101' AGL/742' MSL.
Tree 1796' from DER, 655' right of centerline, 745' MSL.
Trees beginning 1815' from DER, 134' right of centerline, up to 748' MSL.
Trees beginning 2006' from DER, 166' right of centerline, up to 753' MSL.
Trees beginning 2025' from DER, 94' right of centerline, up to 754' MSL.
Trees beginning 2123' from DER, 301' right of centerline, up to 758' MSL.
Tree 2160' from DER, 199' left of centerline, 743' MSL.
Trees beginning 2181' from DER, 108' left of centerline, up to 744' MSL.
Trees beginning 2244' from DER, 87' left of centerline, up to 746' MSL.
Trees beginning 2251' from DER, 93' right of centerline, up to 760' MSL.
Trees, electrical system, transmission line beginning 2300' from DER, 11' right of centerline, up to 765' MSL.
Trees beginning 2527' from DER, 22' left of centerline, up to 751' MSL.
Transmission line, trees beginning 3193' from DER, 182' left of centerline, up to 136' AGL/778' MSL.
Transmission line 4247' from DER, 989' right of centerline, 121' AGL/769' MSL.
Rwy 20, trees, fences, sign, traverse ways, pole beginning 7' from DER, 27' right of centerline, up to 727' MSL.
Terrain 20' from DER, 393' left of centerline, 658' MSL.
Terrain 191' from DER, 489' left of centerline, 663' MSL.
Fences beginning 206' from DER, 140' left of centerline, up to 12' AGL/671' MSL.
Pole, fence, traverse ways beginning 213' from DER, 45' left of centerline, up to 25' AGL/687' MSL.
Tree, sign beginning 328' from DER, 39' left of centerline, up to 707' MSL.
Tree 1564' from DER, 582' right of centerline, 729' MSL.
Trees beginning 1641' from DER, 199' right of centerline, up to 749' MSL.
Trees beginning 1699' from DER, 8' left of centerline, up to 741' MSL.
Trees beginning 1732' from DER, 341' right of centerline, up to 762' MSL.
Trees beginning 1752' from DER, 23' right of centerline, up to 763' MSL.
Trees beginning 1847' from DER, 109' left of centerline, up to 764' MSL.
Trees beginning 2054' from DER, 11' right of centerline, up to 764' MSL.
Trees beginning 2085' from DER, 43' left of centerline, up to 766' MSL.
Trees beginning 2286' from DER, 59' left of centerline, up to 769' MSL.
Trees beginning 2359' from DER, 27' left of centerline, up to 770' MSL.
Trees beginning 2473' from DER, 1' right of centerline, up to 768' MSL.

29 OCT 2026 to 26 NOV 2026

26190

MIDDLEFIELD, OH

GEAUGA COUNTY (7G8)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 08JUN06 (06159) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 11, railroad 331' from DER, 315' left of centerline, 23' AGL/1182' MSL.
Trees 3144' from DER, 671' left of centerline, 100' AGL/1249' MSL.
Rwy 29, railroad 349' from DER, 521' left of centerline, 23' AGL/1212' MSL.
Multiple buildings 993' from DER, 294' right of centerline, 40' AGL/1239' MSL.
Trees 1875' from DER, 791' right of centerline, 100' AGL/1319' MSL.
Tank 2251' from DER, 578' right of centerline, 125' AGL/1315' MSL.

MIDDLETOWN, OH

MIDDLETOWN RGNL/HOOK FLD (MWO)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 20SEP12 (21140) (FAA)

TAKEOFF MINIMUMS:

Rwys 8, 26, NA-Environmental.
Rwy 23, 300-1¾ or std w/min climb of 880' per NM to 1000.

DEPARTURE PROCEDURE:

Rwy 5, climb heading 053° to 1500' before proceeding on course.
Rwy 23, climb heading 233° to 1300' before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 5, vehicles on roadway 17' from DER, left and right of centerline, up to 15' AGL/669' MSL.
Terrain 106' from DER, 447' left of centerline, 661' MSL.
Terrain 335' from DER, 395' left of centerline, 659' MSL.
Trees beginning 676' from DER, left and right of centerline, up to 126' AGL/766' MSL.
Poles beginning 1003' from DER, 259' right of centerline, up to 55' AGL/695' MSL.
Rwy 23, trees 1119' from DER, 76' right of centerline, 109' AGL/739' MSL.
Tower 1794' from DER, 603' left of centerline, 63' AGL/703' MSL.
Stack 1997' from DER, 961' left of centerline, 205' AGL/855' MSL.
Tree 1930' from DER, 903' left of centerline, 109' AGL/749' MSL.

MILLERSBURG, OH

HOLMES COUNTY (10G)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 20AUG15 (15232) (FAA)

TAKEOFF MINIMUMS:

Rwys 9, 27, 300-1.

TAKEOFF OBSTACLE NOTES:

Rwy 9, bushes 136' from DER, 235 left of centerline, up to 25' AGL/1200' MSL.
Rwy 27, trees beginning 212' from DER, 443' right of center line, up to 100' AGL/1287' MSL.
Trees and poles beginning 1220' from DER, 158' right of centerline, up to 100' AGL/1315' MSL.
Trees and buildings beginning 1116' from DER, 272' left of centerline, up to 100' AGL/1337' MSL.

MONTICELLO, IN

WHITE COUNTY (MCX)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 10NOV16 (16315) (FAA)

TAKEOFF MINIMUMS:

Rwy 36, 600-3 or std w/min climb of 265' per NM to 1400.

TAKEOFF OBSTACLE NOTES:

Rwy 18, trees beginning 23' from DER, 309' left of centerline, up to 739' MSL.
Trees beginning 35' from DER, 296' right of centerline, 731' MSL.
Trees and pole beginning 51' from DER, 16' right of centerline, up to 744' MSL.
Trees and building beginning 436' from DER, 3' left of centerline, up to 757' MSL.
Trees beginning 1284' from DER, 11' left of centerline, up to 775' MSL.
Trees beginning 1961' from DER, 27' right of centerline, up to 753' MSL.
Rwy 36, tree 983' from DER, 571' right of centerline, 754' MSL.
Tower 1.7 NM from DER, 1101' right of centerline, 292' AGL/973' MSL.
Tower 2.5 NM from DER, 4185' left of centerline, 420' AGL/1134' MSL.

26190

MT GILEAD, OH

MORROW COUNTY (4I9)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 12JUN25 (25163) (FAA)

TAKEOFF MINIMUMS:

Rwy 10, 300-1½ or std w/min climb of 455'/NM to 1400.

TAKEOFF OBSTACLE NOTES:

Rwy 10, pole 10' from DER, 33' right of centerline, 1' AGL/1086' MSL.
Trees beginning 43' from DER, 190' left of centerline, up to 28' AGL/1108' MSL.
Tree 678' from DER, 110' right of centerline, 25' AGL/1104' MSL.
Trees beginning 911' from DER, 265' right of centerline, up to 87' AGL/1169' MSL.
Tree 931' from DER, 382' left of centerline, 68' AGL/1150' MSL.
Trees beginning 1011' from DER, 506' left of centerline, up to 76' AGL/1162' MSL.
Tree 1608' from DER, 64' left of centerline, 73' AGL/1172' MSL.
Trees beginning 1619' from DER, 37' left of centerline, up to 84' AGL/1186' MSL.
Tree 1651' from DER, 260' right of centerline, 68' AGL/1172' MSL.
Trees beginning 1718' from DER, 255' right of centerline, up to 78' AGL/1188' MSL.
Trees beginning 1767' from DER, 19' left of centerline, up to 92' AGL/1196' MSL.
Trees beginning 1804' from DER, 97' right of centerline, up to 84' AGL/1200' MSL.
Trees, buildings beginning 1932' from DER, 53' left of centerline, up to 88' AGL/1198' MSL.
Trees beginning 1964' from DER, 96' right of centerline, up to 82' AGL/1209' MSL.
Trees, poles, electrical systems, vehicle on roads, buildings beginning 2067' from DER, 9' right of centerline, up to 82' AGL/1211' MSL.
Trees beginning 2298' from DER, 333' left of centerline, up to 74' AGL/1199' MSL.
Trees beginning 2381' from DER, 29' left of centerline, up to 81' AGL/1206' MSL.
Trees, buildings, vehicle on roads, poles, electrical systems beginning 2431' from DER, 10' left of centerline, up to 101' AGL/1229' MSL.
Trees, poles, vehicle on road, electrical system beginning 2787' from DER, 49' right of centerline, up to 80' AGL/1212' MSL.
Trees, electrical system beginning 2836' from DER, 89' right of centerline, up to 67' AGL/1216' MSL.
Trees, pole, vehicle on road, electrical systems, buildings beginning 2871' from DER, 55' right of centerline, up to 69' AGL/1219' MSL.
Trees, building beginning 2929' from DER, 20' left of centerline, up to 103' AGL/1251' MSL.
Trees, vehicle on road, pole beginning 3031' from DER, 63' right of centerline, up to 72' AGL/1221' MSL.
Tree 3092' from DER, 163' right of centerline, 76' AGL/1226' MSL.
Trees, vehicles on roads, electrical systems, poles beginning 3095' from DER, 28' right of centerline, up to 85' AGL/1234' MSL.
Trees, building beginning 3165' from DER, 35' left of centerline, up to 108' AGL/1252' MSL.
Trees beginning 3892' from DER, 501' left of centerline, up to 113' AGL/1256' MSL.
Trees beginning 5147' from DER, 198' right of centerline, up to 110' AGL/1240' MSL.
Tree 1.1 NM from DER, 2286' left of centerline, 107' AGL/1270' MSL.
Rwy 28, pole 10' from DER, 30' left of centerline, 1' AGL/1076' MSL.
Pole 213' from DER, 524' right of centerline, 37' AGL/1102' MSL.
Tree 245' from DER, 396' right of centerline, 37' AGL/1104' MSL.
Trees beginning 370' from DER, 295' right of centerline, up to 60' AGL/1123' MSL.
Pole 819' from DER, 671' left of centerline, 34' AGL/1097' MSL.
Trees beginning 873' from DER, 413' left of centerline, up to 46' AGL/1111' MSL.
Trees beginning 914' from DER, 268' right of centerline, up to 73' AGL/1138' MSL.
Trees beginning 3397' from DER, 235' left of centerline, up to 139' AGL/1161' MSL.
Trees beginning 3485' from DER, 162' left of centerline, up to 143' AGL/1166' MSL.
Tree 3679' from DER, 50' right of centerline, 144' AGL/1167' MSL.

MT VERNON, OH

KNOX COUNTY (4I3)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 15JAN09 (09015) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 28, trees 2121' from DER, 361' right of centerline, 47' AGL/1246' MSL.

MUNCIE, IN

DELAWARE COUNTY RGNL (MIE)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4A 12DEC13 (13346) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 3, pole 717' from DER, 596' right of centerline, 19' AGL/954' MSL.
Trees beginning 771' from DER, 413' right of centerline, up to 56' AGL/991' MSL.
Trees beginning 2463' from DER, 44' left of centerline, up to 76' AGL/1007' MSL.
Towers and pole 3802' from DER, 702' left of centerline, up to 121' AGL/1049' MSL.
Rwy 14, trees beginning 2062' from DER, 1005' right of centerline, up to 68' AGL/1013' MSL.
CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

MUNCIE, IN (CON'T)

DELAWARE COUNTY RGNL (MIE) (CON'T)

Rwy 21, rising terrain beginning 6' from DER, 304' right of centerline, up to 943' MSL.
Flag pole 851' from DER, 627' left of centerline, 25' AGL/962' MSL.
Building 941' from DER, 670' left of centerline, 32' AGL/969' MSL.
Trees beginning 946' from DER, 39' left of centerline, up to 81' AGL/1033' MSL.
Trees beginning 1119' from DER, 207' right of centerline, up to 96' AGL/1032' MSL.
Rwy 32, trees and bushes beginning 86' from DER, 447' left of centerline, up to 17' AGL/940' MSL.

NAPOLEON, OH

HENRY COUNTY (7W5)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 12JUN25 (25163) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 10, vegetation 115' from DER, 137' left of centerline, 17' AGL/696' MSL.
Pole, vehicles on roadway beginning 442' from DER, 574' left of centerline, up to 715' MSL.
Tree 822' from DER, 612' left of centerline, 758' MSL.
Trees beginning 861' from DER, 597' left of centerline, up to 102' AGL/785' MSL.
Pole 1063' from DER, 701' right of centerline, 719' MSL.
Trees beginning 1782' from DER, 436' right of centerline, up to 755' MSL.
Tree 3696' from DER, 352' right of centerline, 778' MSL.
Rwy 28, terrain 79' from DER, 488' right of centerline, 683' MSL.
Tree 114' from DER, 128' left of centerline, 684' MSL.
Vegetation 117' from DER, 110' right of centerline, 13' AGL/687' MSL.
Vehicles on roadway beginning 424' from DER, 230' left of centerline, up to 694' MSL.
Tree, building beginning 721' from DER, 442' right of centerline, up to 708' MSL.
Tree, building beginning 795' from DER, 366' right of centerline, up to 717' MSL.
Trees beginning 879' from DER, 308' right of centerline, up to 727' MSL.
Trees beginning 964' from DER, 411' right of centerline, up to 743' MSL.
Trees beginning 1036' from DER, 432' right of centerline, up to 755' MSL.
Trees beginning 2114' from DER, 180' left of centerline, up to 770' MSL.
Tree 3455' from DER, 476' right of centerline, 782' MSL.
Trees beginning 3469' from DER, 377' right of centerline, up to 786' MSL.
Trees beginning 3724' from DER, 282' right of centerline, up to 790' MSL.
Tree 4085' from DER, 1512' left of centerline, 108' AGL/786' MSL.
Tree 4435' from DER, 562' right of centerline, 115' AGL/792' MSL.

NAPPANEE, IN

NAPPANEE MUNI (C03)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 19FEB81 (81036) (FAA)

TAKEOFF MINIMUMS:

Rwy 9, 300-1.

NEW CASTLE, IN

NEW CASTLE HENRY COUNTY MARLATT FLD (UWL)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1B 19MAR26 (26078) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 10, light pole 9' from DER, 14' left of centerline, 2' AGL/1092' MSL.
Trees beginning 1658' from DER, 156' right of centerline, up to 1142' MSL.
Tree 1822' from DER, 92' left of centerline, 65' AGL/1146' MSL.
Trees beginning 1865' from DER, 22' right of centerline, up to 69' AGL/1153' MSL.
Tree 1931' from DER, 697' right of centerline, 1154' MSL.
Tree 1933' from DER, 817' right of centerline, 91' AGL/1176' MSL.
Trees beginning 1951' from DER, 571' right of centerline, up to 93' AGL/1179' MSL.
Trees beginning 2029' from DER, 530' right of centerline, up to 103' AGL/1190' MSL.
Rwy 28, pole, vehicle on road beginning 160' from DER, 464' right of centerline, up to 30' AGL/1101' MSL.
Poles beginning 346' from DER, 462' right of centerline, up to 32' AGL/1105' MSL.
Pole 444' from DER, 462' right of centerline, 35' AGL/1107' MSL.

26190

NEW LEXINGTON, OH

ED NEWLON FLD (I86)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 30AUG84 (24305) (FAA)

TAKEOFF MINIMUMS:

Rwys 8, 26, 300-1.

NEW PHILADELPHIA, OH

HARRY CLEVER FLD (PHD)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3A 01FEB18 (22083) (FAA)

TAKEOFF MINIMUMS:

Rwys 12, 30, NA-Environmental.

Rwy 15, 500-2½ or std w/min climb to 420' per NM to 1500.

Rwy 33, std w/min climb of 210' per NM to 1500.

DEPARTURE PROCEDURE:

Rwy 15, climb heading 147° to 1500 before turning.

Rwy 33, climb heading 327° to 1600 before turning.

TAKEOFF OBSTACLE NOTES:

Rwy 15, poles beginning 194' from DER, 431' left of centerline, up to 56' AGL/935' MSL.
Vehicle on road beginning 240' from DER, 146' left of centerline, up to 15' AGL/902' MSL.
Rising terrain and trees beginning 320' from DER, 37' left of centerline, up to 100' AGL/1319' MSL.
Siren 383' from DER, 584' left of centerline, 81' AGL/940' MSL.
Tower 3659' from DER, 9' left of centerline, 124' AGL/983' MSL.
Vehicle on road beginning 78' from DER, 45' right of centerline, up to 15' AGL/904' MSL.
Trees beginning 79' from DER, 13' right of centerline, up to 100' AGL/972' MSL.
Poles beginning 678' from DER, 3' right of centerline, up to 61' AGL/920' MSL.
Rwy 33, trees beginning 41' from DER, 64' left of centerline, up to 100' AGL/965' MSL.
Vehicle on road beginning 108' from DER, 26' left of centerline, up to 15' AGL/914' MSL.
Headstone 142' from DER, 272' left of centerline, 6' AGL/900' MSL.
Building 167' from DER, 511' left of centerline, 34' AGL/928' MSL.
OL on pole 261' from DER, 213' left of centerline, 37' AGL/931' MSL.
Vehicle on road beginning 12' from DER, 28' right of centerline, up to 15' AGL/914' MSL.
Rising terrain and trees beginning 36' from DER, 22' right of centerline, up to 100' AGL/984' MSL.
Fence 83' from DER, 217' right of centerline, 6' AGL/900' MSL.
Poles beginning 502' from DER, 368' right of centerline, up to 28' AGL/924' MSL.
Tower 2.6 NM from DER, 2107' right of centerline, 406' AGL/1319' MSL.

NEWARK, OH

LICKING COUNTY RGNL (VTA)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 20JUN19 (24305) (FAA)

TAKEOFF MINIMUMS:

Rwy 9, 600-3 w/min climb of 225' per NM to 1700 or std w/min climb of 300' per NM to 1600 or 1000-3 for VCOA.

Rwy 27, 400-2½ or std w/min climb of 220' per NM to 1200.

DEPARTURE PROCEDURE:

Rwy 9, climb heading 093° to 1700 before proceeding on course.

Rwy 27, climb on heading 273º to 1400 before proceeding on course.

VCOA:

Rwy 9, obtain ATC approval for VCOA when requesting IFR clearance. Climb in visual conditions to cross Licking County Rgnl airport at or above 1700 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 9, tree, terrain beginning 25' from DER, 173' left of centerline, up to 889' MSL.
Lighting 40' from DER, 77' right of centerline, 871' MSL.
Building 93' from DER, 510' right of centerline, 879' MSL.
Transmission line, fence beginning 105' from DER, 249' right of centerline, up to 907' MSL.
Trees, poles, building beginning 107' from DER, 454' left of centerline, up to 71' AGL/934' MSL.
Tree 237' from DER, 554' right of centerline, 922' MSL.
Trees, pole beginning 558' from DER, 29' right of centerline, up to 942' MSL.
Tree 2651' from DER, 263' right of centerline, 949' MSL.
Trees beginning 2741' from DER, 473' right of centerline, up to 953' MSL.
Tree 4800' from DER, 1713' right of centerline, 1005' MSL.
Trees beginning 4884' from DER, 1409' right of centerline, up to 1008' MSL.
Trees, buildings beginning 5018' from DER, 1522' right of centerline, up to 1018' MSL.
Trees, building beginning 5164' from DER, 1437' right of centerline, up to 1032' MSL.
Trees, buildings beginning 5288' from DER, 1367' right of centerline, up to 1041' MSL.
Trees, building beginning 5679' from DER, 1429' right of centerline, up to 1055' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026

NEWARK, OH (CON'T)

LICKING COUNTY RGNL (VTA) (CON'T)

Rwy 9 (CON'T), trees beginning 5909' from DER, 1352' right of centerline, up to 1058' MSL.
Tree 1 NM from DER, 1488' right of centerline, 1065' MSL.
Trees, building beginning 1 NM from DER, 1429' right of centerline, up to 1076' MSL.
Trees beginning 1 NM from DER, 1430' right of centerline, up to 1101' MSL.
Trees beginning 1 NM from DER, 1834' right of centerline, up to 1110' MSL.
Trees beginning 1.1 NM from DER, 1580' right of centerline, up to 69' AGL/1118' MSL.
Trees beginning 1.1 NM from DER, 1546' right of centerline, up to 1120' MSL.
Trees, building beginning 1.1 NM from DER, 1318' right of centerline, up to 1121' MSL.
Trees beginning 1.1 NM from DER, 1230' right of centerline, up to 1122' MSL.
Trees buildings beginning 1.1 NM from DER, 1399' right of centerline, up to 1125' MSL.
Trees beginning 1.3 NM from DER, 1932' right of centerline, up to 1130' MSL.
Tree 1.3 NM from DER, 2058' right of centerline, 1132' MSL.
Trees, buildings beginning 1.3 NM from DER, 297' right of centerline, up to 90' AGL/1151' MSL.
Trees beginning 1.3 NM from DER, 223' left of centerline, up to 1121' MSL.
Trees beginning 1.3 NM from DER, 168' left of centerline, up to 1127' MSL.
Trees beginning 1.3 NM from DER, 66' left of centerline, up to 1150' MSL.
Trees beginning 1.4 NM from DER, 62' left of centerline, up to 151' AGL/1151' MSL.
Trees beginning 1.6 NM from DER, 659' right of centerline, up to 1163' MSL.
Trees beginning 1.6 NM from DER, 8' right of centerline, up to 1168' MSL.
Trees, building beginning 1.6 NM from DER, 107' right of centerline, up to 82' AGL/1179' MSL.
Antenna 2.4 NM from DER, 2425' left of centerline, 360' AGL/1394' MSL.
Tower 2.4 NM from DER, 2371' left of centerline, 362' AGL/1396' MSL.
Antenna 2.4 NM from DER, 2430' left of centerline, 360' AGL/1396' MSL.
Rwy 27, terrain 2' from DER, 251' right of centerline, 884' MSL.
Terrain 11' from DER, 486' right of centerline, 886' MSL.
Pole, vehicles on road beginning 49' from DER, 199' left of centerline, up to 910' MSL.
Pole, vehicles on road beginning 188' from DER, 32' left of centerline, up to 29' AGL/912' MSL.
Trees, poles, bldg twr beginning 543' from DER, 120' left of centerline, up to 968' MSL.
Vehicles on road 604' from DER, 31' right of centerline, 902' MSL.
Pole 697' from DER, 139' right of centerline, 919' MSL.
Poles, building beginning 796' from DER, 206' right of centerline, up to 920' MSL.
Pole 972' from DER, 313' right of centerline, 926' MSL.
Trees beginning 1033' from DER, 11' right of centerline, up to 933' MSL.
Trees, pole beginning 1196' from DER, 64' right of centerline, up to 963' MSL.
Tree 1533' from DER, 7' right of centerline, 971' MSL.
Tree 1591' from DER, 682' right of centerline, 973' MSL.
Trees beginning 1645' from DER, 189' right of centerline, up to 976' MSL.
Trees beginning 1750' from DER, 321' right of centerline, up to 979' MSL.
Trees, poles beginning 2005' from DER, 58' right of centerline, up to 985' MSL.
Tree, poles beginning 2270' from DER, 154' left of centerline, up to 970' MSL.
Tree 3354' from DER, 1131' right of centerline, 993' MSL.
Tree 3381' from DER, 384' left of centerline, 974' MSL.
Tree 3776' from DER, 1384' left of centerline, 983' MSL.
Tree 3791' from DER, 1212' right of centerline, 996' MSL.
Tree 3892' from DER, 1160' right of centerline, 998' MSL.
Tree 3899' from DER, 1424' left of centerline, 992' MSL.
Tree 3984' from DER, 1537' left of centerline, 994' MSL.
Trees beginning 4015' from DER, 1135' right of centerline, up to 1003' MSL.
Trees beginning 4020' from DER, 1325' left of centerline, up to 998' MSL.
Trees beginning 4550' from DER, 755' left of centerline, up to 1009' MSL.
Tree 4739' from DER, 913' left of centerline, 1011' MSL.
Trees beginning 4835' from DER, 634' left of centerline, up to 1021' MSL.
Trees beginning 4982' from DER, 966' left of centerline, up to 1029' MSL.
Tree 1.3 NM from DER, 1932' right of centerline, 1094' MSL.
Tree 1.3 NM from DER, 2173' right of centerline, 1099' MSL.
Trees beginning 1.3 NM from DER, 1874' right of centerline, up to 1109' MSL.
Tree 2.1 NM from DER, 2988' right of centerline, 121' AGL/1204' MSL.

29 OCT 2026 to 26 NOV 2026

26190

NORTH VERNON, IN

NORTH VERNON (OVO)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 27AUG09 (09239) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 5, tree 1866' from DER, 690' left of centerline, 62' AGL/821' MSL.
Tree 428' from DER, 516' right of centerline, 22' AGL/781' MSL.
Rwy 15, fence beginning 259' from DER, crossing left to right, 11' AGL/765' MSL.
Trees beginning 469' from DER, 100' left of centerline, up to 115' AGL/864' MSL.
Tree 1509' from DER, 472' right of centerline, 59' AGL/818' MSL.
Rwy 23, trees beginning 1856' from DER, 94' left of centerline, up to 93' AGL/842' MSL.
Tree 3348' from DER 675' right of centerline, 97' AGL/846' MSL.
Rwy 33, fence beginning 304' from DER, 138' left of centerline, 11' AGL/761' MSL.
Tree 2592' from DER, 596' left of centerline, 90' AGL/839' MSL.
Power pole 751' from DER, 102' right of centerline, 25' AGL/774' MSL.

NORWALK, OH

NORWALK/HURON COUNTY (5A1)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 03NOV22 (24361) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 10, vegetation 24' from DER, 253' left of centerline, 853' MSL.
Tree 47' from DER, 455' right of centerline, 894' MSL.
Poles, traverse ways, fence, trees beginning 92' from DER, 243' right of centerline, up to 61' AGL/918' MSL.
Poles, trees, traverse way, building beginning 461' from DER, 189' right of centerline, up to 929' MSL.
Trees beginning 673' from DER, 247' left of centerline, up to 914' MSL.
Trees beginning 719' from DER, 210' left of centerline, up to 93' AGL/939' MSL.
Trees beginning 852' from DER, 178' right of centerline, up to 930' MSL.
Trees, pole beginning 855' from DER, 197' left of centerline, up to 104' AGL/950' MSL.
Trees beginning 1013' from DER, 200' left of centerline, up to 103' AGL/953' MSL.
Trees beginning 1217' from DER, 40' left of centerline, up to 103' AGL/955' MSL.
Trees beginning 1799' from DER, 230' right of centerline, up to 75' AGL/931' MSL.
Trees beginning 2482' from DER, 260' right of centerline, up to 72' AGL/933' MSL.
Trees beginning 2645' from DER, 16' left of centerline, up to 956' MSL.
Trees beginning 3125' from DER, 5' right of centerline, up to 945' MSL.
Trees beginning 3240' from DER, 13' left of centerline, up to 102' AGL/959' MSL.
Tree 3272' from DER, 325' left of centerline, 105' AGL/963' MSL.
Trees beginning 3276' from DER, 17' left of centerline, up to 109' AGL/967' MSL.
Trees beginning 3303' from DER, 1' left of centerline, up to 112' AGL/975' MSL.
Trees beginning 3346' from DER, 40' right of centerline, up to 85' AGL/947' MSL.
Tree 3385' from DER, 47' right of centerline, 83' AGL/948' MSL.
Trees beginning 3391' from DER, 8' right of centerline, up to 93' AGL/954' MSL.
Trees beginning 3494' from DER, 21' right of centerline, up to 86' AGL/956' MSL.
Trees beginning 3495' from DER, 11' right of centerline, up to 93' AGL/962' MSL.
Tree 3515' from DER, 23' right of centerline, 93' AGL/963' MSL.
Trees beginning 3532' from DER, 12' right of centerline, up to 96' AGL/966' MSL.
Trees beginning 3599' from DER, 3' right of centerline, up to 97' AGL/969' MSL.
Tree 4933' from DER, 1799' right of centerline, 976' MSL.
Rwy 28, tree 50' from DER, 344' left of centerline, 937' MSL.
Trees beginning 55' from DER, 192' right of centerline, up to 15' AGL/846' MSL.
Trees, vegetation, tower beginning 95' from DER, 116' left of centerline, up to 100' AGL/940' MSL.
Trees beginning 120' from DER, 182' right of centerline, up to 847' MSL.
Tree 1298' from DER, 841' right of centerline, 901' MSL.
Trees beginning 1448' from DER, 830' right of centerline, up to 907' MSL.

OTTAWA, OH

PUTNAM COUNTY (OWX)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 27AUG09 (09239) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, trees 1342' from DER, 578' right of centerline, 100' AGL/854' MSL.
Tree 1978' from DER, 5' left of centerline, 50' AGL/814' MSL.
Rwy 27, road 1' from DER, 219' right of centerline, 15' AGL/768' MSL.
Multiple trees and pole beginning 1606' from DER, 303' left of centerline, up to 100' AGL/854' MSL.

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

26190

OXFORD, OH

MIAMI UNIVERSITY (OXD)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2A 12JUN25 (25163) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 5, trees beginning 105' from DER, 424' right of centerline, up to 1048' MSL.
Trees, pole beginning 266' from DER, 119' right of centerline, up to 1055' MSL.
Trees, transmission lines, building beginning 589' from DER, 3' left of centerline, up to 65' AGL/1095' MSL.
Trees beginning 798' from DER, 169' right of centerline, up to 45' AGL/1059' MSL.
Poles, trees, beginning 927' from DER, 34' right of centerline, up to 1086' MSL.
Tree 1355' from DER, 648' left of centerline, 1096' MSL.
Tree 1430' from DER, 751' left of centerline, 1101' MSL.
Trees beginning 1520' from DER, 561' left of centerline, up to 85' AGL/1107' MSL.
Trees beginning 1554' from DER, 544' left of centerline, up to 86' AGL/1109' MSL.
Trees beginning 1594' from DER, 536' left of centerline, up to 91' AGL/1112' MSL.
Tree 1707' from DER, 434' right of centerline, 1087' MSL.
Tree, vehicles on road beginning 2' from DER, 100' right of centerline, up to 1061' MSL.
Tree, transmission line beginning 109' from DER, 468' left of centerline, up to 1078' MSL.
Trees beginning 181' from DER, 384' left of centerline, up to 46' AGL/1084' MSL.
Tree 254' from DER, 410' left of centerline, 1087' MSL.
Trees, building beginning 263' from DER, 356' left of centerline, up to 53' AGL/1091' MSL.
Building, tree, vehicles on road beginning 269' from DER, on centerline, up to 27' AGL/1062' MSL.
Tree 347' from DER, 352' left of centerline, 1093' MSL.
Tree 353' from DER, 509' left of centerline, 67' AGL/1102' MSL.
Trees, poles, building, transmission lines beginning 381' from DER, 3' left of centerline, up to 72' AGL/1107' MSL.
Tree 389' from DER, 324' right of centerline, 1064' MSL.
Building 471' from DER, 190' right of centerline, 17' AGL/1067' MSL.
Trees beginning 558' from DER, 52' right of centerline, up to 1085' MSL.
Trees beginning 831' from DER, 38' right of centerline, up to 1093' MSL.
Trees, tower, pole beginning 987' from DER, 72' left of centerline, up to 1109' MSL.
Trees beginning 1660' from DER, 225' left of centerline, up to 1116' MSL.
Tree 1666' from DER, 422' right of centerline, 1096' MSL.
Trees beginning 1682' from DER, 446' right of centerline, up to 1107' MSL.
Trees beginning 1846' from DER, 528' right of centerline, up to 83' AGL/1109' MSL.

PAINESVILLE, OH

CONCORD AIRPARK (2G1)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3A 11AUG22 (22223) (FAA)

TAKEOFF MINIMUMS:

Rwy 21, 400-2¾ or std w/min climb of 400' per NM to 1500.

DEPARTURE PROCEDURE:

Rwy 21, climb on heading 209° to 1500 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 3, trees beginning 336' from DER, 42' left of centerline, up to 100' AGL/1039' MSL.
Trees beginning 1064' from DER, 217' right of centerline, up to 100' AGL/1039' MSL.
Rwy 21, trees beginning 131' from DER, left and right of centerline, up to 100' AGL/1220' MSL.
Tower 1.2 NM from DER, 2020' right of centerline, 114' AGL/1223' MSL.

PERU, IN

PERU MUNI (I76)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 18JAN07 (07018) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 1, multiple trees beginning 2201' from DER, 321' left of centerline, 100' AGL/879' MSL.
Road plus vehicle beginning 407' from DER, 1524' right of centerline, 15' AGL/794' MSL.
Trees beginning 1656' from DER, 815' right of centerline, 100' AGL/879' MSL.
Rwy 19, multiple trees beginning 44' from DER, 204' left of centerline, 100' AGL/869' MSL.
Multiple trees beginning 588' from DER, 134' right of centerline, 100' AGL/859' MSL.

PIQUA, OH

PIQUA/HARTZELL FLD (I17)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 20OCT11 (21224) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 8, tree 2006' from DER, 515' left of centerline, 76' AGL/1062' MSL.

Rwy 26, vehicles on roadway, beginning 347' from DER, 578' left of centerline, up to 15' AGL/1024' MSL.

Trees and grain bin beginning 61' from DER, 321' left of centerline, up to 100' AGL/1119' MSL.

PLYMOUTH, IN

PLYMOUTH MUNI (C65)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 18JUL74 (74199) (FAA)

TAKEOFF MINIMUMS:

Rwys 10, 28, 300-1.

PORT CLINTON, OH

ERIE-OTTAWA INTL (PCW)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 7 07AUG25 (25219) (FAA)

TAKEOFF MINIMUMS:

Rwy 27, std w/min climb of 235'/NM to 1500, or 1000-3 for VCOA.

VCOA:

Rwy 27, obtain ATC approval for VCOA when requesting IFR clearance. Climb in visual conditions to cross Erie-Ottawa Intl airport at or above 1400 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 9, terrain 36' from DER, 427' right of centerline, 589' MSL.
Buildings beginning 306' from DER, 550' right of centerline, up to 18' AGL/609' MSL.
Electrical system 417' from DER, 581' left of centerline, 17' AGL/607' MSL.
Transmission line 562' from DER, 621' right of centerline, 41' AGL/631' MSL.
Poles, vehicles on road beginning 563' from DER, 49' right of centerline, up to 47' AGL/636' MSL.
Tree, vehicles on road, pole beginning 593' from DER, 1' left of centerline, up to 28' AGL/618' MSL.
Poles, transmission line beginning 758' from DER, 498' left of centerline, up to 43' AGL/630' MSL.
Trees, pole beginning 800' from DER, 312' left of centerline, up to 65' AGL/653' MSL.
Trees beginning 858' from DER, 11' right of centerline, up to 62' AGL/650' MSL.
Trees beginning 925' from DER, 343' left of centerline, up to 74' AGL/666' MSL.
Trees beginning 1135' from DER, 12' left of centerline, up to 88' AGL/677' MSL.
Trees beginning 1153' from DER, 8' right of centerline, up to 82' AGL/668' MSL.
Trees beginning 1513' from DER, 611' left of centerline, up to 91' AGL/684' MSL.
Trees beginning 1558' from DER, 363' left of centerline, up to 95' AGL/685' MSL.
Tree 3110' from DER, 928' right of centerline, 86' AGL/672' MSL.

Rwy 18, tree 57' from DER, 352' left of centerline, 592' MSL.
Buildings beginning 115' from DER, 446' left of centerline, up to 623' MSL.
Buildings, poles, tree beginning 217' from DER, 379' left of centerline, up to 627' MSL.
Trees, vehicles on road, pole beginning 538' from DER, on centerline, up to 648' MSL.
Trees, pole beginning 728' from DER, 362' left of centerline, up to 641' MSL.
Trees beginning 1662' from DER, 195' left of centerline, up to 649' MSL.
Trees beginning 1663' from DER, 178' left of centerline, up to 651' MSL.
Trees beginning 1705' from DER, 16' left of centerline, up to 661' MSL.
Tree 1766' from DER, 647' right of centerline, 650' MSL.
Trees beginning 1773' from DER, 19' right of centerline, up to 672' MSL.
Trees beginning 1986' from DER, 62' left of centerline, up to 663' MSL.
Trees beginning 2527' from DER, 53' left of centerline, up to 674' MSL.
Trees beginning 2751' from DER, 10' left of centerline, up to 676' MSL.
Trees beginning 2902' from DER, 339' left of centerline, up to 679' MSL.
Trees, electrical system beginning 2923' from DER, 26' left of centerline, up to 108' AGL/687' MSL.
Poles beginning 3210' from DER, 548' right of centerline, up to 676' MSL.
Tree 3294' from DER, 1192' right of centerline, 680' MSL.

Rwy 27, vegetation 13' from DER, 491' right of centerline, 7' AGL/593' MSL.
Vegetation beginning 44' from DER, 370' right of centerline, up to 7' AGL/594' MSL.
Poles, transmission line beginning 1044' from DER, 608' right of centerline, up to 39' AGL/622' MSL.
Trees beginning 1102' from DER, 659' right of centerline, up to 67' AGL/650' MSL.
Tree 1141' from DER, 750' left of centerline, 33' AGL/618' MSL.
Tree 1443' from DER, 721' left of centerline, 50' AGL/635' MSL.
Tree 1483' from DER, 737' left of centerline, 57' AGL/639' MSL.
Tree 1622' from DER, 913' left of centerline, 57' AGL/642' MSL.
Tree 1626' from DER, 693' left of centerline, 62' AGL/644' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

PORT CLINTON, OH (CON'T)

ERIE-OTTAWA INTL (PCW) (CON'T)

Rwy 27 (CON'T), trees beginning 1628' from DER, 164' left of centerline, up to 86' AGL/667' MSL.
Trees beginning 2092' from DER, 343' left of centerline, up to 94' AGL/677' MSL.
Tree 2449' from DER, 805' right of centerline, 69' AGL/653' MSL.
Tree 2499' from DER, 1073' right of centerline, 79' AGL/656' MSL.
Trees beginning 2556' from DER, 697' right of centerline, up to 90' AGL/671' MSL.
Tree 3161' from DER, 333' right of centerline, 91' AGL/680' MSL.
Trees beginning 3175' from DER, 325' right of centerline, up to 686' MSL.
Trees beginning 3210' from DER, 304' right of centerline, up to 108' AGL/688' MSL.
Tree 3384' from DER, 580' left of centerline, 102' AGL/681' MSL.
Trees beginning 3489' from DER, 428' left of centerline, up to 102' AGL/686' MSL.
Trees beginning 3581' from DER, 440' left of centerline, up to 103' AGL/689' MSL.
Trees beginning 3613' from DER, 880' right of centerline, up to 111' AGL/692' MSL.
Rwy 36, vegetation 15' from DER, 392' right of centerline, 588' MSL.
Sign 27' from DER, 198' left of centerline, 587' MSL.
Tree 71' from DER, 486' right of centerline, 4' AGL/590' MSL.
Tree, building beginning 272' from DER, 522' right of centerline, up to 609' MSL.
Pole, sign beginning 446' from DER, 317' left of centerline, up to 610' MSL.
Tree 523' from DER, 453' left of centerline, 622' MSL.
Tree 581' from DER, 552' left of centerline, 644' MSL.
Pole 597' from DER, 306' right of centerline, 614' MSL.
Tree 653' from DER, 490' right of centerline, 633' MSL.
Tree 684' from DER, 389' right of centerline, 647' MSL.
Trees beginning 704' from DER, 291' left of centerline, up to 662' MSL.
Trees beginning 768' from DER, 309' right of centerline, up to 648' MSL.
Trees beginning 822' from DER, 331' right of centerline, up to 664' MSL.
Tree 1078' from DER, 656' right of centerline, 667' MSL.
Trees beginning 1110' from DER, 141' right of centerline, up to 100' AGL/675' MSL.
Tree 1693' from DER, 286' left of centerline, 666' MSL.
Tree 1703' from DER, 285' left of centerline, 669' MSL.
Trees beginning 1710' from DER, 101' left of centerline, up to 670' MSL.
Trees beginning 2795' from DER, 67' left of centerline, up to 114' AGL/690' MSL.
Trees beginning 3172' from DER, 1037' right of centerline, up to 679' MSL.
Trees beginning 3264' from DER, 949' right of centerline, up to 687' MSL.
Trees beginning 3345' from DER, 863' right of centerline, up to 692' MSL.
Trees beginning 3602' from DER, 138' right of centerline, up to 693' MSL.
Trees beginning 3766' from DER, 191' right of centerline, up to 696' MSL.
Trees beginning 4025' from DER, 39' right of centerline, up to 90' AGL/698' MSL.
Tree 4082' from DER, 13' left of centerline, 691' MSL.
Trees beginning 4143' from DER, 4' left of centerline, up to 110' AGL/693' MSL.

29 OCT 2026 to 26 NOV 2026

PORTLAND, IN

PORTLAND MUNI (PLD)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 23FEB23 (23054) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, poles, fence beginning 29' from DER, 348' right of centerline, up to 29' AGL/956' MSL.
Tree 69' from DER, 492' left of centerline, 943' MSL.
Tree 102' from DER, 523' left of centerline, 41' AGL/964' MSL.
Trees, poles, building beginning 226' from DER, 13' left of centerline, up to 51' AGL/972' MSL.
Pole 349' from DER, 581' right of centerline, 42' AGL/969' MSL.
Trees, poles beginning 571' from DER, 80' right of centerline, up to 53' AGL/979' MSL.
Trees beginning 1635' from DER, 521' right of centerline, up to 985' MSL.
Tree 1818' from DER, 542' right of centerline, 71' AGL/994' MSL.
Trees beginning 1848' from DER, 520' right of centerline, up to 1003' MSL.
Trees beginning 2268' from DER, 519' right of centerline, up to 1015' MSL.
Tree 2475' from DER, 619' right of centerline, 1016' MSL.
Trees, transmission lines beginning 2517' from DER, 100' right of centerline, up to 1018' MSL.
Trees beginning 2780' from DER, 37' left of centerline, up to 1008' MSL.
Tree 2813' from DER, 48' right of centerline, 1020' MSL.
Trees beginning 2821' from DER, 471' right of centerline, up to 1023' MSL.
Trees beginning 2833' from DER, 233' right of centerline, up to 1025' MSL.
Trees beginning 2908' from DER, 113' right of centerline, up to 1032' MSL.
Trees beginning 2940' from DER, 63' left of centerline, up to 102' AGL/1024' MSL.
Trees beginning 2943' from DER, 71' right of centerline, up to 113' AGL/1035' MSL.
Trees beginning 2967' from DER, 16' left of centerline, up to 1030' MSL.
Trees beginning 3186' from DER, 20' right of centerline, up to 1037' MSL.

26190

PORTSMOUTH, OH

GREATER PORTSMOUTH RGNL (PMH)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 31MAY12 (12152) (FAA)

TAKEOFF MINIMUMS:

Rwy 18, 300-1¾ or std w/min climb of 257' per NM to 1100.

DEPARTURE PROCEDURE:

Rwy 18, climb heading 170° to 1300 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 18, trees beginning 4' from DER, 290' left of centerline, up to 100' AGL/721' MSL.
Trees beginning 678' from DER, 495' right of centerline, up to 100' AGL/931' MSL.
Rwy 36, trees beginning 1' from DER, 180' left of centerline, up to 100' AGL/780' MSL.
Trees beginning 687' from DER, 388' right of centerline, up to 100' AGL/710' MSL.

RAVENNA, OH

PORTAGE COUNTY (POV)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 18NOV10 (10322) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, power poles and road 19' from DER, 368' left of centerline, up to 35' AGL/1238' MSL.
Power pole 413' from DER, 549' right of centerline, 35' AGL/1218' MSL.
Rwy 27, tree 751' from DER, 148' right of centerline, 56' AGL/1226' MSL.
Pole 105' from DER, 523' right of centerline, 35'AGL/1200' MSL.
Power poles 357' from DER, 408' left of centerline, up to 35' AGL/1244' MSL.

RENSSELAER, IN

JASPER COUNTY (RZL)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1A 11AUG22 (22223) (FAA)

TAKEOFF MINIMUMS:

Rwys 18, 36, 300-1.
Rwys 9, 27, NA-Environmental.

DEPARTURE PROCEDURE:

Rwys 18, 36, climb to 1100 on runway heading before proceeding on course.

RICHMOND, IN

RICHMOND MUNI (RID)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 11AUG22 (22223) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 6, NAVAID 10' from DER, 150' left of centerline, 3' AGL/1140' MSL.
Terrain 27' from DER, 177' right of centerline, 1139' MSL.
Terrain beginning 54' from DER, 175' right of centerline, up to 1145' MSL.
Terrain 156' from DER, 472' right of centerline, 1147' MSL.
Tree 667' from DER, 677' left of centerline, 1160' MSL.
Tree 1704' from DER, 797' left of centerline, 1209' MSL.
Trees beginning 1774' from DER, 701' left of centerline, up to 1217' MSL.
Rwy 15, terrain 91' from der, 306' left of centerline, 1145' MSL.
Terrain beginning 93' from DER, 111' left of centerline, up to 1146' MSL.
Tree 2551' from DER, 111' left of centerline, 68' AGL/1208' MSL.
Trees beginning 2573' from DER, 0' left of centerline, up to 75' AGL/1216' MSL.
Trees beginning 2967' from DER, 150' right of centerline, up to 86' AGL/1226' MSL.
Rwy 24, terrain 35' from DER, 321' left of centerline, 1140' MSL.
Terrain beginning 106' from DER, 120' left of centerline, up to 1142' MSL.
Pole, building, traverse way beginning 274' from DER, 276' right of centerline, up to 21' AGL/1148' MSL.
Traverse way 465' from DER, 324' right of centerline, 1149' MSL.
Traverse way 665' from DER, 29' right of centerline, 1156' MSL.
Tree 1084' from DER, 685' left of centerline, 1175' MSL.
Trees beginning 1128' from DER, 525' left of centerline, up to 51' AGL/1177' MSL.
Trees beginning 1377' from DER, 758' left of centerline, up to 68' AGL/1190,' MSL.
Rwy 33, terrain 17' from DER, 483' right of centerline, 1128' MSL.
Traverse way 351' from DER, 578' right of centerline, 1141' MSL.
Tree 434' from DER, 490' right of centerline, 1186' MSL.
Trees beginning 484' from DER, 34' right of centerline, up to 1190' MSL.
Trees beginning 1046' from DER, 358' left of centerline, up to 87' AGL/1198' MSL.
Trees, tower, building beginning 1085' from DER, 17' left of centerline, up to 1200' MSL.
Trees beginning 1742' from DER, 771' right of centerline, up to 1196' MSL.

ROCHESTER, IN

FULTON COUNTY (RCR)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 14MAY26 (26134) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 11, terrain 0' from DER, 469' right of centerline, 797' MSL.
Trees beginning 618' from DER, 597' right of centerline, up to 104' AGL/886' MSL.
Trees beginning 1730' from DER, 179' right of centerline, up to 111' AGL/894' MSL.
Tree 3519' from DER, 28' left of centerline, 98' AGL/886' MSL.
Rwy 29, poles beginning 1' from DER, 459' left of centerline, up to 31' AGL/817' MSL.
Building, pole beginning 228' from DER, 94' right of centerline, up to 38' AGL/829' MSL.
Pole 524' from DER, 502' left of centerline, 36' AGL/823' MSL.
Tree 613' from DER, 436' left of centerline, 53' AGL/837' MSL.
Tree, building beginning 776' from DER, 261' left of centerline, up to 56' AGL/839' MSL.
Tree 1157' from DER, 779' left of centerline, 82' AGL/863' MSL.
Tree 1241' from DER, 488' right of centerline, 49' AGL/842' MSL.
Tree 1516' from DER, 638' left of centerline, 83' AGL/864' MSL.
Tree 2008' from DER, 166' right of centerline, 74' AGL/859' MSL.
Trees beginning 2476' from DER, 153' right of centerline, up to 112' AGL/892' MSL.

ST CLAIRSVILLE, OH

ALDERMAN (2P7)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 16DEC10 (10350) (FAA)

TAKEOFF MINIMUMS:

Rwy 1, 300-1¼ or std w/min climb of 395' per NM to 1800.
Rwy 19, 500-3 or std w/min climb of 244' per NM to 1800.

DEPARTURE PROCEDURE:

Rwy 1, climb heading 013° to 1800 before turning right.
Rwy 19, climb heading 193° to 1800 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 1, trees 49' from DER, 170' left of centerline, up to 90' AGL/1269' MSL.
Trees 179' from DER, 53' left of centerline, up to 90' AGL/1249' MSL.
Trees 210' from DER, 37' right of centerline, up to 90' AGL/1249' MSL.
Rwy 19, trees 141' from DER, 138' left of centerline, up to 90' AGL/1229' MSL.
Trees 154' from DER, 168' right of centerline up to 90' AGL/1249' MSL.
Trees 385' from DER, 34' right of centerline, up to 90' AGL/1229' MSL.
Trees 1764' from DER, 958' right of centerline, up to 90' AGL/1309' MSL.

SALEM, OH

SALEM AIRPARK (38D)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 24MAY18 (24025) (FAA)

TAKEOFF MINIMUMS:

Rwys 10R, 28L, NA-Environmental.
Rwy 10L, std w/min climb of 217' per NM to 1800, or 1400-3 for VCOA.

DEPARTURE PROCEDURE:

Rwy 28R, climb on heading 277° to 2200 before turning left.

VCOA:

Rwy 10L, obtain ATC approval for VCOA when requesting IFR clearance. Climb in visual conditions to cross Salem Airpark at or above 2400 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 10L, tower, 3186' from DER, 654' left of centerline, 72' AGL/1305' MSL.

SEBRING, OH

TRI-CITY (3G6)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 17JUN21 (22307) (FAA)

DEPARTURE PROCEDURE:

Rwy 18, climb on heading 181° to 3000 before turning east.
Rwy 36, climb on heading 001° to 3000 before turning east.

TAKEOFF OBSTACLE NOTES:

Rwy 18, trees 146' from DER, 451' right of centerline, 100' AGL/1242' MSL.
Trees beginning 179' from DER, 39' right of centerline, up to 100' AGL/1262' MSL.
Trees, pole beginning 212' from DER, 4' left of centerline, up to 100' AGL/1262' MSL.
Rwy 36, trees beginning 23' from DER, 31' right of centerline, up to 100' AGL/1272' MSL.
Trees beginning 90' from DER, 12' left of centerline, up to 100' AGL/1262' MSL.

26190

SEYMOUR, IN

FREEMAN MUNI (SER)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 08SEP22 (22251) (FAA)

DEPARTURE PROCEDURE:

Rwy 5, climb on heading 046° to 1100 before turning left.

Rwy 14, climb on heading 136° to 1100 before turning right.

TAKEOFF OBSTACLE NOTES:

Rwy 5, tree 1624' from DER, 755' left of centerline, 52' AGL/631' MSL.
Tree 1706' from DER, 793' left of centerline, 637' MSL.
Trees beginning 1713' from DER, 524' left of centerline, up to 98' AGL/677' MSL.
Tree 2018' from DER, 757' right of centerline, 51' AGL/631' MSL.
Tree 2088' from DER, 708' right of centerline, 69' AGL/650' MSL.
Tree 2114' from DER, 689' right of centerline, 71' AGL/652' MSL.
Trees beginning 3614' from DER, 1055' left of centerline, up to 685' MSL.
Rwy 14, lighting beginning 10' from DER, 30' left of centerline, up to 2' AGL/572' MSL.
Lighting 40' from DER, 123' right of centerline, 2' AGL/572' MSL.
Lighting 50' from DER, 94' right of centerline, 3' AGL/573' MSL.
Tree 2220' from DER, 271' right of centerline, 642' MSL.
Trees beginning 2287' from DER, 442' right of centerline, up to 656' MSL.
Trees beginning 2347' from DER, 326' right of centerline, up to 662' MSL.
Trees beginning 2376' from DER, 353' right of centerline, up to 666' MSL.
Trees beginning 2426' from DER, 292' right of centerline, up to 670' MSL.
Trees beginning 2517' from DER, 390' right of centerline, up to 672' MSL.
Trees beginning 2611' from DER, 403' right of centerline, up to 673' MSL.
Rwy 23, tree 1906' from DER, 882' left of centerline, 623' MSL.
Tree 2001' from DER, 855' left of centerline, 635' MSL.
Tree 2117' from DER, 729' left of centerline, 643' MSL.
Trees beginning 2241' from DER, 461' left of centerline, up to 644' MSL.
Trees beginning 2400' from DER, 458' left of centerline, up to 652' MSL.
Trees beginning 2437' from DER, 172' left of centerline, up to 658' MSL.
Rwy 32, lighting beginning 10' from DER, 30' left of centerline, up to 2' AGL/585' MSL.
Lighting beginning 10' from DER, 30' right of centerline, up to 2' AGL/585' MSL.
Tree 2340' from DER, 401' left of centerline, 57' AGL/647' MSL.
Trees beginning 2392' from DER, 357' left of centerline, up to 71' AGL/662' MSL.
Trees beginning 2647' from DER, 882' left of centerline, up to 668' MSL.

29 OCT 2026 to 26 NOV 2026

SHELBY, OH

SHELBY COMMUNITY (12G)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2A 15AUG19 (19227) (FAA)

TAKEOFF MINIMUMS:

Rwys 3, 21, NA-Environmental.

TAKEOFF OBSTACLE NOTES:

Rwy 18, trees beginning 9' from DER, 171' left of centerline, up to 100' AGL/1219' MSL.
Vehicles beginning 24' from DER, 303' left of centerline, up to 15' AGL/1134' MSL.
Trees beginning 338' from DER, 447' right of centerline, up to 100' AGL/1229' MSL.
Transmission line beginning 2127' from DER, 170' left and right of centerline, up to 91' AGL/1200' MSL.
Rwy 36, vehicles beginning 30' from DER, left and right of centerline, up to 17' AGL/1136' MSL.
Buildings beginning 63' from DER, left and right of centerline, up to 53' AGL/1172' MSL.
Trees beginning 561' from DER, 85' left of centerline, up to 100' AGL/1209' MSL.
Grain silos beginning 1799' from DER, 225' right of centerline, up to 100' AGL/1229' MSL.

SHELBYVILLE, IN

SHELBYVILLE MUNI (GEZ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 5 20OCT11 (11293) (FAA)

TAKEOFF MINIMUMS:

Rwys 9, 27, NA-Environmental.

TAKEOFF OBSTACLE NOTES:

Rwy 1, trees 1111' from DER, 753' right of centerline, 69' AGL/869' MSL.
Rwy 19, trees 2180' from DER, 261' right of centerline, 100' AGL/899' MSL.
Trees 2696' from DER, 498'left of centerline, 100' AGL/899' MSL.

26190

SIDNEY, OH

SIDNEY MUNI (SCA)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 06FEB14 (14037) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 5, trees beginning 1695' from DER, 686' right of centerline, up to 100' AGL/1149' MSL.
Power poles beginning 2125' from DER, crossing centerline, up to 100' AGL/1149' MSL.
Trees beginning 3071' from DER, 402' right of centerline, up to 100' AGL/1149' MSL.
Tree 3247' from DER, 894' left of centerline, 100' AGL/1149' MSL.
Trees beginning 3723' from DER, 208' left of centerline, up to 100' AGL/1149' MSL.
Rwy 10, terrain beginning 26' from DER, 72' right of centerline, up to 1048' MSL.
Terrain beginning 36' from DER, 109' left of centerline, up to 1048' MSL.
Tree 834' from DER, 238' left of centerline, 49' AGL/1100' MSL.
Trees beginning 1060' from DER, 492' right of centerline, up to 100' AGL/1154' MSL.
Trees beginning 3577' from DER, 48' right of centerline, up to 90' AGL/1141' MSL.
Rwy 23, vehicles and aircraft on ramp beginning at DER, 138' left of centerline, up to 15' AGL/1054' MSL.
Trees beginning at DER, 308' left of centerline, up to 100' AGL/1149' MSL.
Vehicles on road beginning 110' from DER, crossing centerline, up to 15' AGL/1054' MSL.
Trees beginning 902' from DER, crossing centerline, up to 100' AGL/1149' MSL.
Rwy 28, sign 5' from DER, 56' left of centerline, 2' AGL/1041' MSL.
Trees beginning 1261' from DER, 405' right of centerline, up to 71' AGL/1102' MSL.
Trees beginning 1658' from DER, crossing centerline, up to 93' AGL/1114' MSL.

SOUTH BEND, IN

SOUTH BEND INTL (SBN)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 9A 14JUL22 (22195) (FAA)

TAKEOFF MINIMUMS:

Rwy 27R, 300-1¼ or std w/min climb of 240' per NM to 1100. Or alternatively, with std takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1800' prior to DER.

DEPARTURE PROCEDURE:

Rwy 9R, climb on heading 094° to 2000 before turning south.
Rwy 18, climb on heading 184° to 2000 before turning east.

TAKEOFF OBSTACLE NOTES:

Rwy 9L, fence 23' from DER, 389' left of centerline, 10' AGL/792' MSL.
Trees beginning 29' from DER, 465' left of centerline, up to 36' AGL/820' MSL.
Trees, transmission lines, electrical system beginning 105' from DER, 8' left of centerline, up to 846' MSL.
Trees beginning 1218' from DER, 45' right of centerline, up to 817' MSL.
Tree 1244' from DER, 684' right of centerline, 829' MSL.
Trees beginning 1258' from DER, 66' right of centerline, up to 832' MSL.
Trees beginning 1313' from DER, 92' right of centerline, up to 842' MSL.
Trees beginning 1333' from DER, 65' right of centerline, up to 846' MSL.
Transmission line 3600' from DER, 385' left of centerline, 110' AGL/876' MSL.
Rwy 9R, trees beginning 1727' from DER, 587' left of centerline, up to 816' MSL.
Tree 1756' from DER, 818' left of centerline, 822' MSL.
Rwy 18, terrain 11' from DER, 253' right of centerline, 761' MSL.
Fence, terrain beginning 25' from DER, 348' right of centerline, up to 11' AGL/773' MSL.
Tree, vehicles on road beginning 148' from DER, 415' left of centerline, up to 784' MSL.
Trees, poles beginning 755' from DER, 561' left of centerline, up to 66' AGL/825' MSL.
Pole 842' from DER, 518' right of centerline, 27' AGL/783' MSL.
Trees beginning 1009' from DER, 15' right of centerline, up to 840' MSL.
Trees beginning 1564' from DER, 12' left of centerline, up to 91' AGL/849' MSL.
Trees beginning 2434' from DER, 128' right of centerline, up to 848' MSL.
Trees beginning 2530' from DER, 34' right of centerline, up to 849' MSL.
Trees beginning 2553' from DER, 125' right of centerline, up to 852' MSL.
Trees beginning 2815' from DER, 261' left of centerline, up to 851' MSL.
Rwy 27L, pole 667' from DER, 480' left of centerline, 23' AGL/810' MSL.
Tree 1178' from DER, 615' left of centerline, 861' MSL.
Trees, poles beginning 1184' from DER, 56' left of centerline, up to 875' MSL.
Tree 1215' from DER, 665' right of centerline, 28' AGL/827' MSL.
Trees, vehicles on roads, poles beginning 1485' from DER, 23' left of centerline, up to 888' MSL.
Pole 1647' from DER, 49' right of centerline, 27' AGL/832' MSL.
Tree 1750' from DER, 653' right of centerline, 33' AGL/835' MSL.
Trees beginning 1965' from DER, 18' left of centerline, up to 895' MSL.
Trees beginning 2336' from DER, 125' left of centerline, up to 898' MSL.
Tree 3478' from DER, 213' right of centerline, 877' MSL.
Trees beginning 3512' from DER, 70' right of centerline, up to 888' MSL.
Trees beginning 3611' from DER, 261' left of centerline, up to 900' MSL.

CON'T

SOUTH BEND, IN (CON'T)

SOUTH BEND INTL (SBN) (CON'T)

Rwy 27L (CON'T), trees beginning 3768' from DER, 83' right of centerline, up to 905' MSL.
Trees beginning 4238' from DER, 102' right of centerline, up to 914' MSL.
Tree 4748' from DER, 538' left of centerline, 97' AGL/913' MSL.
Tree 4766' from DER, 240' right of centerline, 919' MSL.
Trees beginning 4809' from DER, 265' right of centerline, up to 926' MSL.
Trees beginning 4942' from DER, 479' right of centerline, up to 927' MSL.
Tree 5442' from DER, 658' right of centerline, 935' MSL.
Rwy 27R, tree 66' from DER, 497' right of centerline, 843' MSL.
Tree 137' from DER, 507' right of centerline, 846' MSL.
Trees beginning 206' from DER, 501' right of centerline, up to 79' AGL/849' MSL.
Tree 589' from DER, 579' left of centerline, 803' MSL.
Trees beginning 676' from DER, 10' right of centerline, up to 857' MSL.
Trees beginning 808' from DER, 27' left of centerline, up to 843' MSL.
Trees beginning 1161' from DER, 10' left of centerline, up to 844' MSL.
Trees beginning 1247' from DER, 18' left of centerline, up to 853' MSL.
Trees beginning 1374' from DER, 32' left of centerline, up to 857' MSL.
Trees beginning 1518' from DER, 51' left of centerline, up to 859' MSL.
Trees beginning 1723' from DER, 0' right of centerline, up to 863' MSL.
Trees beginning 1789' from DER, 33' left of centerline, up to 866' MSL.
Trees beginning 2321' from DER, 39' right of centerline, up to 885' MSL.
Trees beginning 2468' from DER, 288' left of centerline, up to 880' MSL.
Trees beginning 3256' from DER, 1138' left of centerline, up to 892' MSL.
Tree 3652' from DER, 1213' right of centerline, 886' MSL.
Tree 4922' from DER, 1742' right of centerline, 913' MSL.
Transmission line 5541' from DER, 1924' right of centerline, 99' AGL/954' MSL.
Tree 5611' from DER, 2003' right of centerline, 941' MSL.
Rwy 36, terrain beginning 58' from DER, 349' left of centerline, up to 801' MSL.
Terrain 97' from DER, 390' left of centerline, 803' MSL.
General utility 123' from DER, 415' left of centerline, 6' AGL/808' MSL.
Tree 1693' from DER, 13' left of centerline, 842' MSL.
Tree 1817' from DER, 15' left of centerline, 844' MSL.
Trees beginning 1835' from DER, 837' right of centerline, up to 850' MSL.
Tree 1953' from DER, 873' right of centerline, 857' MSL.
Tree 1953' from DER, 9' left of centerline, 848' MSL.
Tree 2065' from DER, 6' left of centerline, 852' MSL.
Trees beginning 2068' from DER, 848' right of centerline, up to 865' MSL.
Trees beginning 2338' from DER, 442' left of centerline, up to 868' MSL.

SPRINGFIELD, OH

SPRINGFIELD/BECKLEY MUNI (SGH)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 05JUN08 (21336) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 6, trees beginning 642' from DER, 664' left of centerline, up to 96' AGL/1133' MSL.
Tree 66' from DER, 514' right of centerline, 27' AGL/1064' MSL.
Rwy 15, multiple trees beginning 1357' from DER, 160' left of centerline, up to 86' AGL/1127' MSL.
Tree 1763' from DER, 410' right of centerline, 51' AGL/1092' MSL.
Rwy 24, trees beginning 1387' from DER, 66' left of centerline, up to 58' AGL/1109' MSL.
Windsock 1' from DER, 228' right of centerline, 20' AGL/1071' MSL.
Rwy 33, tree 183' from DER, 438' right of centerline, 24' AGL/1066' MSL.

29 OCT 2026 to 26 NOV 2026
29 OCT 2026 to 26 NOV 2026

STEUBENVILLE, OH

GEARY A BATES/JEFFERSON COUNTY AIRPARK (2G2)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 10NOV16 (22083) (FAA)

TAKEOFF MINIMUMS:

Rwy 32, 300-1¾ or std w/min climb of 280' per NM to 1600.

DEPARTURE PROCEDURE:

Rwy 14, climb on heading 142° to 2100 before turning left.

TAKEOFF OBSTACLE NOTES:

Rwy 14, tree 32' from DER, 500' right of centerline, 73' AGL/1240' MSL.
Tree 58' from DER, 448' right of centerline, 71' AGL/1245' MSL.
Trees beginning 113' from DER, 329' left of centerline, up to 43' AGL/1207' MSL.
Trees, beginning 162' from DER, 210' right of centerline, up to 74' AGL/1251' MSL.
Trees, beginning 196' from DER, 186' left of centerline, up to 60' AGL/1208' MSL.
Trees, beginning 221' from DER, 184' left of centerline, up to 54' AGL/1209' MSL.
Trees, beginning 240' from DER, 24' right of centerline, up to 96' AGL/1258' MSL.
Tree 376' from DER, 513' left of centerline, 96' AGL/1235' MSL.
Rwy 32, tree, bush, beginning 0' from DER, 334' left of centerline, up to 59' AGL/1244' MSL.
Tree, ground, bush, beginning 113' from DER, 392' left of centerline, up to 67' AGL/1246' MSL.
Ant 1.3 NM from DER, 760' left of centerline, 193' AGL/1405' MSL.
Tower 1.3 NM from DER, 764' left of centerline, 199' AGL/1411' MSL.

SULLIVAN, IN

SULLIVAN COUNTY (SIV)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 30DEC99 (99364) (FAA)

TAKEOFF MINIMUMS:

Rwys 18, 36, 200-1 or std w/min climb of 320' per NM to 1800.

DEPARTURE PROCEDURE:

Rwy 18, climb runway heading to 1500 before turning west on course.
Rwys 18, 36, climb runway heading to 1800 before turning east on course.

TELL CITY, IN

PERRY COUNTY MUNI (TEL)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 25AUG11 (21112) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 13, fence, terrain, buildings, and trees beginning 6' from DER, 131' left of centerline, up to 49' AGL/ 740' MSL.
Terrain, trees, and poles beginning 93' from DER, 19' right of centerline, up to 30' AGL/750' MSL.
Rwy 31, trees, terrain, and pole beginning 125' from DER, 141' left of centerline, up to 25' AGL/702' MSL.
Trees, terrain, and tower beginning 68' from DER, 64' right of centerline, up to 56' AGL/ 648' MSL.

TERRE HAUTE, IN

SKY KING (3I3)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 5A 11AUG22 (22223) (FAA)

TAKEOFF MINIMUMS:

Rwys 18, 36, NA-Environmental.

DEPARTURE PROCEDURE:

Rwy 27, climb heading 268° to 1300 before turning left.

TAKEOFF OBSTACLE NOTES:

Rwy 9, multiple power lines beginning 34' from DER, left and right of centerline, up to 30' AGL/529' MSL.
Vehicle on road beginning 54' from DER, left and right of centerline, up to 15' AGL/519' MSL.
Fence beginning 33' from DER, left and right of centerline, up to 6' AGL/505' MSL.
Multiple buildings beginning 167' from DER, left and right of centerline, up to 60' AGL/589' MSL.
Rwy 27, trees beginning abeam DER, 235' right of centerline, up to 60' AGL/559' MSL.
Trees beginning abeam DER, 382' left of centerline, up to 60' AGL/539' MSL.
Trees beginning 1057' from DER, 47' left of centerline, up to 60' AGL/539' MSL.

TERRE HAUTE, IN (CON'T)

TERRE HAUTE RGNL (HUF)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-B 07AUG25 (25219) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 5, NAVAID 10' from DER, 149' left of centerline, 4' AGL/584' MSL.
Light poles, terrain beginning 10' from DER, 150' right of centerline, up to 4' AGL/585' MSL.
Poles beginning 969' from DER, 673' right of centerline, up to 37' AGL/621' MSL.
Trees beginning 2260' from DER, 842' left of centerline, up to 652' MSL.
Trees beginning 2389' from DER, 689' left of centerline, up to 659' MSL.
Tree 2955' from DER, 1231' left of centerline, 662' MSL.
Tree 3249' from DER, 648' left of centerline, 665' MSL.
Trees beginning 3275' from DER, 259' left of centerline, up to 677' MSL.
Trees beginning 3506' from DER, 108' left of centerline, up to 682' MSL.
Rwy 14, light poles 40' from DER, 115' left of centerline, 3' AGL/591' MSL.
Trees beginning 2581' from DER, 1030' left of centerline, up to 665' MSL.
Tree 2960' from DER, 1262' left of centerline, 666' MSL.
Trees beginning 3015' from DER, 1159' left of centerline, up to 687' MSL.
Transmission line 3100' from DER, 1205' right of centerline, 89' AGL/672' MSL.
Transmission line 3351' from DER, 387' right of centerline, 100' AGL/680' MSL.
Rwy 23, tree 1875' from DER, 527' right of centerline, 625' MSL.
Rwy 32, light poles 40' from DER, 115' left of centerline, 3' AGL/570' MSL.
NAVAID, light poles beginning 40' from DER, 79' right of centerline, up to 3' AGL/571' MSL.
Tree 397' from DER, 520' left of centerline, 56' AGL/616' MSL.
Trees, poles, transmission line beginning 983' from DER, 313' left of centerline, up to 63' AGL/623' MSL.
Tree 2154' from DER, 811' left of centerline, 628' MSL.
Trees beginning 2384' from DER, 461' left of centerline, up to 658' MSL.
Tree 2875' from DER, 774' right of centerline, 644' MSL.
Trees beginning 2926' from DER, 146' right of centerline, up to 667' MSL.
Trees beginning 2955' from DER, 32' left of centerline, up to 664' MSL.
Light poles, trees beginning 3380' from DER, 52' left of centerline, up to 128' AGL/692' MSL.
Trees beginning 3493' from DER, 1137' right of centerline, up to 670' MSL.
Trees beginning 3542' from DER, 1174' right of centerline, up to 674' MSL.
Trees beginning 3666' from DER, 714' right of centerline, up to 675' MSL.
Trees beginning 3826' from DER, 1385' right of centerline, up to 678' MSL.
Trees beginning 4490' from DER, 1198' right of centerline, up to 685' MSL.
Trees beginning 4635' from DER, 341' right of centerline, up to 698' MSL.
Tree 5340' from DER, 995' right of centerline, 702' MSL.
Trees beginning 5341' from DER, 851' right of centerline, up to 145' AGL/707' MSL.

29 OCT 2026 to 26 NOV 2026

TIFFIN, OH

SENECA COUNTY(16G)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 02JUL09 (09183) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 6, multiple trees and buildings beginning 2' from DER, 186' right of centerline, up to 98' AGL/868' MSL.
Antenna 129' from DER, 438' left of centerline, 66' AGL/836' MSL.
Pole 408' from DER, 477' left of centerline, 39' AGL/809' MSL.
Vehicle on road 501' from DER, 414' left of centerline, 26' AGL/796' MSL.
Trees 2421' from DER, 207' left of centerline, 83' AGL/853' MSL.
Rwy 24, multiple trees beginning 27' from DER, 280' left of centerline, up to 124' AGL/904' MSL.
Building 1291' from DER, 528' left of centerline, 44' AGL/824' MSL.
Multiple trees beginning 1071' from DER, 337' right of centerline, up to 92' AGL/872' MSL.
Pole 1460' from DER, 562' right of centerline, 48' AGL/828' MSL.

TOLEDO, OH

EUGENE F KRANZ TOLEDO EXPRESS (TOL)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3A 05NOV20 (20310) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 7, vehicles on road beginning 246' from DER, 525' right of centerline, up to 10' AGL/671' MSL.
Tree 1339' from DER, 667' left of centerline, 700' MSL.
Trees beginning 1903' from DER, 799' right of centerline, up to 741' MSL.
Tree 2392' from DER, 852' left of centerline, 734' MSL.
Tree 2604' from DER, 1047' left of centerline, 756' MSL.
CON'T

TOLEDO, OH (CON'T)

EUGENE F KRANZ TOLEDO EXPRESS (TOL) (CON'T)

Rwy 16, terrain 59' from DER, 496' left of centerline, 671' MSL.
Tree 618' from DER, 659' right of centerline, 739' MSL.
Trees beginning 719' from DER, 42' right of centerline, up to 752' MSL.
Tree 985' from DER, 478' left of centerline, 694' MSL.
Tree 1021' from DER, 518' left of centerline, 714' MSL.
Tree 1043' from DER, 571' left of centerline, 730' MSL.
Tree 1139' from DER, 711' left of centerline, 732' MSL.
Tree 1279' from DER, 806' left of centerline, 745' MSL.
Tree 1318' from DER, 689' left of centerline, 753' MSL.
Trees beginning 1388' from DER, 648' left of centerline, up to 757' MSL.
Trees beginning 1491' from DER, 80' left of centerline, up to 758' MSL.
Trees beginning 2607' from DER, 155' right of centerline, up to 765' MSL.
Trees beginning 2704' from DER, 36' right of centerline, up to 767' MSL.
Trees beginning 3029' from DER, 45' right of centerline, up to 786' MSL.
Rwy 25, vegetation 245' from DER, 473' right of centerline, 692' MSL.
Vegetation 485' from DER, 527' right of centerline, 695' MSL.
Tree 2214' from DER, 870' right of centerline, 746' MSL.
Tree 2362' from DER, 907' left of centerline, 780' MSL.
Rwy 34, vehicles on road beginning 247' from DER, 488' left of centerline, up to 10' AGL/689' MSL.
Pole, vehicles on road beginning 445' from DER, 533' left of centerline, up to 38' AGL/713' MSL.
Vehicles on road beginning 574' from DER, 622' right of centerline, up to 10' AGL/689' MSL.
Pole 632' from DER, 539' left of centerline, 38' AGL/714' MSL.
Poles, tree beginning 704' from DER, 522' left of centerline, up to 38' AGL/715' MSL.
Trees, pole beginning 1036' from DER, 411' left of centerline, up to 718' MSL.
Trees beginning 1272' from DER, 156' left of centerline, up to 752' MSL.
Pole 1287' from DER, 699' right of centerline, 36' AGL/711' MSL.
Trees beginning 1826' from DER, 102' right of centerline, up to 760' MSL.
Trees beginning 2489' from DER, 90' left of centerline, up to 761' MSL.
Trees, tower, grain elevator beginning 2726' from DER, 92' left of centerline, up to 780' MSL.
Tree 2912' from DER, 119' right of centerline, 766' MSL.
Trees beginning 2953' from DER, 451' right of centerline, up to 780' MSL.

TOLEDO EXEC (TDZ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 21MAY20 (21280) (FAA)

TAKEOFF MINIMUMS:

Rwy 4, std w/min climb of 230' per NM to 2500, or 1300-2½ for VCOA.

DEPARTURE PROCEDURE:

Rwy 4, climb on heading 046° to 2100 before turning left.
Rwy 32, climb on heading 321° to 1400 before turning right.

VCOA:

Rwy 4, obtain ATC approval for VCOA when requesting IFR clearance. Climb in visual conditions to cross Toledo Exec airport at or above 1800 before proceeding on course.

TAKEOFF OBSTACLE NOTES:

Rwy 4, electrical system 10' from DER, 26' left of centerline, 3' AGL/621' MSL.
Sign 22' from DER, 168' right of centerline, 3' AGL/622' MSL.
Vehicle on road, pole beginning 284' from DER, 186' right of centerline, up to 646' MSL.
Tree, pole, vehicle on road beginning 372' from DER, 95' right of centerline, up to 655' MSL.
Trees, vehicle on road beginning 403' from DER, 1' right of centerline, up to 660' MSL.
Vehicle on road 489' from DER, 164' left of centerline, 647' MSL.
Trees, vehicle on road beginning 558' from DER, 1' left of centerline, up to 651' MSL.
Trees beginning 639' from DER, 437' right of centerline, up to 679' MSL.
Trees beginning 785' from DER, 412' right of centerline, up to 681' MSL.
Trees, pole beginning 1096' from DER, 162' right of centerline, up to 694' MSL.
Trees beginning 1996' from DER, 50' left of centerline, up to 680' MSL.
Towers beginning 3309' from DER, 1030' left of centerline, up to 761' MSL.
Rwy 14, sign 23' from DER, 248' left of centerline, 3' AGL/622' MSL.
Sign 39' from DER, 467' left of centerline, 4' AGL/623' MSL.
Vehicle on road beginning 137' from DER, 283' right of centerline, up to 638' MSL.
Vehicle on road, signs, pole beginning 169' from DER, 168' left of centerline, up to 15' AGL/638' MSL.
Vehicle on road, poles beginning 478' from DER, 84' left of centerline, up to 639' MSL.
Vehicle on road beginning 487' from DER, 155' right of centerline, up to 639' MSL.
Poles beginning 573' from DER, 143' left of centerline, up to 20' AGL/640' MSL.
Poles beginning 629' from DER, 384' left of centerline, up to 20' AGL/641' MSL.
Pole 685' from DER, 585' left of centerline, 32' AGL/652' MSL.
Poles, buildings beginning 694' from DER, 428' left of centerline, up to 35' AGL/654' MSL.
Sign 739' from DER, 6' right of centerline, 22' AGL/644' MSL.

CON'T

TOLEDO, OH (CON'T)

TOLEDO EXEC (TDZ) (CON'T)

Rwy 14 (CON'T), building 996' from DER, 672' left of centerline, 657' MSL.
Poles, building beginning 1043' from DER, 305' left of centerline, up to 45' AGL/664' MSL.
Pole beginning 1285' from DER, 565' left of centerline, up to 47' AGL/667' MSL.
Pole 1419' from DER, 252' right of centerline, 38' AGL/658' MSL.
Pole 1487' from DER, 328' right of centerline, 40' AGL/661' MSL.
Trees beginning 1712' from DER, 72' left of centerline, up to 689' MSL.
Rwy 22, electrical system 10' from DER, 26' left of centerline, 2' AGL/623' MSL.
Electrical system 45' from DER, 299' left of centerline, 4' AGL/624' MSL.
Fence 112' from DER, 311' left of centerline, 7' AGL/627' MSL.
Fence 207' from DER, 298' left of centerline, 9' AGL/629' MSL.
Pole 251' from DER, 467' left of centerline, 35' AGL/655' MSL.
Poles, vehicle on road, tree beginning 251' from DER, 108' left of centerline, up to 40' AGL/660' MSL.
Vehicle on road 568' from DER, 2' right of centerline, 637' MSL.
Poles, transmission line, vehicle on road, tree beginning 582' from DER, 246' right of centerline, up to 48' AGL/671' MSL.
Trees, vehicle on road, sign, poles, transmission lines, fence, bridge beginning 595' from DER, 23' left of centerline, up to 684' MSL.
Tower, transmission line beginning 797' from DER, 307' right of centerline, up to 101' AGL/726' MSL.
Tower, vehicle on road, poles, trees, transmission line beginning 807' from DER, 32' right of centerline, up to 98' AGL/727' MSL.
Tree 2062' from DER, 524' left of centerline, 685' MSL.
Trees beginning 2130' from DER, 589' left of centerline, up to 692' MSL.
Tree 2534' from DER, 1053' left of centerline, 75' AGL/697' MSL.
Rwy 32, fence beginning 43' from DER, 424' left of centerline, up to 7' AGL/626' MSL.
Tree 177' from DER, 521' left of centerline, 648' MSL.
Tree, poles, vehicle on road beginning 242' from DER, 346' left of centerline, up to 662' MSL.
Poles, vehicle on road, trees beginning 556' from DER, 18' left of centerline, up to 40' AGL/681' MSL.
Tree 683' from DER, 373' right of centerline, 640' MSL.
Pole 1042' from DER, 79' right of centerline, 659' MSL.
Transmission line 1092' from DER, 193' right of centerline, 46' AGL/665' MSL.
Pole 1206' from DER, 29' right of centerline, 43' AGL/666' MSL.
Transmission line, poles beginning 1271' from DER, 62' right of centerline, up to 55' AGL/674' MSL.
Transmission lines 1605' from DER, 559' right of centerline, 61' AGL/680' MSL.
Transmission line 1676' from DER, 559' right of centerline, 61' AGL/682' MSL.
Pole, transmission line beginning 1679' from DER, 559' right of centerline, up to 71' AGL/691' MSL.
Poles, transmission lines beginning 1781' from DER, 639' right of centerline, up to 74' AGL/692' MSL.
Trees beginning 1998' from DER, 144' left of centerline, up to 693' MSL.
Pole, tower beginning 2903' from DER, 1189' right of centerline, up to 716' MSL.
Transmission line 3372' from DER, 478' right of centerline, 139' AGL/755' MSL.

29 OCT 2026 to 26 NOV 2026

UPPER SANDUSKY, OH

WYANDOT COUNTY (56D)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 15MAY80 (80150) (FAA)

TAKEOFF MINIMUMS:

Rwy 36, 300-1.

URBANA, OH

GRIMES FLD (I74)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1A 03NOV22 (22307) (FAA)

TAKEOFF MINIMUMS:

Rwys 1, 19, NA-Environmental.

TAKEOFF OBSTACLE NOTES:

Rwy 2, numerous trees beginning 995' from DER, 6' left of centerline, up to 100' AGL/1152' MSL.
Numerous trees beginning from 2106' from DER, 327' right of centerline, up to 100' AGL/1140' MSL.
Numerous power poles 1204' from DER, 654' right of centerline, 55' AGL/1125' MSL.
Rwy 20, numerous trees beginning 5' from DER, 487' left of centerline, up to 100' AGL/1111' MSL.
Tank 5459' from DER, 1062' left of centerline, 170' AGL/1195' MSL.
Numerous trees beginning 672' from DER, 92' right of centerline, up to 100' AGL/1120' MSL.

VALPARAISO, IN

PORTER COUNTY RGNL (VPZ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 14FEB08 (08045) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, tree 51' from DER, 350' right of centerline, 100' AGL/874' MSL.
Tree 1219' from DER, 775' left of centerline, 57' AGL/807' MSL.
Rwy 18, tower and multiple trees beginning 140' from DER, 157' right of centerline, up to 100' AGL/865' MSL.
Trees 143' from DER, 71' left of centerline, 100' AGL/865' MSL.
Rwy 27, multiple trees, 1038' from DER, 308' left of centerline, up to 68' AGL/828' MSL.
Sign, 1847' from DER, 263' right of centerline, 49' AGL/817' MSL.
Rwy 36, trees 105' from DER, 99' right of centerline, 100' AGL/895' MSL
Trees 108' from DER, 129' left of centerline, 100' AGL/874' MSL.

VAN WERT, OH

VAN WERT COUNTY (VNW)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4 02OCT25 (25275) (FAA)

TAKEOFF MINIMUMS:

Rwys 18, 36, NA-Environmental.
Rwy 9, 300-1¼ or std w/min climb of 245'/NM to 1100 or alternatively, with std takeoff minimums and a normal 200'/NM climb gradient, takeoff must occur no later than 2100' prior to DER.

TAKEOFF OBSTACLE NOTES:

Rwy 9, light poles 0' from DER, 83' left of centerline, 3' AGL/786' MSL.
Vehicles on road beginning 18' from DER, 484' left of centerline, up to 798' MSL.
Trees beginning 419' from DER, 376' left of centerline, up to 853' MSL.
Trees beginning 438' from DER, 301' left of centerline, up to 860' MSL.
Tree 450' from DER, 384' right of centerline, 830' MSL.
Trees beginning 472' from DER, 253' right of centerline, up to 851' MSL.
Trees, building, poles, tower beginning 536' from DER, 3' left of centerline, up to 864' MSL.
Trees, building beginning 744' from DER, 222' right of centerline, up to 852' MSL.
Trees beginning 987' from DER, 164' right of centerline, up to 853' MSL.
Trees beginning 1100' from DER, 16' right of centerline, up to 861' MSL.
Trees, pole beginning 1382' from DER, 9' right of centerline, up to 870' MSL.
Trees beginning 1493' from DER, 24' right of centerline, up to 888' MSL.
Trees beginning 1774' from DER, 40' left of centerline, up to 871' MSL.
Water tower 3310' from DER, 493' right of centerline, 153' AGL/933' MSL.
Building 5062' from DER, 1419' left of centerline, 915' MSL.
Tower 5893' from DER, 2037' left of centerline, 965' MSL.
Tower 1 NM from DER, 1965' left of centerline, 170' AGL/954' MSL.
Rwy 27, terrain 6' from DER, 373' left of centerline, 784' MSL.
Pole 45' from DER, 473' right of centerline, 816' MSL.
Poles beginning 266' from DER, 436' right of centerline, up to 46' AGL/829' MSL.
Trees, poles beginning 519' from DER, 127' right of centerline, up to 859' MSL.
Tree 587' from DER, 638' left of centerline, 830' MSL.
Trees beginning 679' from DER, 310' left of centerline, up to 834' MSL.
Trees beginning 841' from DER, 344' left of centerline, up to 845' MSL.
Trees beginning 2190' from DER, 786' left of centerline, up to 872' MSL.
Trees beginning 2276' from DER, 36' left of centerline, up to 881' MSL.
Trees, transmission line beginning 2293' from DER, 23' right of centerline, up to 861' MSL.
Transmission lines beginning 2527' from DER, 490' right of centerline, up to 86' AGL/863' MSL.

VERSAILLES, OH

DARKE COUNTY (VES)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 08NOV18 (18312) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, pole 20' from DER, 83' left of centerline, 1006' MSL.
Pole 20' from DER, 81' right of centerline, 1005' MSL.
Tree, antenna, pole, buildings beginning 169' from DER, 357' left of centerline, up to 44' AGL/1045' MSL.
Tree, vehicles on road, buildings beginning 237' from DER, 131' left of centerline, up to 1053' MSL.
Tree, vehicles on road beginning 366' from DER, 15' left of centerline, up to 1072' MSL.
Vehicles on road beginning 410' from DER, left and right of centerline, up to 1017' MSL.
Trees beginning 835' from DER, 688' right of centerline, up to 1086' MSL.
Tree 1066' from DER, 696' right of centerline, 1095' MSL.
Trees beginning 1149' from DER, 472' right of centerline, up to 1101' MSL.
Trees beginning 1341' from DER, 295' right of centerline, up to 1108' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

VERSAILLES, OH (CON'T)

DARKE COUNTY (VES) (CON'T)

Rwy 9 (CON'T), trees beginning 1445' from DER, 235' right of centerline, up to 1112' MSL.
Rwy 27, pole 121' from DER, 356' left of centerline, 1028' MSL.
Pole, tree beginning 121' from DER, 447' right of centerline, up to 1037' MSL.
Trees beginning 982' from DER, 503' right of centerline, up to 1043' MSL.
Tree 1404' from DER, 162' left of centerline, 1052' MSL.
Tree 1461' from DER, 64' right of centerline, 1051' MSL.
Trees beginning 1722' from DER, 328' left of centerline, up to 1065' MSL.
Tree 1923' from DER, 353' left of centerline, 1067' MSL.
Trees beginning 2062' from DER, 741' left of centerline, up to 1076' MSL.

WABASH, IN

WABASH MUNI (IWH)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 10DEC15 (15344) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 9, trees beginning 194' from DER, left and right of centerline, up to 110' AGL/910' MSL.
Rwy 18, trees beginning 310' from DER, 128' left of centerline, up to 83' AGL/873' MSL.
Rwy 27, poles and power line beginning 484' from DER, left and right of centerline, up to 44' AGL/840' MSL.
Vehicles on road beginning 502' from DER, left and right of centerline, up to 15' AGL/813' MSL.
Tree 517' from DER, 618' left of centerline, 77' AGL/871' MSL.
Trees beginning 624' from DER, left and right of centerline, up to 64' AGL/855' MSL.
Poles and power line beginning 1613' from DER, left and right of centerline, up to 48' AGL/853' MSL.
Rwy 36, buildings beginning 31' from DER, 272' left of centerline, up to 25' AGL/815' MSL.
Trees beginning 459' from DER, left and right of centerline, up to 70' AGL/876' MSL.
Vehicles on road 469' from DER, left and right of centerline, up to 15' AGL/804' MSL.

WADSWORTH, OH

WADSWORTH MUNI (3G3)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 09JUL26 (26190) (FAA)

TAKEOFF MINIMUMS:

Rwy 2, 400-2¼ w/min climb of 280'/NM to 1900 or std w/min climb of 445'/NM to 1500, or 1100-3 for VCOA.
Rwy 10, 700-3 or std w/min climb of 760'/NM to 1500.
Rwy 20, 300-1⅝ or std w/min climb of 381'/NM to 1300.
Rwy 28, 400-2¾ or std w/min climb of 475'/NM to 1400.

DEPARTURE PROCEDURE:

Rwy 10, climb on heading 097° to 1700 before proceeding on course.
Rwy 28, climb on heading 277° to 1500 before turning right.

VCOA:

Rwy 2, obtain ATC approval for VCOA when requesting IFR clearance. Climb in visual conditions to cross Wadsworth Muni airport at or above 1900.

TAKEOFF OBSTACLE NOTES:

Rwy 2, fence 9' from DER, 268' right of centerline, 6' AGL/979' MSL.
Tree 12' from DER, 354' left of centerline, 35' AGL/1007' MSL.
Tree 25' from DER, 456' left of centerline, 1030' MSL.
Vehicles on road 49' from DER, 403' right of centerline, 1000' MSL.
Tree, pole beginning 64' from DER, 37' left of centerline, up to 1033' MSL.
Vehicles on roads beginning 90' from DER, 367' right of centerline, up to 1001' MSL.
Tree, vehicles on road beginning 218' from DER, 166' right of centerline, up to 67' AGL/1044' MSL.
Tree 490' from DER, 399' right of centerline, 1052' MSL.
Trees, vehicles on roads, smokestack, buildings, poles beginning 505' from DER, 13' right of centerline, up to 75' AGL/1055' MSL.
Transmission line towers, poles, trees beginning 1311' from DER, 8' left of centerline, up to 61' AGL/1036' MSL.
Trees beginning 1841' from DER, 44' right of centerline, up to 67' AGL/1070' MSL.
Tree 1946' from DER, 823' left of centerline, 70' AGL/1044' MSL.
Trees beginning 1961' from DER, 3' left of centerline, up to 74' AGL/1056' MSL.
Trees beginning 2254' from DER, on and right of centerline, up to 86' AGL/1087' MSL.
Trees beginning 2776' from DER, 1165' left of centerline, up to 1063' MSL.
Trees beginning 2782' from DER, 339' right of centerline, up to 88' AGL/1100' MSL.
Trees beginning 3226' from DER, 340' right of centerline, up to 94' AGL/1107' MSL.
Trees beginning 3764' from DER, 566' right of centerline, up to 75' AGL/1121' MSL.
Tree 3840' from DER, 55' left of centerline, 88' AGL/1075' MSL.
Trees beginning 3942' from DER, 535' right of centerline, up to 86' AGL/1124' MSL.
Trees beginning 4107' from DER, 467' right of centerline, up to 82' AGL/1133' MSL.
Tree 4348' from DER, 234' left of centerline, 90' AGL/1083' MSL.

CON'T

WADSWORTH, OH (CON'T)

WADSWORTH MUNI (3G3) (CON'T)

Rwy 2 (CON'T), tree 4403' from DER, 187' left of centerline, 93' AGL/1087' MSL.
Trees beginning 4501' from DER, 232' right of centerline, up to 1138' MSL.
Trees beginning 4599' from DER, 56' right of centerline, up to 89' AGL/1143' MSL.
Trees beginning 4835' from DER, 33' left of centerline, up to 87' AGL/1100' MSL.
Trees beginning 4970' from DER, 318' right of centerline, up to 100' AGL/1151' MSL.
Trees beginning 5138' from DER, 10' right of centerline, up to 100' AGL/1173' MSL.
Tree 5274' from DER, 8' left of centerline, 85' AGL/1111' MSL.
Trees beginning 5594' from DER, 33' right of centerline, up to 104' AGL/1184' MSL.
Tree 5617' from DER, 17' left of centerline, 85' AGL/1116' MSL.
Trees beginning 5625' from DER, 4' left of centerline, up to 94' AGL/1120' MSL.
Trees beginning 5680' from DER, 187' left of centerline, up to 1122' MSL.
Tree 5985' from DER, 226' left of centerline, 1124' MSL.
Trees beginning 1 NM from DER, 1763' right of centerline, up to 102' AGL/1197' MSL.
Tree 1.1 NM from DER, 2248' right of centerline, 1216' MSL.
Tower, antenna beginning 1.6 NM from DER, 2795' left of centerline, up to 195' AGL/1352' MSL.
Rwy 10, terrain 102' from DER, 394' left of centerline, 974' MSL.
Trees, vehicles on roads beginning 203' from DER, 134' left of centerline, up to 100' AGL/1075' MSL.
Trees beginning 204' from DER, 168' right of centerline, up to 100' AGL/1072' MSL.
Trees, rig, vehicles on roads beginning 434' from DER, 168' right of centerline, up to 100' AGL/1078' MSL.
Trees, vehicles on roads beginning 663' from DER, 5' left of centerline, up to 100' AGL/1085' MSL.
Trees, vehicles on roads, utility pole beginning 664' from DER, 6' right of centerline, up to 100' AGL/1085' MSL.
Trees beginning 1123' from DER, 69' left of centerline, up to 100' AGL/1088' MSL.
Trees 1124' from DER, 165' right of centerline, 100' AGL/1088' MSL.
Trees beginning 1125' from DER, 106' right of centerline, up to 100' AGL/1091' MSL.
Trees beginning 1353' from DER, 138' left of centerline, up to 100' AGL/1095' MSL.
Trees 1355' from DER, 468' right of centerline, 100' AGL/1095' MSL.
Trees beginning 1356' from DER, 164' right of centerline, up to 100' AGL/1098' MSL.
Trees, building, utility pole beginning 1581' from DER, 101' left of centerline, up to 100' AGL/1108' MSL.
Trees beginning 1585' from DER, 10' right of centerline, up to 100' AGL/1104' MSL.
Trees, pole beginning 1811' from DER, 22' left of centerline, up to 100' AGL/1114' MSL.
Trees 1815' from DER, 466' right of centerline, 100' AGL/1111' MSL.
Trees, pole beginning 1816' from DER, 162' right of centerline, up to 100' AGL/1118' MSL.
Trees beginning 2041' from DER, 141' left of centerline, up to 100' AGL/1118' MSL.
Trees, building beginning 2046' from DER, 161' right of centerline, up to 100' AGL/1121' MSL.
Trees beginning 2271' from DER, 142' left of centerline, up to 100' AGL/1124' MSL.
Trees beginning 2275' from DER, 465' right of centerline, up to 100' AGL/1131' MSL.
Trees beginning 2277' from DER, 160' right of centerline, up to 100' AGL/1134' MSL.
Trees beginning 2501' from DER, 142' left of centerline, up to 100' AGL/1131' MSL.
Trees 2505' from DER, 464' right of centerline, 100' AGL/1141' MSL.
Trees 2506' from DER, 768' right of centerline, 100' AGL/1144' MSL.
Trees beginning 2507' from DER, 284' right of centerline, up to 100' AGL/1157' MSL.
Trees beginning 2698' from DER, 159' right of centerline, up to 1160' MSL.
Trees beginning 2732' from DER, 143' left of centerline, up to 100' AGL/1134' MSL.
Trees 2736' from DER, 767' right of centerline, 100' AGL/1170' MSL.
Trees, utility pole beginning 2737' from DER, 159' right of centerline, up to 100' AGL/1180' MSL.
Trees beginning 2961' from DER, 144' left of centerline, up to 100' AGL/1137' MSL.
Trees 2966' from DER, 766' right of centerline, 100' AGL/1183' MSL.
Trees beginning 2967' from DER, 158' right of centerline, up to 100' AGL/1193' MSL.
Trees beginning 3190' from DER, 145' left of centerline, up to 100' AGL/1150' MSL.
Trees 3196' from DER, 765' right of centerline, 100' AGL/1200' MSL.
Trees beginning 3197' from DER, 157' right of centerline, up to 100' AGL/1206' MSL.
Trees 3427' from DER, 1068' right of centerline, 100' AGL/1209' MSL.
Trees, utility poles beginning 3429' from DER, 154' right of centerline, up to 100' AGL/1213' MSL.
Trees 3650' from DER, 1057' left of centerline, 100' AGL/1157' MSL.
Trees beginning 3651' from DER, 147' left of centerline, up to 100' AGL/1160' MSL.
Trees beginning 3883' from DER, 147' left of centerline, up to 100' AGL/1163' MSL.
Trees beginning 4113' from DER, 148' left of centerline, up to 100' AGL/1167' MSL.
Trees 4342' from DER, 453' left of centerline, 100' AGL/1170' MSL.
Trees beginning 4343' from DER, 149' left of centerline, up to 100' AGL/1173' MSL.
Trees 4347' from DER, 1064' right of centerline, 100' AGL/1216' MSL.
Trees beginning 4349' from DER, 153' right of centerline, up to 100' AGL/1219' MSL.
Trees 4579' from DER, 1367' right of centerline, 100' AGL/1223' MSL.
Trees beginning 4580' from DER, 152' right of centerline, up to 100' AGL/1229' MSL.
Trees beginning 4797' from DER, 151' left of centerline, up to 100' AGL/1183' MSL.
Trees, utility poles, building beginning 4810' from DER, 6' right of centerline, up to 100' AGL/1232' MSL.
Trees, utility pole beginning 5027' from DER, 152' left of centerline, up to 100' AGL/1186' MSL.
Trees, buildings, utility pole beginning 5257' from DER, 152' left of centerline, up to 100' AGL/1193' MSL.
CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

WADSWORTH, OH (CON'T)

WADSWORTH MUNI (3G3) (CON'T)

Rwy 10 (CON'T), trees, utility pole beginning 5487' from DER, 116' left of centerline, up to 100' AGL/1196' MSL.
Trees, utility pole beginning 5716' from DER, 24' left of centerline, up to 100' AGL/1213' MSL.
Trees beginning 5946' from DER, 46' left of centerline, up to 100' AGL/1219' MSL.
Trees, building, utility pole beginning 1 NM from DER, 156' left of centerline, up to 100' AGL/1259' MSL.
Trees, utility poles beginning 1.1 NM from DER, 27' left of centerline, up to 100' AGL/1295' MSL.
Trees beginning 1.1 NM from DER, 107' right of centerline, up to 100' AGL/1239' MSL.
Trees, buildings, utility pole beginning 1.2 NM from DER, 50' left of centerline, up to 100' AGL/1301' MSL.
Trees beginning 1.3 NM from DER, 40' right of centerline, up to 100' AGL/1249' MSL.
Trees, poles, tank, buildings, terrain beginning 1.4 NM from DER, 27' left of centerline, up to 1313' MSL.
Trees beginning 1.4 NM from DER, 136' right of centerline, up to 100' AGL/1259' MSL.
Trees beginning 1.5 NM from DER, 10' right of centerline, up to 100' AGL/1282' MSL.
Trees beginning 1.8 NM from DER, 176' left of centerline, up to 100' AGL/1314' MSL.
Trees beginning 1.9 NM from DER, 177' left of centerline, up to 100' AGL/1350' MSL.
Trees beginning 1.9 NM from DER, 123' right of centerline, up to 1294' MSL.
Trees beginning 2 NM from DER, 122' right of centerline, up to 100' AGL/1305' MSL.
Trees beginning 2 NM from DER, 2306' left of centerline, up to 100' AGL/1364' MSL.
Trees beginning 2.1 NM from DER, 422' right of centerline, up to 100' AGL/1318' MSL.
Trees beginning 2.3 NM from DER, 114' right of centerline, up to 100' AGL/1350' MSL.
Trees beginning 2.3 NM from DER, 3225' left of centerline, up to 100' AGL/1367' MSL.
Trees, tower beginning 2.4 NM from DER, 2006' left of centerline, 416' AGL/1581' MSL.
Rwy 20, trees beginning 17' from DER, 216' left of centerline, up to 57' AGL/1026' MSL.
Vehicles on road 28' from DER, 320' right of centerline, 976' MSL.
Trees, vehicles on roads, fence, terrain beginning 37' from DER, 181' left of centerline, up to 1034' MSL.
Trees, vehicles on roads beginning 349' from DER, 3' left of centerline, up to 1067' MSL.
Vehicles on road 420' from DER, 102' right of centerline, 980' MSL.
Vehicles on roads beginning 423' from DER, 3' right of centerline, up to 981' MSL.
Trees, vehicles on roads beginning 707' from DER, 1' left of centerline, up to 1072' MSL.
Tree 1377' from DER, 44' right of centerline, 35' AGL/1003' MSL.
Tree 1521' from DER, 61' right of centerline, 38' AGL/1006' MSL.
Trees beginning 2741' from DER, 872' left of centerline, up to 74' AGL/1076' MSL.
Trees beginning 2900' from DER, 1' left of centerline, up to 86' AGL/1088' MSL.
Tree 3241' from DER, 16' right of centerline, 74' AGL/1048' MSL.
Tree 3411' from DER, 69' right of centerline, 86' AGL/1058' MSL.
Tree 3581' from DER, 1384' left of centerline, 1110' MSL.
Trees beginning 3687' from DER, 1165' left of centerline, up to 1130' MSL.
Trees beginning 3852' from DER, 993' left of centerline, up to 1148' MSL.
Trees beginning 3921' from DER, 15' left of centerline, up to 1151' MSL.
Trees beginning 4113' from DER, 1169' left of centerline, up to 1153' MSL.
Trees beginning 4352' from DER, 114' left of centerline, up to 1172' MSL.
Trees beginning 4605' from DER, 25' right of centerline, up to 96' AGL/1100' MSL.
Trees beginning 4934' from DER, 194' left of centerline, up to 1173' MSL.
Trees beginning 5065' from DER, 2' left of centerline, up to 1190' MSL.
Trees beginning 5271' from DER, 29' right of centerline, up to 1114' MSL.
Tree 1.2 NM from DER, 2423' left of centerline, 89' AGL/1152' MSL.
Rwy 28, silo 16' from DER, 476' left of centerline, 12' AGL/977' MSL.
Pole 32' from DER, 505' left of centerline, 22' AGL/987' MSL.
Building 41' from DER, 328' right of centerline, 27' AGL/991' MSL.
Tree 134' from DER, 187' left of centerline, 49' AGL/1011' MSL.
Tree 141' from DER, 218' left of centerline, 67' AGL/1028' MSL.
Trees beginning 169' from DER, 177' left of centerline, up to 100' AGL/1065' MSL.
Trees, building, utility poles, vehicles on road beginning 171' from DER, 122' right of centerline, up to 100' AGL/1065 ' MSL.
Trees beginning 762' from DER, 380' left of centerline, up to 1067' MSL.
Trees beginning 781' from DER, 159' left of centerline, up to 1070' MSL.
Trees beginning 1320' from DER, 181' left of centerline, up to 100' AGL/1072' MSL.
Trees beginning 1321' from DER, 121' right of centerline, up to 100' AGL/1068' MSL.
Trees beginning 1551' from DER, 119' right of centerline, up to 100' AGL/1072' MSL.
Trees beginning 1780' from DER, 183' left of centerline, up to 100' AGL/1075' MSL.
Trees beginning 2241' from DER, 115' right of centerline, up to 100' AGL/1075' MSL.
Trees beginning 2927' from DER, 187' left of centerline, up to 100' AGL/1081' MSL.
Trees beginning 3157' from DER, 187' left of centerline, up to 100' AGL/1101' MSL.
Trees 3386' from DER, 1403' left of centerline, 100' AGL/1111' MSL.
Trees beginning 3387' from DER, 188' left of centerline, up to 100' AGL/1114' MSL.
Trees beginning 3391' from DER, 115' right of centerline, up to 100' AGL/1085' MSL.
Trees beginning 3616' from DER, 189' left of centerline, up to 100' AGL/1134' MSL.
Trees beginning 3621' from DER, 114' right of centerline, up to 100' AGL/1108' MSL.
Trees beginning 3760' from DER, 167' left of centerline, up to 1137' MSL.
Trees beginning 3846' from DER, 117' left of centerline, up to 100' AGL/1154' MSL.
CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

WADSWORTH, OH (CON'T)

WADSWORTH MUNI (3G3) (CON'T)

Rwy 28 (CON'T), trees beginning 3851' from DER, 113' right of centerline, up to 100' AGL/1134' MSL.
Trees beginning 3968' from DER, 153' left of centerline, up to 1166' MSL.
Trees beginning 3997' from DER, 1050' left of centerline, up to 1167' MSL.
Trees beginning 4028' from DER, 112' right of centerline, up to 1177' MSL.
Tree 4062' from DER, 1288' left of centerline, 1176' MSL.
Trees beginning 4076' from DER, 26' left of centerline, up to 100' AGL/1186' MSL.
Trees beginning 4089' from DER, 199' right of centerline, up to 1183' MSL.
Trees beginning 4113' from DER, 179' right of centerline, up to 1192' MSL.
Trees beginning 4168' from DER, 233' left of centerline, up to 1194' MSL.
Tree 4179' from DER, 376' right of centerline, 1193' MSL.
Trees beginning 4211' from DER, 50' left of centerline, up to 1200' MSL.
Tree 4224' from DER, 403' right of centerline, 1196' MSL.
Trees beginning 4240' from DER, 112' right of centerline, up to 1207' MSL.
Trees beginning 4306' from DER, 41' left of centerline, up to 100' AGL/1209' MSL.
Trees beginning 4393' from DER, 912' left of centerline, up to 1215' MSL.
Trees, buildings beginning 4399' from DER, 38' right of centerline, up to 1213' MSL.
Trees beginning 4535' from DER, 130' left of centerline, up to 100' AGL/1219' MSL.
Trees 4765' from DER, 1711' left of centerline, 100' AGL/1223' MSL.
Trees beginning 4766' from DER, 496' left of centerline, up to 100' AGL/1226' MSL.
Trees beginning 4770' from DER, 37' left of centerline, up to 100' AGL/1229' MSL.
Trees beginning 4771' from DER, 60' right of centerline, up to 100' AGL/1229' MSL.
Trees 4999' from DER, 497' left of centerline, 100' AGL/1232' MSL.
Trees beginning 5000' from DER, 193' left of centerline, up to 100' AGL/1239' MSL.
Trees, utility poles beginning 5001' from DER, 27' right of centerline, up to 100' AGL/1246' MSL.
Trees, building, utility pole, vehicles on road beginning 5230' from DER, 17' left of centerline, up to 100' AGL/1242' MSL.
Trees, building beginning 5231' from DER, 30' right of centerline, up to 100' AGL/1255' MSL.
Trees, buildings, utility poles beginning 5460' from DER, 85' left of centerline, up to 100' AGL/1246' MSL.
Trees 5462' from DER, 412' right of centerline, 100' AGL/1259' MSL.
Trees 5463' from DER, 715' right of centerline, 100' AGL/1262' MSL.
Trees, terrain beginning 5464' from DER, 107' right of centerline, up to 100' AGL/1265' MSL.
Trees 5694' from DER, 1018' right of centerline, 100' AGL/1268' MSL.
Trees, rig, utility pole beginning 5695' from DER, 106' right of centerline, up to 100' AGL/1272' MSL.
Trees, terrain, vehicles on road, building beginning 5926' from DER, 25' right of centerline, up to 100' AGL/1275' MSL.
Trees beginning 1.3 NM from DER, 203' left of centerline, up to 100' AGL/1255' MSL.
Trees, buildings, silo beginning 1.4 NM from DER, 205' left of centerline, up to 100' AGL/1265' MSL.
Trees beginning 1.4 NM from DER, 96' right of centerline, up to 1287' MSL.
Trees, utility pole, silo beginning 1.5 NM from DER, 206' left of centerline, up to 100' AGL/1268' MSL.
Trees, utility pole, building beginning 1.5 NM from DER, 94' right of centerline, up to 100' AGL/1291' MSL.
Trees beginning 1.6 NM from DER, 90' right of centerline, up to 100' AGL/1295' MSL.
Trees beginning 1.8 NM from DER, 1303' right of centerline, up to 100' AGL/1298' MSL.
Trees 2.1 NM from DER, 3729' right of centerline, 100' AGL/1288' MSL.

29 OCT 2026 to 26 NOV 2026

WAPAKONETA, OH

NEIL ARMSTRONG (AXV)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 31JUL08 (08213) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 8, vehicle on road, 1' from DER, 403' right of centerline, 15' AGL/926' MSL.
Fence 70' from DER, 222' right of centerline, 6' AGL/919' MSL.
Fence 149' from DER, 270' left of centerline, 8' AGL/921' MSL.
Obstruction light on pole, 348' from DER, 239' left of centerline, 15' AGL/928' MSL.
Building, 614' from DER, 463' left of centerline, 15' AGL/929' MSL.
Trees beginning 2385' from DER, 51' left of centerline, up to 101' AGL/1014' MSL.
Trees beginning 2263' from DER, 268' right of centerline, up to 75' AGL/988' MSL.
Rwy 26, obstruction light on DME, 401' from DER, 268' right of centerline, 9' AGL/922' MSL.
Trees beginning 496' from DER, 51' right of centerline, up to 83' AGL/996' MSL.
Trees beginning 563' from DER, 120' left of centerline, up to 72' AGL/985' MSL.
Pole 620' from DER, 332' left of centerline, 25' AGL/938' MSL.
Stack, 3021' from DER, 577' left of centerline, 125' AGL/1035' MSL.
Tower, 3265' from DER, 729' right of centerline, 149' AGL/1050' MSL.

26190

WARSAW, IN

WARSAW MUNI (ASW)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3 30JAN20 (20030) (FAA)

TAKEOFF MINIMUMS:

Rwy 9, 300-1⅛ or std w/min climb of 266' per NM to 1100, or alternatively, with std takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 2000' prior to DER.

TAKEOFF OBSTACLE NOTES:

Rwy 9, fence beginning 148' from DER, 476' left of centerline, up to 5' AGL/856' MSL.
Vehicle on road beginning 181' from DER, 22' right of centerline, up to 865' MSL.
Vehicle on road 183' from DER, 264' left of centerline, 865' MSL.
Vehicle on road beginning 184' from DER, 404' left of centerline, up to 866' MSL.
Trees beginning 835' from DER, 447' right of centerline, up to 65' AGL/914' MSL.
Trees beginning 1258' from DER, 755' left of centerline, up to 50' AGL/888' MSL.
Tree 1283' from DER, 763' left of centerline, 52' AGL/890' MSL.
Trees beginning 1287' from DER, 524' left of centerline, up to 58' AGL/897' MSL.
Trees beginning 1367' from DER, 476' left of centerline, up to 61' AGL/898' MSL.
Trees beginning 1472' from DER, 72' right of centerline, up to 77' AGL/928' MSL.
Trees beginning 1529' from DER, 176' left of centerline, up to 66' AGL/908' MSL.
Trees beginning 1701' from DER, 824' right of centerline, up to 91' AGL/944' MSL.
Trees beginning 2231' from DER, 841' right of centerline, up to 99' AGL/949' MSL.
Tree 2497' from DER, 969' left of centerline, 69' AGL/913' MSL.
Transmission line 4888' from DER, 1104' left of centerline, 167' AGL/1012' MSL.
Transmission line 5638' from DER, 106' left of centerline, 173' AGL/1018' MSL.
Tower 5639' from DER, 106' left of centerline, 172' AGL/1020' MSL.
Catenary 5730' from DER, 3' right of centerline, 169' AGL/1014' MSL.
Rwy 18, terrain 6' from DER, 193' left of centerline, 837' MSL.
Poles beginning 712' from DER, 360' left of centerline, up to 47' AGL/880' MSL.
Poles, tree beginning 744' from DER, 150' right of centerline, up to 33' AGL/866' MSL.
Trees beginning 832' from DER, 572' left of centerline, up to 63' AGL/896' MSL.
Trees beginning 932' from DER, 17' left of centerline, up to 75' AGL/905' MSL.
Trees beginning 1041' from DER, 172' right of centerline, up to 40' AGL/870' MSL.
Trees beginning 1267' from DER, 115' right of centerline, up to 86' AGL/905' MSL.
Trees beginning 1846' from DER, 305' right of centerline, up to 103' AGL/917' MSL.
Rwy 27, tree 1341' from DER, 650' right of centerline, 41' AGL/872' MSL.
Pole 1715' from DER, 387' left of centerline, 60' AGL/883' MSL.
Pole 1717' from DER, 462' right of centerline, 57' AGL/884' MSL.
Rwy 36, building 199' from DER, 528' left of centerline, 15' AGL/849' MSL.
Pole 313' from DER, 537' left of centerline, 43' AGL/877' MSL.
Tree 366' from DER, 520' left of centerline, 59' AGL/893' MSL.
Trees, poles, vehicle on road beginning 448' from DER, 237' left of centerline, up to 77' AGL/910' MSL.
Pole, vehicle on road beginning 483' from DER, 5' right of centerline, up to 27' AGL/864' MSL.
Pole 524' from DER, 544' right of centerline, 29' AGL/866' MSL.
Tree 560' from DER, 507' right of centerline, 51' AGL/887' MSL.
Trees, buildings, pole beginning 568' from DER, 404' right of centerline, up to 56' AGL/891' MSL.
Trees beginning 1666' from DER, 643' right of centerline, up to 87' AGL/916' MSL.
Trees beginning 1766' from DER, 519' right of centerline, up to 91' AGL/919' MSL.
Trees beginning 1783' from DER, 357' left of centerline, up to 105' AGL/928' MSL.
Trees beginning 1952' from DER, 380' left of centerline, up to 108' AGL/929' MSL.
Trees beginning 2148' from DER, on centerline, up to 109' AGL/932' MSL.
Trees beginning 2740' from DER, 183' right of centerline, up to 103' AGL/925' MSL.
Trees beginning 2857' from DER, 165' right of centerline, up to 125' AGL/945' MSL.
Trees beginning 3244' from DER, 148' left of centerline, up to 106' AGL/934' MSL.
Trees beginning 3309' from DER, 11' left of centerline, up to 107' AGL/936' MSL.

WASHINGTON, IN

DAVIESS COUNTY (DCY)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 10AUG23 (23222) (FAA)

TAKEOFF MINIMUMS:

Rwys 9, 27, NA-Environmental.
Rwy 18, 300-2 or std w/min climb of 295'/NM to 700.

TAKEOFF OBSTACLE NOTES:

Rwy 18, vegetation beginning 7' from DER, 158' left of centerline, up to 5' AGL/471' MSL.
Vegetation beginning 20' from DER, 135' left of centerline, up to 7' AGL/472' MSL.
Terrain 34' from DER, 391' right of centerline, 468' MSL.
NAVAID, terrain beginning 39' from DER, 113' right of centerline, up to 2' AGL/469' MSL.
Tree, vegetation beginning 66' from DER, 95' left of centerline, up to 473' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

WASHINGTON, IN (CON'T)

DAVIESS COUNTY (DCY) (CON'T)

Rwy 18 (CON'T), vegetation 83' from DER, 99' left of centerline, 9' AGL/474' MSL.
Vehicles on road beginning 148' from DER, 511' right of centerline, up to 485' MSL.
Vehicles on road beginning 574' from DER, 496' right of centerline, up to 486' MSL.
Trees beginning 1037' from DER, 246' left of centerline, up to 526' MSL.
Tree 1526' from DER, 152' left of centerline, 542' MSL.
Tree 1957' from DER, 223' right of centerline, 538' MSL
Trees beginning 2629' from DER, 265' right of centerline, up to 575' MSL.
Silo 4155' from DER, 126' left of centerline, 110' AGL/611' MSL.
Silo, tanks, elevator beginning 4156' from DER, 17' left of centerline, up to 115' AGL/615' MSL.
Elevator 4221' from DER, 9' left of centerline, 121' AGL/621' MSL.
Tree 1.5 nm from DER, 2975' right of centerline, 710' MSL.
Rwy 36, poles beginning 651' from DER, 373' right of centerline, up to 482' MSL.
Tree 2749' from DER, 1110' left of centerline, 545' MSL.
Trees beginning 2813' from DER, 1113' left of centerline, up to 552' MSL.
Trees beginning 2926' from DER, 1148' left of centerline, up to 562' MSL.
Trees beginning 3051' from DER, 880' left of centerline, up to 563' MSL.
Trees beginning 3430' from DER, 1' left of centerline, up to 569' MSL.
Tree 3833' from DER, 17' right of centerline, 554' MSL.
Tree 4069' from DER, 75' right of centerline, 559' MSL.

WASHINGTON COURT HOUSE, OH

FAYETTE COUNTY (I23)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 20DEC07 (07354) (FAA)

TAKEOFF MINIMUMS:
Rwy 5, 300-1¾ or std w/min climb of 268' per NM to 1400.

TAKEOFF OBSTACLE NOTES:
Rwy 5, train on railroad tracks 384' from DER, 243' right of centerline, 23' AGL/997' MSL.
Terrain 81' from DER, 184' left of centerline, 0' AGL/978' MSL.
Silo 8848' from DER, 772' right of centerline, 238' AGL/1213' MSL.
Rwy 23, train on railroad tracks 509' from DER, 257' left of centerline, 23' AGL/1003' MSL.

WAUSEON, OH

FULTON COUNTY (USE)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1A 17AUG17 (17229) (FAA)

TAKEOFF MINIMUMS:
Rwys 18, 36, NA-Environmental.
Rwys 9, 27, 300-1.

TAKEOFF OBSTACLE NOTES:
Rwy 9, antenna, building beginning 1137' from DER, 637' left of centerline, up to 808' MSL.
Trees beginning 1309' from DER, 414' right of centerline, up to 840' MSL.
Trees beginning 1371' from DER, 562' right of centerline, up to 80' AGL/848' MSL.
Tree 1455' from DER, 543' right of centerline, 83' AGL/850' MSL.
Trees beginning 1569' from DER, 635' right of centerline, up to 90' AGL/854' MSL.
Trees beginning 2161' from DER, 4' left of centerline, up to 111' AGL/876' MSL.
Rwy 27, building 11' from DER, 460' left of centerline, 799' MSL.
Pole 26' from DER, 487' left of centerline, 808' MSL.
Antenna, building, road, tree, flagpole, tk, pole beginning 88' from DER, 47' left of centerline, up to 45' AGL/824' MSL.
Trees beginning 3976' from DER, 170' left of centerline, up to 889' MSL.

WAVERLY, OH

PIKE COUNTY (EOP)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 12JUN25 (25163) (FAA)

DEPARTURE PROCEDURE:
Rwy 7, climb on heading 068° to 1500 before turning left.

TAKEOFF OBSTACLE NOTES:
Rwy 7, fence, light pole beginning 1' from DER, 75' right of centerline, up to 668' MSL.
Light pole 39' from DER, 78' left of centerline, 663' MSL.
Fence 88' from DER, 462' left of centerline, 670' MSL.
Tree 95' from DER, 487' right of centerline, 24' AGL/679' MSL.
Fence 198' from DER, 462' left of centerline, 671' MSL.
Tree 237' from DER, 516' left of centerline, 701' MSL.
Tree 368' from DER, 506' left of centerline, 715' MSL.

CON'T

29 OCT 2026 to 26 NOV 2026
29 OCT 2026 to 26 NOV 2026

WAVERLY, OH (CON'T)

PIKE COUNTY (EOP) (CON'T)

Rwy 7 (CON'T), trees, buildings beginning 435' from DER, 286' right of centerline, up to 732' MSL.
Trees beginning 566' from DER, 332' left of centerline, up to 721' MSL.
Trees beginning 641' from DER, 568' left of centerline, up to 741' MSL.
Trees beginning 965' from DER, 382' left of centerline, up to 751' MSL.
Trees beginning 2400' from DER, 1048' right of centerline, up to 734' MSL.
Tree 2650' from DER, 1202' right of centerline, 736' MSL.
Tree 2923' from DER, 494' left of centerline, 752' MSL.
Rwy 25, light pole 39' from DER, 79' left of centerline, 662' MSL.
Light pole 40' from DER, 78' right of centerline, 662' MSL.
Antenna 56' from DER, 474' left of centerline, 699' MSL.
Trees, vehicles on road beginning 80' from DER, 372' right of centerline, up to 67' AGL/722' MSL.
Tree 150' from DER, 265' right of centerline, 80' AGL/737' MSL.
Light pole, antenna, fence, poles, vehicle on road, trees beginning 154' from DER, 97' left of centerline, up to 46' AGL/705' MSL.
Trees, vehicle on road, pole beginning 191' from DER, 1' right of centerline, up to 86' AGL/739' MSL.
Tree 930' from DER, 590' left of centerline, 710' MSL.
Trees beginning 989' from DER, 363' left of centerline, up to 711' MSL.
Trees beginning 1133' from DER, 319' left of centerline, up to 714' MSL.
Trees beginning 1317' from DER, 367' left of centerline, up to 728' MSL.
Trees beginning 1548' from DER, 202' left of centerline, up to 729' MSL.
Trees beginning 1670' from DER, 75' left of centerline, up to 734' MSL.
Trees beginning 1795' from DER, 233' left of centerline, up to 737' MSL.
Trees beginning 2201' from DER, 134' left of centerline, up to 746' MSL.
Trees beginning 2310' from DER, 210' left of centerline, up to 757' MSL.
Trees beginning 2582' from DER, 343' left of centerline, up to 758' MSL.
Trees beginning 2783' from DER, 498' left of centerline, up to 760' MSL.
Trees beginning 2859' from DER, 384' left of centerline, up to 766' MSL.
Trees beginning 2955' from DER, 475' left of centerline, up to 115' AGL/769' MSL.

WEST UNION, OH

ALEXANDER SALAMON (AMT)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 16MAY24 (25191) (FAA)

TAKEOFF MINIMUMS:
Rwy 5, 300-1½ or std w/min climb of 462'/NM to 1200.
Rwy 23, 300-2¼.

DEPARTURE PROCEDURE:
Rwy 23, climb on heading 229° to 1400 before turning right.

TAKEOFF OBSTACLE NOTES:
Rwy 5, trees beginning 120' from DER, 36' right of centerline, up to 100' AGL/996' MSL.
Trees beginning 166' from DER, 10' left of centerline, up to 100' AGL/999' MSL.
Tree 1741' from DER, 775' left of centerline, 100' AGL/1003' MSL.
Tree 1817' from DER, 156' right of centerline, 100' AGL/1003' MSL.
Tree 1863' from DER, 226' left of centerline, 100' AGL/1006' MSL.
Trees beginning 1909' from DER, 608' left of centerline, up to 100' AGL/1009' MSL.
Trees beginning 1940' from DER, 323' right of centerline, up to 100' AGL/1013' MSL.
Tree 2031' from DER, 58' left of centerline, 100' AGL/1013' MSL.
Trees beginning 2077' from DER, 441' left of centerline, up to 100' AGL/1019' MSL.
Tree 2108' from DER, 873' right of centerline, 100' AGL/1016' MSL.
Trees beginning 2154' from DER, 108' right of centerline, up to 100' AGL/1019' MSL.
Trees beginning 2245' from DER, 106' left of centerline, up to 100' AGL/1022' MSL.
Trees beginning 2322' from DER, 276' right of centerline, up to 100' AGL/1026' MSL.
Trees beginning 2459' from DER, 489' left of centerline, up to 100' AGL/1029' MSL.
Trees beginning 2536' from DER, 60' right of centerline, up to 100' AGL/1029' MSL.
Trees beginning 2628' from DER, 321' left of centerline, up to 100' AGL/1036' MSL.
Trees beginning 2750' from DER, 228' right of centerline, up to 100' AGL/1032' MSL.
Trees beginning 2796' from DER, 154' left of centerline, up to 100' AGL/1039' MSL.
Tree 2918' from DER, 395' right of centerline, 100' AGL/1052' MSL.
Trees beginning 2964' from DER, 13' right of centerline, up to 100' AGL/1055' MSL.
Trees beginning 3010' from DER, 34' left of centerline, up to 100' AGL/1055' MSL.
Trees beginning 3132' from DER, 132' right of centerline, up to 100' AGL/1059' MSL.
Trees beginning 1 NM from DER, 1015' left of centerline, up to 100' AGL/1068' MSL.
Trees beginning 1 NM from DER, 1064' right of centerline, up to 100' AGL/1081' MSL.
Trees beginning 1.1 NM from DER, 849' right of centerline, up to 100' AGL/1085' MSL.
Trees beginning 1.1 NM from DER, 2162' left of centerline, up to 100' AGL/1075' MSL.
CON'T

29 OCT 2026 to 26 NOV 2026
29 OCT 2026 to 26 NOV 2026

WEST UNION, OH (CON'T)

ALEXANDER SALAMON (AMT) (CON'T)

Rwy 23, trees beginning 7' from DER, 59' right of centerline, up to 100' AGL/993' MSL.
Trees beginning 98' from DER, 107' left of centerline, up to 100' AGL/990' MSL.
Trees beginning 481' from DER, 155' left of centerline, up to 100' AGL/993' MSL.
Tree 817' from DER, 12' right of centerline, 100' AGL/996' MSL.
Trees beginning 939' from DER, 179' right of centerline, up to 100' AGL/999' MSL.
Trees beginning 1031' from DER, 203' left of centerline, up to 100' AGL/996' MSL.
Trees beginning 1108' from DER, 346' right of centerline, up to 100' AGL/1003' MSL.
Trees beginning 1199' from DER, 35' left of centerline, up to 100' AGL/999' MSL.
Trees beginning 1322' from DER, 131' right of centerline, up to 100' AGL/1009' MSL.
Trees beginning 1490' from DER, 299' right of centerline, up to 100' AGL/1019' MSL.
Trees beginning 1582' from DER, 83' left of centerline, up to 100' AGL/1006' MSL.
Trees beginning 1658' from DER, 84' right of centerline, up to 100' AGL/1045' MSL.
Trees beginning 1796' from DER, 298' left of centerline, up to 100' AGL/1009' MSL.
Trees beginning 1872' from DER, 251' right of centerline, up to 100' AGL/1068' MSL.
Trees beginning 1964' from DER, 130' left of centerline, up to 100' AGL/1022' MSL.
Trees beginning 2041' from DER, 36' right of centerline, up to 100' AGL/1101' MSL.
Trees beginning 2178' from DER, 346' left of centerline, up to 100' AGL/1036' MSL.
Trees beginning 2209' from DER, 203' right of centerline, up to 100' AGL/1124' MSL.
Trees beginning 2346' from DER, 178' left of centerline, up to 100' AGL/1045' MSL.
Tree 2377' from DER, 1136' right of centerline, 100' AGL/1131' MSL.
Trees beginning 2423' from DER, 371' right of centerline, up to 100' AGL/1150' MSL.
Trees beginning 2515' from DER, 11' left of centerline, up to 100' AGL/1055' MSL.
Trees beginning 2591' from DER, 156' right of centerline, up to 100' AGL/1170' MSL.
Trees beginning 2759' from DER, 323' right of centerline, up to 100' AGL/1173' MSL.
Trees, transmission line beginning 2928' from DER, 13' right of centerline, up to 100' AGL/1180' MSL.
Trees beginning 4809' from DER, 297' left of centerline, up to 100' AGL/1059' MSL.
Trees beginning 4977' from DER, 9' left of centerline, up to 100' AGL/1068' MSL.
Trees beginning 1.7 NM from DER, 2002' right of centerline, up to 100' AGL/1167' MSL.

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

WILLARD, OH

WILLARD (8G1)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 13SEP18 (18256) (FAA)

DEPARTURE PROCEDURE:

Rwy 10, climb on heading 103° to 1400 before turning left.

TAKEOFF OBSTACLE NOTES:

Rwy 10, building 705' from DER, 149' left of centerline, 19' AGL/959' MSL.
Transmission line 783' from DER, 289' left of centerline, 39' AGL/980' MSL.
Pole 1900' from DER, 418' left of centerline, 32' AGL/985' MSL.
Pole 1965' from DER, 985' left of centerline, 32' AGL/986' MSL.
Rwy 28, building beginning 6' from DER, 159' right of centerline, up to 30' AGL/969' MSL.
Pole 78' from DER, 306' left of centerline, up to 30' AGL/969' MSL.
Pole 125' from DER, 326' right of centerline, up to 40' AGL/979' MSL.
Trees beginning 201' from DER, 279' right of centerline, up to 100' AGL/1039' MSL.
Trees beginning 406' from DER, 487' right of centerline, up to 100' AGL/1049' MSL.
Trees beginning 1239' from DER, 144' left of centerline, up to 100' AGL/1069' MSL.
Trees beginning 1300' from DER, 4' right of centerline, up to 100' AGL/1069' MSL.

WILLOUGHBY, OH

LAKE COUNTY EXEC (LNN)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 3B 26MAR20 (22083) (FAA)

DEPARTURE PROCEDURE:

Rwy 10, climb on heading 099° to 1600 before turning right.
Rwy 23, climb on heading 233° to 1400 before turning right.
Rwy 28, climb on heading 279° to 1400 before turning left.

TAKEOFF OBSTACLE NOTES:

Rwy 5, fence, tree beginning 3' from DER, 273' left of centerline, up to 13' AGL/633' MSL.
Terrain 40' from DER, 382' right of centerline, 625' MSL.
Tree, pole beginning 50' from DER, 343' right of centerline, up to 56' AGL/673' MSL.
Tree 403' from DER, 584' right of centerline, 62' AGL/679' MSL.
Trees beginning 416' from DER, 351' left of centerline, up to 24' AGL/640' MSL.
Tree, building beginning 428' from DER, 538' right of centerline, up to 62' AGL/680' MSL.
Tree, building, fence, electrical system beginning 455' from DER, 244' right of centerline, up to 703' MSL.
Trees beginning 522' from DER, 466' left of centerline, up to 660' MSL.
CON'T

WILLOUGHBY, OH (CON'T)

LAKE COUNTY EXEC (LNN) (CON'T)

Rwy 5 (CON'T), trees beginning 662' from DER, 587' left of centerline, up to 62' AGL/674' MSL.
Tree 802' from DER, 558' left of centerline, 76' AGL/688' MSL.
Trees beginning 811' from DER, 528' left of centerline, up to 101' AGL/714' MSL.
Trees beginning 1070' from DER, 15' left of centerline, up to 109' AGL/728' MSL.
Tree, electrical system beginning 1286' from DER, 168' right of centerline, up to 98' AGL/716' MSL.
Trees beginning 1994' from DER, 356' right of centerline, up to 101' AGL/720' MSL.
Tree, electrical system beginning 2034' from DER, 434' right of centerline, up to 725' MSL.
Tree, electrical system, pole, transmission line beginning 2120' from DER, 10' right of centerline, up to 116' AGL/734' MSL.
Trees beginning 2613' from DER, 31' left of centerline, up to 109' AGL/732' MSL.
Tree 3426' from DER, 525' right of centerline, 107' AGL/736' MSL.
Trees beginning 3427' from DER, 328' right of centerline, up to 119' AGL/737' MSL.
Trees beginning 3667' from DER, 29' right of centerline, up to 124' AGL/740' MSL.
Trees beginning 4179' from DER, 303' left of centerline, up to 737' MSL.
Rwy 10, fence 77' from DER, 478' right of centerline, 10' AGL/633' MSL.
Trees beginning 168' from DER, 353' right of centerline, up to 63' AGL/684' MSL.
Tree, building, pole beginning 348' from DER, 139' right of centerline, up to 76' AGL/698' MSL.
Pole, tree beginning 405' from DER, 142' left of centerline, up to 34' AGL/656' MSL.
Tree, building, electrical system, transmission line, pole, vertical point beginning 437' from DER, 3' right of centerline, up to 95' AGL/717' MSL.
Electrical system, vertical point, transmission line, pole, lighting beginning 607' from DER, 26' left of centerline, up to 55' AGL/677' MSL.
Electrical system, tree, pole beginning 694' from DER, 54' left of centerline, up to 60' AGL/682' MSL.
Tree, electrical system, building beginning 733' from DER, 66' left of centerline, up to 67' AGL/695' MSL.
Tree, electrical system beginning 773' from DER, 10' left of centerline, up to 78' AGL/701' MSL.
Tree, building beginning 850' from DER, 520' left of centerline, up to 86' AGL/709' MSL.
Tree, electrical system beginning 955' from DER, 78' left of centerline, up to 89' AGL/711' MSL.
Tree, electrical system beginning 1081' from DER, 142' right of centerline, up to 98' AGL/721' MSL.
Tree, electrical system beginning 1112' from DER, 83' left of centerline, up to 105' AGL/727' MSL.
Trees beginning 1226' from DER, 4' right of centerline, up to 730' MSL.
Trees beginning 1260' from DER, 1' right of centerline, up to 108' AGL/732' MSL.
Trees beginning 2218' from DER, 4' left of centerline, up to 112' AGL/733' MSL.
Trees beginning 2349' from DER, 85' right of centerline, up to 112' AGL/736' MSL.
Trees beginning 2428' from DER, 15' right of centerline, up to 116' AGL/742' MSL.
Trees beginning 3541' from DER, 187' left of centerline, up to 110' AGL/736' MSL.
Rwy 23, fence 4' from DER, 489' left of centerline, 8' AGL/633' MSL.
Tree, fence, electrical system, building beginning 94' from DER, 62' left of centerline, up to 687' MSL.
Building 195' from DER, 495' right of centerline, 29' AGL/652' MSL.
Building, fence, electrical system, pole beginning 200' from DER, 448' right of centerline, up to 49' AGL/672' MSL.
Tree 526' from DER, 591' right of centerline, 77' AGL/698' MSL.
Tree, transmission line, pole, electrical system beginning 529' from DER, 363' right of centerline, up to 79' AGL/701' MSL.
Tree, pole, transmission line, electrical system beginning 628' from DER, 166' right of centerline, up to 87' AGL/709' MSL.
Trees beginning 1582' from DER, 204' left of centerline, up to 78' AGL/701' MSL.
Trees beginning 1659' from DER, 119' left of centerline, up to 714' MSL.
Trees beginning 1971' from DER, 260' right of centerline, up to 722' MSL.
Trees beginning 1987' from DER, 22' right of centerline, up to 100' AGL/724' MSL.
Tree 3023' from DER, 52' left of centerline, 94' AGL/717' MSL.
Trees beginning 3037' from DER, 269' left of centerline, up to 111' AGL/721' MSL.
Trees beginning 3445' from DER, 327' right of centerline, up to 105' AGL/728' MSL.
Trees beginning 3792' from DER, 1078' right of centerline, up to 108' AGL/730' MSL.
Rwy 28, antenna 579' from DER, 325' right of centerline, 20' AGL/640' MSL.
Building 835' from DER, 209' left of centerline, 23' AGL/645' MSL.
Building 845' from DER, 561' left of centerline, 29' AGL/652' MSL.
Building, electrical system, pole beginning 876' from DER, 410' left of centerline, up to 49' AGL/672' MSL.
Electrical system 965' from DER, 470' right of centerline, 34' AGL/653' MSL.
Electrical system, transmission line, pole, building beginning 985' from DER, 338' right of centerline, up to 44' AGL/661' MSL.
Tree 1134' from DER, 436' left of centerline, 77' AGL/698' MSL.
Tree 1140' from DER, 188' right of centerline, 45' AGL/664' MSL.
Trees beginning 1141' from DER, 397' left of centerline, up to 706' MSL.
Trees beginning 1143' from DER, 541' right of centerline, up to 692' MSL.
Trees beginning 1186' from DER, 386' right of centerline, up to 74' AGL/694' MSL.
Trees beginning 1213' from DER, 8' left of centerline, up to 87' AGL/709' MSL.
Tree 1240' from DER, 378' right of centerline, 76' AGL/695' MSL.
Trees beginning 1278' from DER, 21' right of centerline, up to 700' MSL.
Trees beginning 1711' from DER, 21' right of centerline, up to 95' AGL/711' MSL.
Tree 2447' from DER, 207' left of centerline, 99' AGL/715' MSL.
Trees beginning 2467' from DER, 200' left of centerline, up to 102' AGL/723' MSL.
Trees beginning 2671' from DER, 172' left of centerline, up to 108' AGL/728' MSL.
CON'T

29 OCT 2026 to 26 NOV 2026

29 OCT 2026 to 26 NOV 2026

WILLOUGHBY, OH (CON'T)

LAKE COUNTY EXEC (LNN) (CON'T)

Rwy 28 (CON'T), tree 3022' from DER, 1211' left of centerline, 116' AGL/735' MSL.
Tree, antenna beginning 3105' from DER, 248' left of centerline, up to 123' AGL/743' MSL.

WILMINGTON, OH

CLINTON FLD (I66)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 05JUL07 (21224) (FAA)

TAKEOFF MINIMUMS:

Rwy 3, 300-1¼ or std w/min climb of 224' per NM to 1300', or alternatively, with std takeoff minimums and a normal 200'/NM climb gradient, takeoff must occur no later than 1700' prior to DER.

TAKEOFF OBSTACLE NOTES:

Rwy 3, multiple trees beginning 76' from DER, 76' right of centerline, up to 88' AGL/1137' MSL.
Multiple trees beginning 279' from DER, 140' left of centerline, up to 96' AGL/1105' MSL.
Water tank 1 NM from DER, 554' left of centerline, 176' AGL/1205' MSL.
Rwy 21, multiple trees beginning 187' from DER, 509' right of centerline, up to 87' AGL/1111' MSL.
Multiple trees beginning 243' from DER, 214' left of centerline, up to 77' AGL/1086' MSL.

WILMINGTON AIR PARK (ILN)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 17APR25 (25107) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 4L, tree 1032' from DER, 643' right of centerline, 1114' MSL.
Rwy 22R, fence 296' from DER, 552' right of centerline, 1063' MSL.

WINAMAC, IN

ARENS FLD (RWN)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG-A 11OCT18 (21224) (FAA)

TAKEOFF MINIMUMS:

Rwy 9, 300-1½ or std w/min climb of 225' per NM to 1000

TAKEOFF OBSTACLE NOTES:

Rwy 9, fence 195' from DER, 190' right of centerline, 5' AGL/712' MSL.
Pole, NAVAID and vehicle beginning 268' from DER, 21' left of centerline, up to 26' AGL/735' MSL.
Tree 356' from DER, 172' right of centerline, 723' MSL.
Pole 595' from DER, 409' right of centerline, 34' AGL/741' MSL.
Pole 729' from DER, 393' left of centerline, 31' AGL/740' MSL.
Poles beginning 736' from DER, 172' right of centerline, up to 37' AGL/745' MSL.
Tree 2466' from DER, 463' left of centerline, 782' MSL.
Tower 1 NM from DER, 24' left of centerline, 181' AGL/894' MSL.
Rwy 27, fence 6' from DER, 203' left of centerline, 2' AGL/707' MSL.
Tree 99' from DER, 190' left of centerline, 715' MSL.
Fence 108' from DER, 208' right of centerline, 3' AGL/709' MSL.
Tree 1660' from DER, 852' right of centerline, 757' MSL.

WINCHESTER, IN

RANDOLPH COUNTY (I22)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

ORIG 10MAR11 (11069) (FAA)

TAKEOFF OBSTACLE NOTES:

Rwy 8, power poles beginning 503' from DER, 433' right of centerline, up to 26' AGL/1155' MSL.
Trees 1013' from DER, 586' right of centerline, 38' AGL/1167' MSL.
Trees beginning 3523' from DER, 112' right of centerline, up to 101' AGL/1220' MSL.
Tree 1745' from DER, 718' left of centerline, 61' AGL/1180' MSL.
Rwy 26, trees and power pole beginning 389' from DER, 461' right of centerline, up to 59' AGL/1178' MSL.
Barn and silo beginning 590' from DER, 360' right of centerline, up to 32' AGL/1151' MSL.
Tree 479' from DER, 571' left of centerline, 23' AGL/ 1142' MSL.
Power poles, antenna, and barn beginning 913' from DER, 444' left of centerline, up to 34' AGL/ 1153' MSL.
Tree and antenna beginning 1023' from DER, 424' left of centerline, up to 43' AGL/1162' MSL.

26190

WOODSFIELD, OH

MONROE COUNTY (4G5)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 30MAY91 (91150) (FAA)

TAKEOFF MINIMUMS:

Rwy 25, 300-1.

WOOSTER, OH

WAYNE COUNTY (BJJ)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 2 25DEC25 (25359) (FAA)

TAKEOFF MINIMUMS:

Rwy 28, 300-1 or std w/min climb of 270'/NM to 1400.

TAKEOFF OBSTACLE NOTES:

Rwy 10, vehicle on road 11' from DER, 479' right of centerline, 1141' MSL.
Vehicles in parking lot beginning 61' from DER, 359' left of centerline, up to 1143' MSL.
Pole, vehicles on road beginning 126' from DER, 40' right of centerline, up to 34' AGL/1159' MSL.
Poles beginning 165' from DER, 226' left of centerline, up to 33' AGL/1157' MSL.
Pole, vehicles on road beginning 168' from DER, 1' left of centerline, up to 35' AGL/1158' MSL.
Rwy 28, tree, vegetation, vehicles on road beginning 24' from DER, 192' right of centerline, up to 16' AGL/1126' MSL.
Tree 1241' from DER, 814' left of centerline, 1177' MSL.
Tree 1336' from DER, 617' left of centerline, 1187' MSL.
Trees beginning 1346' from DER, 594' left of centerline, up to 67' AGL/1188' MSL.
Trees beginning 1496' from DER, 896' left of centerline, up to 79' AGL/1197' MSL.
Trees beginning 1653' from DER, 881' left of centerline, up to 82' AGL/1202' MSL.
Trees beginning 1854' from DER, 110' left of centerline, up to 100' AGL/1213' MSL.
Tree 2589' from DER, 286' right of centerline, 63' AGL/1186' MSL.
Trees beginning 2591' from DER, 223' right of centerline, up to 74' AGL/1198' MSL.
Trees beginning 2591' from DER, 101' left of centerline, up to 95' AGL/1214' MSL.
Trees beginning 2701' from DER, 9' right of centerline, up to 1199' MSL.
Tree 2725' from DER, 677' right of centerline, 76' AGL/1201' MSL.
Trees beginning 2730' from DER, 282' right of centerline, up to 85' AGL/1207' MSL.
Trees beginning 2786' from DER, 341' right of centerline, up to 83' AGL/1208' MSL.
Trees beginning 2928' from DER, 719' right of centerline, up to 87' AGL/1209' MSL.
Tree 3707' from DER, 1419' right of centerline, 80' AGL/1213' MSL.
Tree 3859' from DER, 1310' right of centerline, 75' AGL/1214' MSL.
Tree 3905' from DER, 896' left of centerline, 1218' MSL.
Tree 4034' from DER, 899' left of centerline, 88' AGL/1224' MSL.
Trees beginning 4239' from DER, 957' left of centerline, up to 1232' MSL.
Tree 4330' from DER, 1008' left of centerline, 1237' MSL.
Tree 4378' from DER, 1303' left of centerline, 1247' MSL.
Trees beginning 4383' from DER, 925' left of centerline, up to 113' AGL/1262' MSL.
Trees beginning 4515' from DER, 925' left of centerline, up to 114' AGL/1264' MSL.
Trees beginning 4775' from DER, 921' left of centerline, up to 111' AGL/1264' MSL.
Tree 5225' from DER, 1845' right of centerline, 100' AGL/1248' MSL.
Tree 5411' from DER, 1946' right of centerline, 103' AGL/1252' MSL.

WRIGHT-PATTERSON AFB (KFFO)

DAYTON, OH

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

22OCT09 (09295)

TAKEOFF MINIMUMS:

Rwy 5R, 200-1½*
Rwy 23R, 400-2¾**
Rwy 23L, 400-2¾***
* Or std w/min climb of 240ft/NM to 1100'.
** Or std w/min climb of 260ft/NM to 1300'.
*** Or std w/min climb of 210ft/NM to 1300'.
Rwy 5R, climb on track 050° until reaching 1100.

TAKEOFF OBSTACLE NOTES:

Rwy 23L: 43' AGL VORTAC, 850' from DER, 662' right of centerline.
Rwy 5L: up to 105' AGL tree line beginning 3000' from DER, 700' right of centerline to 5100' from DER, 1300' left of centerline.

YOUNGSTOWN, OH

YOUNGSTOWN ELSER METRO (4G4)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1A 05FEB15 (15036) (FAA)

TAKEOFF MINIMUMS:

Rwy 10, 300-1¾ or std w/min climb of 237' per NM to 1500.

Rwy 28, 300-2½ or std w/min climb of 463' per NM to 1300.

DEPARTURE PROCEDURE:

Rwy 10, climb heading 098° to 2000 before proceeding on course.

Rwy 28, climb heading 278° to 1700 before turning right.

TAKEOFF OBSTACLE NOTES:

Rwy 10, vehicle on road 200' from DER, on centerline, 15' AGL/1104' MSL.
Hangar and trees beginning 34' from DER, 203' right of centerline, up to 100' AGL/1189' MSL.
Trees and tower beginning 283' from DER, 322' left of centerline, up to 138' AGL/1332' MSL.
Rwy 28, trees on centerline, beginning 3380' from DER, up to 100' AGL/1209' MSL.
Trees beginning at DER, 222' right of centerline, up to 100' AGL/1119' MSL.
Trees beginning at DER, 191' left of centerline, up to 100' AGL/1119' MSL.

YOUNGSTOWN/WARREN, OH

YOUNGSTOWN/WARREN RGNL (YNG)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 4 26JUL90 (21336) (FAA)

TAKEOFF MINIMUMS:

Rwy 23, 300-1.

ZANESVILLE, OH

ZANESVILLE MUNI (ZZV)

TAKEOFF MINIMUMS AND (OBSTACLE) DEPARTURE PROCEDURES

AMDT 1 27JAN22 (22027) (FAA)

TAKEOFF MINIMUMS:

Rwy 16, 300-1¼ or std w/min climb of 215' per NM to 1200, or alternatively, with std takeoff minimums and a normal 200' per NM climb gradient, takeoff must occur no later than 1400' prior to DER.

TAKEOFF OBSTACLE NOTES:

Rwy 4, trees, lighting, NAVAID beginning 45' from DER, 115' right of centerline, up to 92' AGL/900' MSL.
Lighting, NAVAID beginning 51' from DER, 114' left of centerline, up to 3' AGL/873' MSL.
Fence 80' from DER, 506' left of centerline, 874' MSL.
Tree 534' from DER, 634' left of centerline, 907' MSL.
Rwy 16, tree, vegetation beginning 2' from DER, 66' right of centerline, up to 929' MSL.
Vegetation 105' from DER, 95' left of centerline, 7' AGL/899' MSL.
Tree 194' from DER, 386' right of centerline, 939' MSL.
Trees beginning 208' from DER, 61' right of centerline, up to 99' AGL/956' MSL.
Trees beginning 1280' from DER, 331' left of centerline, up to 934' MSL.
Trees beginning 1435' from DER, 62' right of centerline, up to 958' MSL.
Tree 1438' from DER, 528' left of centerline, 939' MSL.
Trees beginning 1465' from DER, 35' right of centerline, up to 962' MSL.
Trees beginning 1522' from DER, 28' left of centerline, up to 942' MSL.
Tree 1618' from DER, 446' left of centerline, 944' MSL.
Trees beginning 1730' from DER, 378' left of centerline, up to 945' MSL.
Trees beginning 1860' from DER, 58' right of centerline, up to 968' MSL.
Trees beginning 1955' from DER, 96' left of centerline, up to 74' AGL/947' MSL.
Trees beginning 1977' from DER, 5' right of centerline, up to 972' MSL.
Trees beginning 2099' from DER, 129' left of centerline, up to 62' AGL/948' MSL.
Trees beginning 2107' from DER, 8' left of centerline, up to 74' AGL/956' MSL.
Trees beginning 2127' from DER, 5' right of centerline, up to 980' MSL.
Trees beginning 2134' from DER, 46' left of centerline, up to 74' AGL/961' MSL.
Trees beginning 2241' from DER, 6' left of centerline, up to 75' AGL/971' MSL.
Trees beginning 2276' from DER, 17' left of centerline, up to 77' AGL/975' MSL.
Trees beginning 5615' from DER, 1532' right of centerline, up to 1041' MSL.
Tree 1 NM from DER, 615' right of centerline, 102' AGL/1065' MSL.
Rwy 22, vehicle on road, NAVAID, tree beginning 2' from DER, 114' right of centerline, up to 910' MSL.
Tree, NAVAID beginning 28' from DER, 114' left of centerline, up to 904' MSL.
Tree 105' from DER, 185' left of centerline, 25' AGL/917' MSL.
Trees beginning 305' from DER, 293' left of centerline, up to 975' MSL.
Trees beginning 419' from DER, 291' left of centerline, up to 984' MSL.
Tree 1285' from DER, 565' right of centerline, 932' MSL.
CON'T

29 OCT 2026 to 26 NOV 2026

ZANESVILLE, OH (CON'T)

ZANESVILLE MUNI (ZZV) (CON'T)

Rwy 34, trees, vegetation beginning 23' from DER, 54' left of centerline, up to 78' AGL/920' MSL.
Trees beginning 71' from DER, 212' right of centerline, up to 888' MSL.
Trees beginning 472' from DER, 268' right of centerline, up to 894' MSL.
Tree 1348' from DER, 189' right of centerline, 75' AGL/903' MSL.
Tree 1351' from DER, 211' right of centerline, 73' AGL/904' MSL.
Tree 1365' from DER, 216' right of centerline, 73' AGL/906' MSL.
Trees beginning 1365' from DER, 144' right of centerline, up to 84' AGL/912' MSL.
Trees beginning 1412' from DER, 112' right of centerline, up to 78' AGL/915' MSL.
Trees beginning 1437' from DER, 67' right of centerline, up to 77' AGL/920' MSL.
Tree 1521' from DER, 277' left of centerline, 101' AGL/921' MSL.
Tree 1525' from DER, 299' left of centerline, 100' AGL/923' MSL.
Trees beginning 1531' from DER, 4' right of centerline, up to 926' MSL.
Tree 1563' from DER, 386' left of centerline, 934' MSL.
Trees beginning 1567' from DER, 28' left of centerline, up to 936' MSL.
Trees beginning 1674' from DER, 34' right of centerline, up to 933' MSL.
Trees beginning 1680' from DER, 3' left of centerline, up to 937' MSL.
Trees beginning 1688' from DER, 15' right of centerline, up to 943' MSL.
Trees beginning 1805' from DER, 1' left of centerline, up to 941' MSL.
Trees, building beginning 1878' from DER, 6' right of centerline, up to 952' MSL.
Trees beginning 1880' from DER, 10' left of centerline, up to 946' MSL.
Trees beginning 1976' from DER, 16' left of centerline, up to 95' AGL/956' MSL.
Trees beginning 2322' from DER, 137' left of centerline, up to 962' MSL.
Trees beginning 2420' from DER, 119' left of centerline, up to 968' MSL.
Grain elevator, building beginning 2977' from DER, 73' right of centerline, up to 65' AGL/954' MSL.
Trees beginning 3046' from DER, 17' left of centerline, up to 975' MSL.
Tree 3581' from DER, 80' right of centerline, 75' AGL/957' MSL.
Tree 3592' from DER, 97' right of centerline, 78' AGL/959' MSL.
Trees beginning 3593' from DER, 7' right of centerline, up to 93' AGL/968' MSL.

29 OCT 2026 to 26 NOV 2026