

**BARNWELL RGNL** (BNL)(KBNL) 1 NW UTC-5(-4DT) N33°15.46' W81°23.29'

246 B NOTAM FILE AND

CHARLOTTE

H-9B, 12G, L-24I

IAP

**RWY 17-35:** H5119X100 (ASPH) S-69, D-99 PCN 26 F/B/X/T MIRL

**RWY 17:** ODALS. REIL. PAPI(P2L)—GA 3.0° TCH 52'. Tree. Rgt ttc.

**RWY 35:** PAPI(P2L)—GA 3.0° TCH 42'. Tree.

**RWY 05-23:** H4526X70 (ASPH-AFSC) S-12

**RWY 23:** Rgt ttc.

**SERVICE:** FUEL 100LL, JET A, MOGAS LGT ACTIVATE ODALS Rwy 17, MIRL Rwy 17-35—CTAF.

**AIRPORT REMARKS:** Attended 1400-2200Z±. Fuel 24 hr credit card svc avbl. Rwy 05-23 has multiple cracks and raveling producing FOD. Runway thresholds not marked. Emerg fuel shutoff located on rgt side of terminal bldg attached to electrical vault. Rwy 05-23 rstd use to acft weighing 12,500 lbs and less. Aerobatic activity west of Rwy 17-35. When active, incoming acft apch aprt from east.

**AIRPORT MANAGER:** 803-259-1090

**WEATHER DATA SOURCES:** AWOS-3 119.775 (803) 259-4536.

**COMMUNICATIONS:** CTAF/UNICOM 122.8

® **JAX CENTER APP/DEP CON** 132.925

**GCO** 121.725 (ZJX CLEARANCE DELIVERY)

**CLEARANCE DELIVERY PHONE:** For CD if una via GCO ctc Jacksonville ARTCC at 904-845-1592.

**RADIO AIDS TO NAVIGATION:** NOTAM FILE CAE.

**COLUMBIA (VH) (H) VORTAC** 114.7 CAE Chan 94 N33°51.44' W81°03.23' 207° 39.6 NM to fld. 404/2W.

VOR unusable:

000°-073° byd 35 NM blo 6,000'

200°-234° byd 12 NM blo 3,000'

235°-245° byd 12 NM blo 6,000'

246°-289° byd 12 NM blo 3,000'

290°-305° byd 12 NM blo 2,400'

306°-344° byd 30 NM

345°-359° byd 10 NM blo 5,000'

