

BARNWELL RGNL (BNL)(KBNL) 1 NW UTC-5(-4DT) N33°15.46' W81°23.29'

246 B NOTAM FILE AND

RWY 17-35: H5119X100 (ASPH) S-69, D-99 PCN 26 F/B/X/T MIRL

RWY 17: ODALS. REIL. PAPI(P2L)—GA 3.0° TCH 52'. Tree. Rgt ttc.

RWY 35: PAPI(P2L)—GA 3.0° TCH 42'. Tree.

RWY 05-23: H4526X70 (ASPH-AFSC) S-12

RWY 23: Rgt ttc.

SERVICE: FUEL 100LL, JET A, MOGAS LGT ACTIVATE ODALS Rwy 17, MIRL Rwy 17-35—CTAF.

AIRPORT REMARKS: Attended 1400-2200Z. Fuel 24 hr credit card svc avbl.

Rwy 05-23 has multiple cracks and raveling producing FOD. Runway thresholds not marked. Emerg fuel shutoff located on rgt side of terminal bldg attached to electrical vault. Rwy 05-23 rstd use to acft weighing 12,500 lbs and less. Aerobatic activity west of Rwy 17-35.

When active, incoming acft apch arpt from east.

AIRPORT MANAGER: 803-259-1090

WEATHER DATA SOURCES: AWOS-3PT 119.775 (803) 259-4536.

COMMUNICATIONS: CTAF/UNICOM 122.8

® **JACKSONVILLE CENTER APP/DEP CON** 132.925

GCO 121.725 (ZJX CLEARANCE DELIVERY)

CLEARANCE DELIVERY PHONE: For CD if una via GCO ctc Jacksonville ARTCC at 904-845-1592.

RADIO AIDS TO NAVIGATION: NOTAM FILE CAE.

COLUMBIA (VH) (H) VORTAC 114.7 CAE Chan 94 N33°51.44' W81°03.23' 207° 39.6 NM to fld. 404/2W.

VOR unusable:

000°-073° byd 35 NM blo 6,000'

200°-234° byd 12 NM blo 3,000'

235°-245° byd 12 NM blo 6,000'

246°-289° byd 12 NM blo 3,000'

290°-305° byd 12 NM blo 2,400'

306°-344° byd 30 NM

345°-359° byd 10 NM blo 5,000'

CHARLOTTE

H-9B, 12G, L-24I

IAP

