

INDEPENDENCE (207) 1 N UTC-8(-7DT) N36°48.98' W118°12.30'
 3908 TPA-4708(800) NOTAM FILE RAL
RWY 14-32: H3533X60 (ASPH) S-20 MIRL
RWY 14: Fence.
RWY 32: Trees. Rgt tfc.
RWY 05-23: 1498X30 (DIRT) 1.9% up SW
RWY 05: Road.
RWY 23: Fence.

SAN FRANCISCO
 L-9A

SERVICE: LGT ACTIVATE MIRL Rwy 14-32-CTAF.

AIRPORT REMARKS: Unattended. Rwy 05-23 clsd for public use. Rwy 05-23 unsafe for acft. Rwy 05-23 rstd can be used only during extreme crosswind conditions. Tfc pat indicators for Rwy 14-32 only. Rwy 14-32 extsv cracks on the north end of the rwy. Rwy 05-23 marked with an R on each end, no numbers or centerline markings. Rwy 05-23 undulating uneven dirt sfc. Brush in sporadic locations on rwy. Rwy 05-23 sfc uneven, rough, undulating with extsv brush. Unsafe for acft use.

AIRPORT MANAGER: 760-872-2971

COMMUNICATIONS: CTAF 122.9

CLEARANCE DELIVERY PHONE: For CD ctc Joshua Apch at 661-277-3843.

RADIO AIDS TO NAVIGATION: NOTAM FILE BIH.

BISHOP (VL) (L) VORW/DME 113.35 BIH Chan 80(Y) N37°22.62' W118°21.99' 152° 34.5 NM to fld.
 4117/15E.

VOR unusable:

136°-143° byd 40 NM
 157°-164° byd 40 NM
 165°-285° byd 12 NM
 286°-304° byd 40 NM
 305°-315° byd 35 NM
 316°-342° byd 40 NM
 340°-135° byd 12 NM

DME unusable:

165°-285° byd 12 NM
 305°-315° byd 35 NM
 340°-135° byd 12 NM

INYOKERN (IYK)(KIYK) 1 NW UTC-8(-7DT) N35°39.52' W117°49.77'
 2457 B NOTAM FILE IYK

LOS ANGELES
 H-41, L-7C
 IAP

RWY 15-33: H7100X75 (ASPH) S-24 PCN 7 F/C/Y/U MIRL
 0.4% up NW
RWY 15: PAPI(P2L)-GA 3.0° TCH 40'.
RWY 33: PAPI(P2L)-GA 3.3° TCH 40'.
RWY 02-20: H6275X75 (ASPH) S-30, D-50, 2D-80 PCN 6 F/C/X/U
 MIRL 0.4% up S
RWY 02: PAPI(P2L)-GA 3.3° TCH 40'.
RWY 20: VASI(V4L)-GA 3.0° TCH 35'. Thld dsplcd 320'. Rgt tfc.
RWY 10-28: H4150X75 (ASPH) S-24 PCN 7 F/C/Y/U MIRL
 1.0% up W
RWY 28: Thld dsplcd 103'.

SERVICE: S2 FUEL 100LL, JET A LGT ACTVT VASI Rwy 20; MIRL Rwy 02-20, Rwy 10-28, Rwy 15-33-CTAF. PAPI Rwy 02, Rwy 15 and Rwy 33 opr consly.

AIRPORT REMARKS: Attended Mon-Fri 1500-0100Z†, Frequent glider ops on weekends. After 0000Z† callout fee for svc call 760-382-3383. Rwy 10-28 condition poor but stable. Ptns of rwy ctrlrn marking obscd by crack filler. Rwy 15-33 surface: pavement experiencing longl and lateral block cracking on ptns of rwy.

AIRPORT MANAGER: 760-377-5844

COMMUNICATIONS: CTAF/AUNICOM 122.8

JOSHUA APP/DEP CON 133.65

CLEARANCE DELIVERY PHONE: For CD ctc Los Angeles ARTCC at 661-575-2079.

RADIO AIDS TO NAVIGATION: NOTAM FILE EDW.

EDWARDS (T) (T) VORTACW 116.4 EDW Chan 111 N34°58.94' W117°43.96' 341° 40.8 NM to fld. 2378/12E.

TACAN AZIMUTH unusable:

098°-158° byd 19 NM blo 7,900'

DME unusable:

107°-158° byd 19 NM

VOR unusable:

098°-158° byd 19 NM blo 7,900'

COMM/NAV/WEATHER REMARKS: Automated UNICOM-3 clicks for arpt advisory and wx or dial 617-262-3825, 4 clicks for radio check. Monitor 122.8 in tfc pat.

