

LINDEN (LDJ)(KLDJ) 1 SE UTC-5(-4DT) N40°37.05' W74°14.68'

22 B TPA—See Remarks NOTAM FILE MIV

RWY 09-27: H4140X100 (ASPH) S-31.5, D-42 MIRL

RWY 09: REIL. VASI(V2R)—GA 3.8° TCH 60'. Thld dsplcd 462'. Pole.

RWY 27: REIL. VASI(V2L)—GA 3.5° TCH 40'. Thld dsplcd 541'. Antenna.

SERVICE: S2 **FUEL** 100LL, JET A **LGT** ACTVT MIRL Rwy 09-27; VASI Rwy 09 and 27; and REIL Rwys 09 and 27—CTAF. Rwy 09 VASI unusbl byd 6 degs right and left of cntrln. Rwy 27 VASI unusbl byd 2 degs right of cntrln.

NOISE: Noise abatement procedures in effect.

AIRPORT REMARKS: Attended Oct-Apr 1330-2300Z†, May-Sep 1200-0130Z†. Deer and birds on and invof arpt. Touch and go ldrs for base assigned acft, all others ctc arpt manager 908-862-8800 for PPR. TPA—800' MSL, Rwy 09 enter tcf pat upwind, entries other rwys standard. Departing Rwy 27 depart straight out to 800'. Rwy 09 VASI is baffled to cut off the lgt beam at 6° each side of rwy centerline extended, total usable width is 12°. Rwy 09-27 rwy shoulder markings nstd. Ldg fee.

AIRPORT MANAGER: 908-862-5557

WEATHER DATA SOURCES: AWOS-3 124.025 (908) 862-7383.

COMMUNICATIONS: CTAF/UNICOM 123.0

Ⓡ **NEWARK APP CON** 128.55

CLNC DEL 127.25

Ⓡ **NEWARK DEP CON** 119.2

CLEARANCE DELIVERY PHONE: For CD ctc Newark twr on 127.25 or ctc Newark Apch at 800-645-3206.

RADIO AIDS TO NAVIGATION: NOTAM FILE JFK.

CANARSIE (T) (T) VOR/DME 112.3 CRI Chan 70 N40°36.75' W73°53.67' 282° 16.0 NM to fld. 4/11W.

**NEW YORK
COPTER
L-33A, 34H
IAP**

LITTLE FERRY SPB (2N7) 1 E UTC-5(-4DT) N40°51.01' W74°01.98'

00 TPA—500(500) NOTAM FILE MIV

WATERWAY 01W-19W: 5500X150 (WATER)

WATERWAY 01W: Tower.

WATERWAY 19W: Bridge. Rgt tfc.

SEAPLANE REMARKS: Unattended. Dalgt use only. Ldg area usbl but dckg area and lnd side aces unsafe. Do not use dckg area til reinspected.

AIRPORT MANAGER: 201-264-6728

COMMUNICATIONS: CTAF/UNICOM 122.8

CLEARANCE DELIVERY PHONE: For CD ctc New York Apch at 800-645-3206.

**NEW YORK
COPTER**

LUMBERTON

FLYING W (N14) 1 SW UTC-5(-4DT) N39°56.06' W74°48.43'

49 B NOTAM FILE MIV

RWY 01-19: H3496X75 (ASPH) MIRL 0.4% up N

RWY 01: REIL. PAPI(P2L)—GA 3.5° TCH 26'. Trees. Rgt tfc.

RWY 19: REIL. PAPI(P2L)—GA 3.2° TCH 22'.

SERVICE: S2 **FUEL** 100LL, JET A **LGT** ACTIVATE MIRL Rwy 01-19 PAPI and REIL Rwys 01 and 19, and twy lghts—CTAF. Rwy 01-19 REILS inop.

AIRPORT REMARKS: Attended Apr-Oct 1200-0200Z†, Nov-Mar 1200-0000Z†. Deer & birds on & invof arpt. East-west ravine crosses extended centerline Rwy 01 100' from thld. Deep retention pond 23' west of parallel twy centerline north of ops building.

AIRPORT MANAGER: 609-267-7673

COMMUNICATIONS: CTAF/UNICOM 122.8

Ⓡ **MC GUIRE APP/DEP CON** 126.475

CLEARANCE DELIVERY PHONE: For CD ctc Mc Guire Apch at 609-754-2767.

RADIO AIDS TO NAVIGATION: NOTAM FILE MIV.

ROBBINSVILLE (H) (H) VORTAC 113.8 RBV Chan 85 N40°12.14' W74°29.70' 232° 21.6 NM to fld. 248/10W.

TACAN AZIMUTH unusable:

105°-115° byd 30 NM

DME unusable:

075°-115° byd 25 NM

130°-160° byd 30 NM blo 4,000'

**WASHINGTON
L-34G, A
IAP**

